

Attention:
Telephone Number :
Fax Number :
Vendor Number : 500000

Quotation Deadline Date : 06.08.2013
Quotation Deadline Time : 16:00

REQUEST for QUOTATION
Transnet Capital Projects
RFQ Number / Date
6000168696 / 26.07.2013
Contact Person / Telephone
Yandiswa Oldjohn / 021 940 1886
Return to VAX Number/EMAIL
0218100000 / TCFendersCapeTown@Transnet.net

Registration Number: 1990/000900/06
Vat Number : 4720103177

REQUEST FOR QUOTATION

Item	Material	Description	RFQ Qty	UoM	Required Del date	Confirm Del date	Unit Price Excl	Total Price Excl
100010		Supply & Installation o	1	Ac	12.08.2013			

Supply & Installation of 6 x 5m wide spike boom Units for Entry & Exit points & connection of Spike boom units to the Vehicle / Personal Access Control System- as per attached Bill of Quantities

REQUESTER AND DELIVERY ADDRESS:

Martin Scott- Transnet Freight Rail

Compulsory Site Clarification Meeting: 1 August 2013 at 12h00. Suppliers to meet at 85 Burman Road, Deal Party, Port Elizabeth

Contact Martin Scott on 083-557-1654

If you are unable to quote for this enquiry, please submit a NO QUOTE, with a short reason, if possible, for not being able to quote.

Otherwise we look forward to receive your quote by the date and time stated





Registration Number: 1990/000900/06
 Vat Number : 4720103177

REQUEST for QUOTATION
 Transnet Capital Projects
 RFQ Number / Date
 6000168696 / 26.07.2013
Contact Person / Telephone
 Yandiswa Oldjohn / 021 940 1886
Return to VAX Number/EMAIL
 0218100000 / TCPlendersCapetown@Transnet.net

REQUEST FOR QUOTATION

Transnet SOC Limited
 T/A Transnet Capital Projects
 TRANSNET FREIGHT RAIL - RME
 TFR RFQ BOARD-RME
 PROCUREMENT DEPARTMENT
 PORT ELIZABETH
 6001

Attention:
 Telephone Number :
 Fax Number :
 Vendor Number : 500000

Quotation Deadline Date : 06.08.2013
Quotation Deadline Time : 16:00

Item	Material	Description	RFQ Qty	UoM	Required Del date	Confirm Del date	Unit Price Excl	Total Price Excl
------	----------	-------------	---------	-----	-------------------	------------------	-----------------	------------------

The item covers the following services:

Delivery Address
 TRANSNET FREIGHT RAIL - RME
 85 Burman Road, Deal Party
 PORT ELIZABETH
 6001

This RFQ is subject to the following conditions:

1. Prices/ : The prices/quoted in SA currency and is excluding of V.A.T

2. Delivery : The prices/quoted should include delivery cost to the delivery address stated on the RFQ

3. Returnables : A valid tax clearance certificate and BBBEE certificate from a SANAS accredited verification agency attached to quotation for all quotes above R30 000.

Please note that only the official Transnet RFQ will be accepted and all other correspondence to be attached to the original

4. Safety : To confirm to Transnet Capital Projects Health & Safety plan and specification; HAS-std-0001, copy available on request.

5. Confirmation: To confirm your participation in this tender process please sign and return this document as immediate effect prior to the quotation deadline.

6. Negotiations: The Employer may elect to negotiate the final terms of the contract/order with the preferred tenderer in accordance with Clauses F.2.17 and F.3.13

of the CIDB Standard Conditions of Tender. A copy of which is available upon request.

Signature _____

Date _____

MAIN ENTRANCE ACCESS CONTROL

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
A. FRONT END HARDWARE & SOFTWARE					
1	17 Tower PC with 1Tb HDD, 4Mb Ram, DVD Writer, 23" LED Screen, Windows 7 Pro. (To be used as the Server)	ea	1		
2	15 Tower PC with 1Tb HDD, 4Mb Ram, DVD Writer, 23" LED Screen, Windows 7 Pro. (Work Station - Located in Guard House)	ea	1		
3	Data Switch	ea	1		
4	Network cables	lot	1		
5	IXP400i Controller with integrated PSU	ea	1		
6	Impronet Engine - USB Firebird SQL Client/Server Database	ea	1		
7	Impronet Access (125KHz) - USB Firebird SQL Client/Server Database	ea	1		
8	1Kva Line Interactive UPS	ea	2		
9	Software installation and setup	lot	1		
B. FIELD HARDWARE					
TRUCK / TENANT ENTRANCE - SPIKE BOOMS					
10	Improx ITRT with Ethernet	ea	6		
11	Long Range AVI Reader with identification up to 10m	ea	6		
12	Pole Mounting Kit	ea	6		
13	Squelch Upgrade Kit	ea	6		
14	Power supply, 12vdc 3 amps	ea	6		
15	Battery 12vdc 7 A/H	ea	6		
16	Installation and setup	lot	1		
C. FIELD HARDWARE					
TURNSTILE CONTROL					
17	Improx ITRT with Ethernet	ea	1		
18	MHA - Metal Non-Keypad Antenna Reader for employees using standard tags	ea	2		
19	Power supply, 12vdc 3 amps	ea	1		
20	Battery 12vdc 7 A/H	ea	1		
21	Installation and setup	lot	1		
D. TAGS					
VECHILE TAGS					
22	Window Button Tag - Long Range Single ID Tag, inc Industrial Suction Cup for Windshield	ea	200		
23	Standard Teardrop Tag	ea	200		
E. INSTALLATION					
24	Trenching	m	80		
25	Post 80mm dia x 2m high galvanised	ea	6		
26	Concrete works	lot	1		
27	Conduit PVC	lot	1		
28	Training	lot	1		
29	Surfix Power Cable	m	250		
30	4pr Mylar Screen cable	m	400		
TOTAL (EXCL. VAT)					

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
A	SPIKE BOOM BARRIER				
	5m TALON BARRIER (recessed for concrete ramping) with 5m barrier arm	ea	6		
	<ul style="list-style-type: none"> • 2 x 100% duty geared torque motor • Microprocessor control modules - combined logic and loop detector • Heavy -Duty 1.6mm 3CR12 stainless steel cabinet • Lockable access door and top cover • Cabinet UV resistant polyester exterior powder coated - white with blue cover • Hi visibility, powder coated aluminium barrier arm with red reflective striping - round pole • Tye Talon housing in hot dip galvanised mild steel • Tye Talon in KalGard primer and UV resistant polyester exterior powder coat • XtalLife Triple Buffered Mechanism - delivers consistent & long lasting operation • Harmonic-motion lifting and lowering - eliminates mechanical stress-damage 				
	Traffic robots	ea	6		
	<ul style="list-style-type: none"> • Fitted to the cabinet of the vehicle barrier 				
B	FULL HEIGHT 4-ARM TURNSTILE				
	TRIUMPH 4 FULL HEIGHT, 4 ARM TURNSTILE	ea	1		
	<ul style="list-style-type: none"> • Ultra heavy duty • No routine maintenance or lubrication • Bi-directional, electrical locking • Complete with control panel for power and data connections • FIVE -YEAR GUARENTEE on locking mechanism and base bearing • Finish: Hot-dip galvanised 				
C	Card Reader Mounting Brackets for Turnstile	ea	2		
D	Delivery by a registered road transport contractor (JHB to PE)	lot	1		
E	Installation	lot	1		
TOTAL (EXCL. VAT)					

"PRELIMINARY"