

ANNEXURE B

TENDER PRICE LIST PER ITEM FOR FENCING

ASSET DESCRIPTION: SECURITY FENCE

CITY / TOWN: SANDHILLS

TENDER NO: BLE/ 51894

ASSET NO: 07HFG01C

WORK DESCRIPTION: ERECT SECURITY FENCE 1082M LONG X 1,80M HIGH

Measurements and or quantities do not include off cuts or waste all measurements of material is measure as nett fixed. Contractor to add his own % for off cuts and waste.

The contractor is responsible to check all the measurements and quantities as stated before ordering any material. The measurement and quantities are only for tender purposes.

Value Added Tax (VAT) shall be excluded in the schedule of rates and prices.

To be supplied by the Contractor: The Contractor shall provide all labour, material, transport, consumable stores, plant, equipment, tools, services, materials and ingredients of every description required for the carrying out and completion of the WORK as per the attached worklist and specification and as may be ordered by the Project Manager.

GENERAL: All normal cleaning, preparation include sanding and wash of items to be painted as specified by the paint manufacturer is included in all the paint items. All scaffolding and use of ladders as necessary is part of all the items. All work shall be done according to the attached specifications. Unless otherwise specified all materials must comply with SANS specifications.

Where no applicable SANS Specification exists the materials must be approved by the Transnet Freight Rail project manager.

All material shall be fitted, install or applied as specified by the manufacture.

The contractor shall be liable for any damages cause by him or his staff to any Transnet Freight Rail property or equipment.

SAFETY: The contractor shall comply with the Occupational Health Safety Act, 1993 (Act 85 of 1993).

Page 1 of 3

SUB TOTAL PAGE 1

TENDER NO: BLE/ 51894

ASSET NO: 07HFG01C

ITEM NO	FAULT DESCRIPTION	ITEM TOTAL	MEASURE UNIT	UNIT RATE	ITEM AMOUNT
EXCAVATIONS/BACKFILL					
835	Excavations of foundations for Posts;Stays and Intermediat Posts 0,45m x0,45m x0,60m total 378 foundations (use pick and space)	46	M^3	<input type="text"/>	<input type="text"/>
MASS CONCRETE/REINFORCING					
844	Hand mix concrete on site where a small quantity is required. Concrete shall be mixed on mixing board or hard surface. cast concrete in foundations and compact. concrete shall be at least 20mpa. all work and material to comply with attached specification	46	M^3	<input type="text"/>	<input type="text"/>
FENCING					
862	Cut all vegetation to 50mm above ground level, both sides of fence 1m wide (in total 2.0m wide) see attached specification	2164	M^2	<input type="text"/>	<input type="text"/>
863	Replace straining wire Ø 4mm diameter thick for fence up to 1,80m high above ground	540	KG	<input type="text"/>	<input type="text"/>

Respondent's signature: _____

Date: ____ / ____ / ____

--

TENDER NO: BLE/ 51894

ASSET NO: 07HFG01C

ITEM NO	FAULT DISCRPTION	ITEM TOTAL	MEASURE UNIT	UNIT RATE	ITEM AMOUNT
864	Binding wire Ø 2mm to secure and connect all tipe of wire fencing posts and razor wire in position except where the wire cross the timber posts.	60	KG		
866	Replace Tanalith Timber Corner and Straining Posts Ø100/119mm x 2.4m long. Height 1,80m high from ground level.	24	EA		
867	Replace Tanalith Timber Gate posts Ø120/139mm x 2,40m long and 1,80 above ground level	2	EA		
868	Replace Tanalith Timber Intermediat posts Ø 80/90mm x 2,40m long and 1,80 above ground level	308	EA		
869	Replace Tanalith Timber Stay posts Ø 80/90mm x 2,40m long and 1,80 above ground level	50	EA		
871	Remove 1.2m stock fence complete, include all poles and droppers	170	M		
875	Replace flat wrap razor coil fence Ø 50m x 1.8m high.The cover of rolls not more than 13m and tie every 300mm and with U staples 400mm long where crossing timber posts	330	EA		
876	Erect flat wrap razor coil fence 1,2m high. complete, item include planting of all corner, straining, intermediate posts and stays as per attached specification	2	JOB		
888	Replace double leaf gate 6,0m wide x 1,80m hige and cover with razor wire and one third above gates end tied with Ø 2mm binding wire as per specification. Gates NOT COVER WITH DIAMOND MESH	1	EA		

"PREVIEW COPY ONLY"

Respondent's signature: _____

Date: ____ / ____ / ____

TENDER NO: BLE/ 51894

ASSET NO: 07HFG01C

ITEM NO	FAULT DISCRPTION	ITEM TOTAL	MEASURE UNIT	UNIT RATE	ITEM AMOUNT
---------	------------------	------------	--------------	-----------	-------------

PRELIMINARY AND GENERAL

P and G shall include all cost not directly relate to a specific item on the schedule of prices and rates. All items not specifically mentioned in the Schedule of Rates and prices and form part of contractor's requirements such as cost of stationery, as well as establishment of workers on site and removal of site establishment, it will also include the handing over of the site to the contractor and the handing back of the site after completion of work .

P + G

RISK AND SAFETY

RISK ASSESSMENTAND SAFETY INDUCTION

Cost for the risk assessment must include a full identification of the risks before the work starts and the necessary equipment, appropriate precautions and systems of work must be provided and Implemented.

TOTAL

Cost for the risk assessment and safety include complete compliance with the current Occupational Health Safety Act.

Included in risk and safety, The standardised Transnet Freight Rail induction shall be given to all staff of all contractors at the start of each project and the contractors shall send all his staff that will work on the Transnet Freight Rail site to the induction on the date as agreed on between TFR Project manager and the contractor.

The total price, excluding VAT, must be carried over to the Service Fee and Cost Form, Section 6 of the RFQ. The amount must also be written in words on the Service Fee and Cost Form.

"PREVIEW COPY ONLY"

Respondent's signature: _____

Date: ____ / ____ / ____

ANNEXURE B

TENDER PRICE LIST PER ITEM FOR FENCING

ASSET DESCRIPTION: SECURITY FENCE

CITY / TOWN: TOUWSRIVIER

TENDER NO: BLE/51894

ASSET NO: 07HFB03C

WORK DESCRIPTION: ERECT SECURITY FENCE 1260M LONG X 1,80M HIGH

Measurements and or quantities do not include off cuts or waste all measurements of material is measure as nett fixed. Contractor to add his own % for off cuts and waste.

The contractor is responsible to check all the measurements and quantities as stated before ordering any material. The measurement and quantities are only for tender purposes.

Value Added Tax (VAT) shall be excluded in the schedule of rates and prices.

To be supplied by the Contractor: The Contractor shall provide all labour, material, transport, consumable stores, plant, equipment, tools, services, materials and ingredients of every description required for the carrying out and completion of the WORK as per the attached worklist and specification and as may be ordered by the Project Manager.

GENERAL: All normal cleaning, preparation include sanding and wash of items to be painted as specified by the paint manufacturer is included in all the paint items. All scaffolding and use of ladders as necessary is part of all the items. All work shall be done according to the attached specifications. Unless otherwise specified all materials must comply with SANS specifications.

Where no applicable SANS Specification exists the materials must be approved by the Transnet Freight Rail project manager.

All material shall be fitted, install or applied as specified by the manufacture.

The contractor shall be liable for any damages cause by him or his staff to any Transnet Freight Rail property or equipment.

SAFETY: The contractor shall comply with the Occupational Health Safety Act, 1993 (Act 85 of 1993).

Page 1 of 3

SUB TOTAL PAGE 1

--

TENDER NO: BLE/51894

ASSET NO: 07HFB03C

ITEM NO	FAULT DISCRPTION	ITEM TOTAL	MEASURE UNIT	UNIT RATE	ITEM AMOUNT
EXCAVATIONS/BACKFILL					
835	Excavations of foundations for Posts;Stays and Intermediat Posts 0,45m x0,45m x0,60m total 370 foundations (use pick and space)	58	M^3		
MASS CONCRETE/REINFORCING					
844	Hand mix concrete on site where a small quantity is required. Concrete shall be mixed on mixing board or hard surface. cast concrete in foundations and compact. concrete shall be at least 20mpa. all work and material to comply with attached specification	58	M^3		
FENCING					
862	Cut all vegetation to 50mm above ground level, both sides of fence 1m wide (in total 2.0m wide) see attached specification	2164	M^2		
863	Replace straining wire Ø 4mm diameter thick for fence up to 1,80m high above ground	625	KG		

Respondent's signature: _____

Date: ____/____/____

--

TENDER NO: BLE/51894

ASSET NO: 07HFB03C

ITEM NO	FAULT DISCRPTION	ITEM TOTAL	MEASURE UNIT	UNIT RATE	ITEM AMOUNT
864	Binding wire Ø 2mm to secure and connect all tipe of wire fencing posts and razor wire in position except where the wire cross the timber posts.	80	KG		
866	Replace Tanalith Timber Corner and Straining Posts Ø100/119mm x 2.4m long. Height 1,80m high from ground level.	27	EA		
867	Replace Tanalith Timber Gate posts Ø120/139mm x 2,40m long and 1,80 above ground level	2	EA		
868	Replace Tanalith Timber Intermediat posts Ø 80/90mm x 2,40m long and 1,80 above ground level	394	EA		
869	Replace Tanalith Timber Stay posts Ø 80/90mm x 2,40m long and 1,80 above ground level	52	EA		
871	Remove 1.2m stock fence complete, include all poles and droppers	170	M		
875	Replace flat wrap razor coil fence Ø 50m x 1.8m high.The cover of rolls not more than 13m and tie every 300mm and with U staples 400mm long where crossing timber posts	385	EA		
888	Replace double leaf gate 6,0m wide x 1,80m high and cover with razor wire and one third above gates end tied with Ø 2mm binding wire as per specification (As per position on plan)	1	EA		

"PREVIEW COPY ONLY"

Respondent's signature: _____

Date: ____/____/____

TENDER NO: BLE/51894

ASSET NO: 07HFB03C

ITEM NO	FAULT DISCRPTION	ITEM TOTAL	MEASURE UNIT	UNIT RATE	ITEM AMOUNT
---------	------------------	------------	--------------	-----------	-------------

PRELIMINARY AND GENERAL

P and G shall include all cost not directly relate to a specific item on the schedule of prices and rates. All items not specifically mentioned in the Schedule of Rates and prices and form part of contractor's requirements such as cost of stationery, as well as establishment of workers on site and removal of site establishment, it will also include the handing over of the site to the contractor and the handing back of the site after completion of work .

P + G

RISK AND SAFETY

RISK ASSESSMENTAND SAFETY INDUCTION
 Cost for the risk assessment must include a full identification of the risks before the work starts and the necessary equipment, appropriate precautions and systems of work must be provided and Implemented.

TOTAL

Cost for the risk assessment and safety include complete compliance with the current Occupational Health Safety Act.

Included in risk and safety, The standardised Transnet Freight Rail induction shall be given to all staff of all contractors at the start of each project and the contractors shall send all his staff that will work on the Transnet Freight Rail site to the induction on the date as agreed on between TFR Project manager and the contractor.

The total price, excluding VAT, must be carried over to the Service Fee and Cost Form, Section 6 of the RFQ. The amount must also be written in words on the Service Fee and Cost Form.

"PREVIEW COPY ONLY"

Respondent's signature: _____

Date: ____ / ____ / ____