

PRECAST CONCRETE DRAINAGE CHANNELS

- 1. CONCRETE CUBE STRENGTH TO BE 25 MPg AT 28 DAYS
- 2. WELDED MESH REINFORCEMENT.
- HORIZONTAL BARS Ø7.1mm
- HORIZONTAL BARS ON SIDES @ 200mm SPACING VERTICAL BARS ON SIDES @ 100mm SPACING VERTICAL BARS Ø6.3mm
- 3. CONCRETE TO HAVE STEEL SHUTTER FINISH
- 4. THIS DESIGN IS NOT TO BE BUILT WITHIN 5km OF THE COAST
- REF. 433 MESH -6.5kg/panel $1.594 \text{m} \times 0.940 \text{m} = 1.498 \text{m}^2$
- 391kg 384kg/panel (0.160m³)
- 6. JOINTS TO BE AS SMALL AS POSSIBLE AND SEALED INTERNALLY WITH PROSTRUCT DYMONIC NT AS PER MANUFACTURERS SPECIFICATION.

Z		4	4						
		NSNET	AMEND	WYSIG	\ -	2	W	4	۲٦.
CONSTRUCTION J. Smuts	DRAWN D. Atkins	DESIGNED	DESCRIPTION		PRECAST CONCRETE DRAIN DETAILS ADJUSTED FOR TENDER PURPOSES.	SUB-SOIL DRAIN ADDED.	BEDDING & GROUT ADDED	JOINT SPEC CHANGED.	BED MATERIAL CHANGED (30 TO 80mm)
P.O. Box 425 Richards Bay 3900 Tel. 035-9053400 Fax 035-7979375				RPOSES.				+	
9375	25 Jy 3400 375		IN IN	PARAAF	D.A.	D.A.	D.A.	D.A.	D.A.
•	1	TRANSMET	22.	DATUM	2005-3-31	2005-5-23	2005-11-7	2006-01-30	2006-11-24

DATE

2010-04-23 | REF4421498-C-LA-1018-01

PROJECT MUNBER | BU | FBS | DIS | TYPE | DRG. NO. | SHT. | REV. | A 4 2 1 4 9 8 | -3 | 000 | C | LA | 1 0 1 8 | 0 1 | 0 1 |