

TRANSNET SOC LIMITED
(REGISTRATION NO.1990/000900/30)
TRADING AS
TRANSNET FREIGHT RAIL

NEC3 Engineering & Construction Short Contract
(ECSC)

RFQ No. MMC-ERAC-NGP-014739 CIDB

SUPPLY, INSTALL, TEST AND COMMISSION WAVE
FILTER EQUIPMENT AND ASSOCIATED CABLES AT
NGODWANA 3KV DC SUBSTATION, UNDER THE
CONTROL OF DEPOT ENGINEERING MANAGER,
NELSPRUIT.

Opens on: 29 July 2014
Closing date: 12 August 2014 (at 10h00)
Validity date: 30 October 2014

Document reference	Title: Supply, Install, Test And Commission Wave Filter Equipment And Associated Cables At Ngodwana 3kv Dc Substation, Under The Control Of Depot Engineering Manager, Nelspruit.	No of pages
<p>Part T1</p> <p>Tendering procedures</p> <p>T1.1</p> <p>T1.2</p> <p>Part T2</p> <p>T2.1</p> <p>T2.2</p>	<p>THE TENDER</p> <p>Tendering procedures</p> <p>Tender Notice and Invitation to Tender</p> <ul style="list-style-type: none"> • Suppliers Code of Conduct <p>Tender Data</p> <p>Returnable documents</p> <p>List of Returnable Documents/Schedules</p> <p>Returnable Schedules</p>	
<p>Part C1</p> <p>C1.1</p> <p>C1.2</p> <p>Part C2</p> <p>C2.1</p> <p>C2.2</p> <p>Part C3</p> <p>C3.1</p> <p>C3.2</p> <p>C3.3</p> <p>Part C4</p> <p>C4.1</p>	<p>THE CONTRACT</p> <p>Agreement and Contract Data</p> <p>Contract Data: Works Information</p> <p>Contract Data: The Contractor's Offer & Acceptance</p> <p>Pricing Data</p> <p>Pricing instructions</p> <p>Price list</p> <p>Scope of Work</p> <p>Works Information</p> <p>Secondary Specifications</p> <p>General Specifications</p> <p>Site information</p> <p>Site Information</p>	

Part T1: Tendering Procedures

"PREVIEW COPY ONLY"

T1.1 TENDER NOTICE AND INVITATION TO TENDER

RFQ No MMC-ERAC-NPG-014739 CIDB

Transnet SOC Limited trading as Transnet Freight Rail invites renderers for Supply, Install, Test And Commission Wave Filter Equipment And Associated Cables At Ngodwana 3kv Dc Substation, Under The Control Of Depot Engineering Manager, Nelspruit

Tenderers should have a CIDB contractor grading designation of **1 EP** or higher.

Queries relating to the administrative issues of these documents may be addressed to:

Ms. Matete Madisha
Tel. No. 013 656 4254
Fax. No. 013 656 4259
E-mail: Matete.Madisha

A compulsory clarification meeting with representatives of the Employer will take place on **Tuesday, 05 August 2014, 09H00 at Transnet – Maroela Boardroom, Andrew Street at Nelspruit Depot and thereafter proceed to the entire substations for physical site briefing.**

(For direction please contact: Joseph Majola on 083 277 8737).

[Respondent to provide own PPE, transportation and accommodation].

Tenderers without a valid tender document in their possession will not be allowed to attend this compulsory clarification meeting/site inspections.

Tenderers shall be responsible for their own travel arrangements and cost regarding the site meeting and site inspections.

Tenderers without a valid tender document in their possession will not be allowed to attend this compulsory clarification meeting/site inspections. Tenderers shall be responsible for their own travel arrangements and cost regarding the site meeting and site inspections.

Transnet reserves the right to accept the whole or any part of a tender. Transnet also reserves the right to negotiate terms and conditions with all, or a short-listed group of contenders, or the preferred tenderer, should it be deemed necessary.

This tender closes punctually at 10h00 on Tuesday, 12 August 2014.

Tenders may only be submitted on the tender documentation that is issued. Telegraphic, telephonic, facsimile and late tenders will not be accepted. Tenderers are warned that a tender will be liable to disqualification should any attempt be made by a Tenderer either directly or indirectly to canvass any officer(s) or employees of Transnet Limited in respect of a tender between the date the tender is submitted and the date of the award. A Tenderer may, however, at any time communicate with the Chairperson of the Transnet Freight Rail Acquisition Council, at telephone no. 011 5449486 on any matter relating to his tender.

Envelopes must not contain documents relating to any tender other than that shown on the envelope. *No slips are to be attached to the tender documents. Any additional conditions must be embodied in an accompanying letter. Alterations, additions or deletions must not be made by the Tenderer to the actual tender documents.* Tenders submitted by Tenderers must be neatly bound and the inclusion of loose documents must be avoided.

Requirements for sealing, addressing, delivery, opening and assessment of tenders are stated in the Tender Data.

Compliance of tender(s) with Transnet's requirements is the sole responsibility of the Tenderer and any costs incurred in subsequent modifications to or replacement of equipment accepted by Transnet Limited in good faith on the grounds of certified compliance with specified standards by the contractor and in fact found to be inadequate in such respects, will be to the relevant Tenderer's account.

BROAD-BASED BLACK ECONOMIC EMPOWERMENT (“BBBEE”)

TRANSNET fully endorses and supports the South African Government's Broad-Based Black Economic Empowerment Programme and it is strongly of the opinion that all business enterprises have an equal obligation to redress the imbalances of the past.

TRANSNET would therefore prefer to do business with business enterprises who share these same values and who are prepared to contribute to meaningful BBBEE initiatives (including and not limited to enterprise development, subcontracting and Joint Ventures) as part of their tender response.

Transnet would accordingly allow a “preference” in accordance with the 10% preference system, as per the Preferential Procurement Policy Framework Act 5 of 2000 (as amended) to companies who provide a BBBEE accreditation Certificate. All procurement and disposal transactions in excess of R30000 (Thirty thousand ZAR) will be evaluated accordingly. All transactions below R30000 will, as far as possible, be earmarked for Exempted Micro Enterprises (EME's).

TRANSNET consequently urges Respondents (Large enterprises and QSE's – see below) to have themselves duly accredited by any one of the Accreditation Agencies approved by SANAS (South African National Accreditation System, under the auspices of the DTI).

In terms of Government Gazette No. 32467, Notice No. 810 dated 31 July 2009, as from 1 February 2010 only BBBEE certificates issued by Accredited Verification Agencies of Verification Agencies that are in possession of a valid pre-assessment letter from South African National Accreditation System will be valid.

However accreditation certificates issued by non-accredited verification agencies before 01 February 2010 and which are still within their one (1) year validity period will still be acceptable, until their expiry date provided that the accreditation was done in accordance with the latest codes (i.e. those promulgated on 9 February 2007).

BBBEE Accreditation Certificates issued after the published date i.e. 01 February 2010, by a Verification Agency not approved by SANAS, will NOT be acceptable as from 01 February 2010.

Enterprises will be rated by such Accreditation Agencies based on the following:

- (a) **Large Enterprises (i.e. annual turnover >R35 million):**
 - Rating level based on all 7 (seven) elements of the BBBEE scorecard
 - Enterprises to provide BBBEE certificate and detailed scorecard (to be renewed annually)
- (b) **Qualifying Small Enterprises – QSE (i.e. annual turnover >R5 million but <R35 million):**
 - Rating based on any 4 (four) of the elements of the BBBEE scorecard
 - Enterprises to provide BBBEE certificate and detailed scorecard (to be renewed annually)
- (c) **Exempted Micro Enterprises – EME (i.e. annual turnover <R5m are exempted from being rated or verified):**
 - Automatic BBBEE Level 4 rating, irrespective of race ownership, i.e. 100% BBBEE recognition
 - Black ownership >50% or Black Women ownership >30% automatically qualify as Level 3 BBBEE rating, i.e. 110% BBBEE recognition
 - EME's should provide documentary proof of annual turnover (i.e. audited financials) plus proof of Black ownership if Black ownership >50% or Black Women ownership >30% (to be renewed annually) from their Auditors / Accounting Officers

In addition to the above, Respondents who wish to enter into a Joint Venture (JV) or subcontract portions of the contract to BBBEE companies must state in their Tenders / Proposals the percentage of the total contract value which would be allocated to such BBBEE companies, should they be successful in being awarded any business. A rating certificate in respect of such BBBEE JV-partners and/or sub-contractors, as well as a breakdown of the distribution of the aforementioned percentage allocation must also be furnished with the tender response to enable Transnet to evaluate / adjudicate on all tenders received on a fair basis.

Each Respondent is required to furnish proof of its BBBEE status (Certificate and Detailed Scorecard) and ensure that the documentation is valid at the date of Tender Submission as stipulated above to TRANSNET.

Failure to submit your BBBEE Certificate and Detailed Scorecard will result in a score of zero being allocated for BBBEE evaluation.

Turnover: Indicate your company's most recent annual turnover: R.....

- If annual turnover <R5m, please attach auditors / accounting officers letter confirming annual turnover and percentage black ownership as well as Black Women ownership
- If annual turnover >R5m please attach BBBEE certificate and detailed scorecard from an accredited rating agency.

The DTI has created an online **B-BBEE Registry** (<http://www.dti.gov.za>) in order to provide a central and standardized source of the B-BBEE status of all entities, and to facilitate the flow of this information amongst entities by providing a Unique Profile Number (UPN) per each listing. Existing and prospective suppliers are therefore urged to list their B-BBEE status on the DTI Registry. Hence, entities verified by DTI, will receive the following benefits:

- Their BBBEE status will be verified and confirmed by the DTI, before listing on the Registry
- Listing on the Registry will provide suppliers the option to market themselves on the DTI B-BBEE Opportunities Network. This is a search engine that is designed to help businesses find B-BBEE compliant entities who match specific requirements in terms of the nature of services/goods provided, region, B-BBEE status or other search criteria.

Transnet supports this DTI initiative and will use the DTI Registry to verify prospective and existing suppliers' BBBEE credentials.

Kindly provide Transnet with your DTI B-BBEE UNIQUE PROFILE NUMBER with all tender submissions.

DTI BBBEE UNIQUE PROFILE NUMBER:

.....

Failure to submit your BBBEE information in terms of the above-mentioned clauses will result in a score of zero being allocated for BBBEE evaluation.

Suppliers and Tenderers are requested to duly complete the Supplier Declaration Form (SDF) and provide all the relevant supporting attachments as requested. Failure to provide the following may disqualify your tender submission:-

1. Duly completed SDF
2. BBBEE Certificate and detailed scorecard
3. Current tax clearance certificate

The Supplier and Tenderer shall furnish proof of the above to Transnet.

Transnet at its sole discretion may decide to allow certain price preferences in order to uplift the historically disadvantaged in terms of the PPPFA (Act 5 of 2000).

Transnet insists on honesty and integrity beyond reproach at all times and will not tolerate any form of improper influencing, bribery, corruption, fraud, or any other unethical conduct on the part of bidders/ Transnet employees. If, in the opinion of Transnet's Chief Operating Officer, a tenderer/contractor/ supplier has or has caused to be promised, offered or given to any Transnet employee, any bribe, commission, gift, loan, advantage or other consideration, Transnet shall be entitled to revoke the tender / contract by following its internal policies that govern the Exclusion process. In such an event Transnet will be entitled to place any Tenderer/Contractor/Supplier who has contravened the provisions of Transnet's business ethics on its List of Excluded Tenderers. This List will also be distributed to all other State Owned Enterprises and Government Departments.

Transnet invites its valued suppliers to report any allegations of fraud, corruption or other unethical activities to Transnet Tip-offs Anonymous, at any of the following addresses/contract numbers :-

- Toll free anonymous hotline – 0800 003 056
- Email – Transnet@tip-offs.com
- Fax number – 0800 007 788
- Freepost DN 298, Umhlanga Rocks, 4320

CONFIDENTIALITY IS GUARANTEED.

"PREVIEW COPY ONLY"

Part T1.2: Tender Data

"PREVIEW COPY ONLY"

T1.2 TENDER DATA

The conditions of tender are the Standard Conditions of Tender as contained in Annexure F of the CIDB Standard for Uniformity in Construction Procurement. (See www.cidb.org.za) The Standard Conditions of Tender make several references to the Tender Data for details that apply specifically to this tender. The Tender Data shall have precedence in the interpretation of any ambiguity or inconsistency between it and the standard conditions of tender. Each item of data given below is cross-referenced to the clause in the Standard Conditions of Tender to which it mainly applies.

F.1.1 The employer is **Transnet Limited trading as Transnet Freight Rail.**

F.1.2 The tender documents issued by the employer comprise:

Part T1: Tendering procedure

T1.1 Tender notice and invitation to tender

- Suppliers Code of Conduct

T1.2 Tender data

Part T2: Returnable documents

T2.1 List of returnable documents

T2.2 Returnable Schedules

Part C1: Agreements and contract data

C1.1 Contract Data: General

C1.2 Contract data: The contractor's Offer and Acceptance

C1.3 Contract Data: Works Information

Part C2: Pricing data

C2.1 Pricing instructions

C2.2 Price list

Part C3: Scope of work

C3.1 Works Information

C3.2 Secondary specifications

C3.3 General specifications

Part C4: Site information

C4 Site information

- Principal Controlled insurance

F.1.4 The employer's agent is:

Name: Mr. Joseph Majola

Address: Electrical Department

Nelspruit Depot

Tel: 083 277 8737

E-mail: Joseph.Majola@transnet.net

F.2.11 The following Tenderers who are registered with the CIDB, or are capable of being so prior to the evaluation of submissions, in a contractor grading designation equal to or higher than a contractor grading designation determined in accordance with the sum tendered for a **1 EP** class of construction work, are eligible to submit tenders.

- a) contractors who have a contractor grading designation equal to or higher than a contractor grading designation determined in accordance with the sum tendered for a **1 EP** class of construction work; and

F.2.11(b) The arrangements for a compulsory clarification meeting are as stated in the Tender Notice and Invitation to Tender. Tenderers must sign the attendance list in the name of the tendering entity. Addenda will be issued to and tenders will be received only from those tendering entities appearing on the attendance list.

F.2.12 If a Tenderer wishes to submit an alternative tender offer, the only criteria permitted for such alternative tender offer is that it demonstrably satisfies the Employer's standards and requirements, the details of which may be obtained from the Employer's Agent.

Calculations, drawings and all other pertinent technical information and characteristics as well as modified or proposed Pricing Data must be submitted with the alternative tender offer to enable the Employer to evaluate the efficacy of the alternative and its principal elements, to take a view on the degree to which the alternative complies with the Employer's standards and requirements and to evaluate the acceptability of the pricing proposals. Calculations must be set out in a clear and logical sequence and must clearly reflect all design assumptions. Pricing Data must reflect all assumptions in the development of the pricing proposal.

Acceptance of an alternative tender offer will mean acceptance in principle of the offer. It will be an obligation of the contract for the Tenderer, in the event that the alternative is accepted, to accept full responsibility and liability that the alternative offer complies in all respects with the Employer's standards and requirements.

The modified Pricing Data must include an amount equal to 5% of the amount tendered for the alternative offer to cover the Employer's costs of confirming the acceptability of the detailed design before it is constructed. No alternative tender offers will be considered.

F.2.13.2 Return all returnable documents to the employer after completing them in their entirety, either electronically (if they were issued in electronic format) or by writing in black ink.

F.2.13.3 Parts of the tender offer communicated on paper shall be submitted as an original, plus one copy.

F.2.13.5 The employer's address for delivery of tender offers and identification details to be shown on each tender offer package are:

If posted, the envelope must be addressed to:

**The Chairperson
Transnet Freight Rail Acquisition Council
P.O. Box 4244
JOHANNESBURG
2000**

and must be dispatched in time for sorting by the Post Office to reach the Post Office Box indicated above, before the closing time of the tender.

If delivered by hand, to be deposited to the Transnet Freight Rail Acquisition Council tender box which is located in the foyer, and to be addressed as follows:

**The Chairperson
Transnet Freight Rail Acquisition Council
Ground Floor, Inyanda House
21 Wellington Road
ParkTown
JOHANNESBURG
2001**

It should also be noted that the above tender box is accessible to the public 24 hours per day, 7 days a week.

The measurements of the "tender slot" are 500mm wide x 100mm high, and Tenderers must please ensure that tender documents/files are not larger than the above dimensions. Tenders, which are too bulky (i.e. more than 100mm thick) must be split into two or more files, and placed in separate envelopes.

Identification details

Tenders must be submitted before the closing hour on the date as shown in F.2.15 below, and must be enclosed in a sealed envelope which must have inscribed on the outside:

- (a) **Tender No**
- (b) **Description of work**
- (c) **Closing date of tender**

F.2.13.6 A two-envelope procedure will not be followed.

F.2.15 The closing time for submission of tender offers is as stated in the Tender Notice and Invitation to Tender.

F.2.15 Telephonic, telegraphic, telex, facsimile or e-mailed tender offers will not be accepted.

F.2.16 The tender offer validity period is **(30 October 2014)**

F.2.19 Access shall be provided for the following inspections, tests and analysis:

Inspection of current arrangement foundation and steelwork condition and measurements in substation yards during the tender period after the site meeting and prior to the closing date of tender.

F.2.23 The Tenderer is required to submit with his tender:
Either a Certificate of Registration issued by the Construction Industry Development Board or a copy of the application Form for registration in terms of the construction Industry Development Board Act (Form F006) and an original valid Tax Clearance Certificate issued by the South African Revenue Services.

F.3.4 The time and location for opening of the tender offers are:
Time: **10:00** on the closing date of tender.
Location: **Transnet Freight Rail Acquisition Council,
Ground Floor,
Inyanda House,
21 Wellington Road,
Park Town,
JOHANNESBURG**

F.3.11.1 The procedure for the evaluation of responsive tenders is

The score for quality is to be calculated using the following formula:

$$W_Q = W_2 \times S_O / M_S$$

Where: W_2 is the percentage score given to quality and equals **60**
 S_O is the score for quality allocated to the submission under consideration
 M_S is the maximum possible score for quality in respect of a submission

The score for financial offer is calculated using Formula 2 (option 1) of SANS294

Formula	Comparison aimed at achieving	Option 1	Option 2
1	Highest price or discount	$A = (1 + \frac{P - P_m}{P_m})$	$A = P / P_m$
2	Lowest price or percentage commission / fee	$A = (1 - \frac{P - P_m}{P_m})$	$A = P_m / P$

where:

P_m = the comparative offer of the most favourable tender offer.
 P = the comparative offer of tender offer under consideration

Where: W_1 is the percentage score given to financial offer and equals 100 minus W_2 .

The score for quality and financial offer is to be combined, before the addition of the score for preference, as follows:

$$W_C = W_3 \times (1 + \frac{S - S_m}{S_m})$$

S_m

Where W_3 is the number of tender evaluation points for quality and financial offer and equals:

- 1) 90 where the financial value, VAT inclusive, of all responsive tenders received have a value in excess of R1,000,000; or
- 2) 80 where the financial value, VAT inclusive, of one or more responsive tender offers equals or is less than R1,000,000.

S is the sum of score for quality and financial offer of the submission under consideration.

S_m is sum of the score for quality and financial offer of the submission scoring the highest number of points

Up to 100 minus W_3 tender evaluation points will be awarded to Tenderers who complete the preference schedule and who are found to be eligible for the preference claimed. Tenderers shall submit BBBEE rating certificates with detailed scorecards that will be issued by the verification agencies that do their BBBEE ratings in accordance with the latest Department of Trade and Industry codes of Good Practice.

F.3.11.3 Only those Tenderers who score a minimum score of **60** points in respect of the following quality criteria are eligible to submit tenders.

As prescribed in terms of the Preferential Procurement Policy Framework Act (PPPFA), Act 5 of 2000 and its Regulations, Respondents are to note the following:

- Functionality is included at a pre-qualification stage with a prescribed percentage threshold of **60**
- Proposals will be evaluated on price which will be allocated **80 or 90 points** and preference which will be allocated **20 or 10 points**, dependent on the value of the Services.
- The 80/20 preference point system applies where the acquisition of the Goods or Services will be less than R1 000 000.00.
- If the 80/20 preference point system is stipulated and all Bids received exceed R1 000 000.00, the RFQ will be cancelled.
- The 90/10 preference point system applies where acquisition of the Goods or Services will exceed R1 000 000.00
- If the 90/10 preference point system is stipulated and all Bids received are equal to or below R1 000 000.00, the RFQ will be cancelled.
- **In this RFQ, Transnet will apply 80/20 preference point system prescribed in the PPPFA.**

In compliance with the Government Gazette No 34612, Notice No. 754 dated 23 September 2011, as from 1 October 2011 valid B-BBEE Verification Certificates must be issued by:

- Verification Agencies accredited by the South African National Accreditation System [SANAS]; or
- Registered Auditors approved by the Independent Regulatory Board of Auditors [IRBA], in accordance with the approval granted by the Department of Trade and Industry.

Enterprises will be rated by such agencies based on the following:

a) Large Enterprises [i.e. annual turnover greater than R35 million]:

Rating level based on all seven elements of the B-BBEE scorecard

b) Qualifying Small Enterprises – QSE [i.e. annual turnover between R5 million and R35 million]:

Rating based on any four of the elements of the B-BBEE scorecard

c) Exempted Micro Enterprises – EME [i.e. annual turnover less than R5 million]:

In accordance with B-BBEE Codes of Good Practice [Statement 000, Section 4], any enterprise with an annual total revenue of R 5 million or less qualifies as an EME.

- Automatic rating of B-BBEE Level 4 irrespective of race or ownership
- Black ownership greater than 50% or Black Women ownership greater than 50% automatically qualify as B-BBEE Level 3

Sufficient evidence to qualify as an EME would be a certificate (which may be in the form of a letter) from an auditor or accounting officer or a certificate from a Verification Agency accredited by SANAS. The certificate must confirm the company's turnover, black ownership / black female ownership, B-BBEE status level and validity date.

Respondents are required to furnish proof of the above to Transnet. [i.e. a valid detailed scorecard as stipulated above in respect of Large Enterprises and QSEs, or a valid certificate in respect of EMEs].

Transnet will accordingly allocate a maximum of **20 [twenty] points** in accordance with the **80/20** preference point system prescribed in the Preferential Procurement Policy Framework Act (PPPFA), Act 5 of 2000 and its Regulations to the Respondent's

final score based on an entity's B-BBEE scorecard rating. [Refer **Annexure A- B-BBEE Preference Points Claim Form** for further details].

N.B. Failure to submit a B-BBEE certificate, which is valid as at the Closing Date of this RFP, will result in a score of zero being allocated for B-BBEE.

Transnet will utilise the following criteria in choosing a Supplier/Service Provider, if so required:

Stage One - Administrative responsiveness

- Completeness of response and returnable documents

Stage Two - Substantive responsiveness (Mandatory requirements)

- All respondents must be graded on a **1 EP CIDB** grading.
- Valid Letter of Good Standing from Department of Labour

The test for Administrative responsiveness and Substantive responsiveness must be passed for a Respondent's Quotations to progress to Stage Three for further evaluation.

Stage Three – Minimum Qualifying score is 60 % for Technical Criteria

The test for the Technical and Functional threshold will include the following:

FUNCTIONAL EVALUATION	RATING					WEIGHT	TOTAL
	1	2	3	4	5		
Risk/Safety Plan						5%	
Technical Capacity/Resources						10%	
Clause by clause compliance to specification						30%	
Delivery period for the project						50%	
Qualifications of staff						5%	

	TOTAL	100	
--	--------------	------------	--

The following applicable values will be utilised when scoring each criterion mentioned above:

Poor	=	20
Satisfactory	=	40
Good	=	60
Very good	=	80
Excellent	=	100

Stage Four – Pricing/BBB-EE scoring

The bidders that have successfully progressed through to Phase 2 will be evaluated in accordance with the **90/10 preference point system** contemplated in the Preferential Procurement Policy Framework Act (Act 5 of 2011)

Weighted evaluation based on 80/20 preference point system:

Pricing

- Pricing will be calculated using the lowest price quoted as the baseline, thus the lowest price quoted will achieve full marks, while all other quotes will achieve a weighted average mark based on the lowest price.
- Pricing and price basis [firm] - whilst not the sole factor for consideration, competitive pricing and overall level of unconditional discounts¹ will be critical

Transnet will utilise the following formula in its evaluation of Price:

$$PS = 90 \left(1 - \frac{Pt - Pmin}{Pmin} \right) \text{ Where:}$$

P_s	=	Score for the Bid under consideration
P_t	=	Price of Bid under consideration
P_{min}	=	Price of lowest acceptable Bid

- B-BBEE status of company

¹ Only unconditional discounts will be taken into account during evaluation. A discount which has been offered conditionally will, despite not being taken into account for evaluation purposes, be implemented when payment is effected.

Preference points will be awarded to a bidder for attaining the B-BBEE status level of contribution in accordance with the table below:

B-BBEE Status Level of Contributor	Number of points (90/10 system)	Number of points (80/20 system)
1	10	20
2	9	18
3	8	16
4	5	12
5	4	8
6	3	6
7	2	4
8	1	2
Non-compliant contributor	0	0

Description	Total	Total
Price	90	80
BBBEE	10	20
Total	100	100

F.3.13.1 Tender offers will only be accepted if:

- a) The Tenderer has in his or her possession an original valid Tax Clearance Certificate issued by the South African Revenue Services or has made arrangements to meet outstanding tax obligations.
- b) The Tenderer is registered with the Construction Industry Development Board in an appropriate contractor grading designation;
- c) The Tenderer or any of its directors is not listed on the Register of Tender Defaulters in terms of the Prevention and Combating of Corrupt Activities Act of 2004 as a person prohibited from doing business with the public sector.

- d) The Tenderer has not:
- i) abused the Employer's Supply Chain Management System; or
 - ii) failed to perform on any previous contract and has been given a written notice to this effect; and
- e) has completed the Compulsory Enterprise Questionnaire and there are no conflicts of interest which may impact on the Tenderer's ability to perform the contract in the best interests of the employer or potentially compromise the tender process.

F.3.18 The number of paper copies of the signed contract to be provided by the employer is one.

The additional conditions of tender are:

1. The Tenderer is deemed to have satisfied himself before tendering as to the correctness and sufficiency of his tender for the *works* and of the prices stated in the priced Activity Schedule in the *works* Information. The rates and prices (except in so far as otherwise provided in the Tender) collectively cover full payment for the discharge of all his obligations under the Contract and all matters and things necessary for the proper completion of the *works*.

2. *The tenders shall be completed in black ink only.*

3. ADDITIONAL TENDER CONDITIONS

- 3.1 Tenderers shall submit qualifications of staff that will be performing the works. Only qualified technical personnel shall perform the works on the electrical equipment or installations thereof.
- 3.2 During the duration of the contract, the successful Tenderer shall be required to inform the Deputy of any staff changes and provide the qualifications of the replacement staff for approval.
- 3.3 Clause by clause statement of compliance to General conditions of Contract and technical specifications (Please refer to NEC Contract Data under Works Information on page 75 on item 12.5 under Transnet Freight Rail Specifications)

3.3.1 *Tenderers shall indicate clause-by-clause compliance with the specifications.*

3.3.2 *This shall take the form of a separate document listing all the specifications clause numbers indicating the individual statement of compliance or non-compliance.*

3.3.3 *Tenderers shall motivate a statement of non-compliance.*

3.3.4 *Number the specifications according to the original tender document.*

3.3.5 *The head and sub-headings must be listed next to the specification number.*

3.3.6 *Indicate statement of compliance and motivate (give reasons for not complying).*

3.3.7 *Indicate other statements which don't require compliance.*

Note: The committee will take decision to give an average score to companies who indicated their compliance but with short comings.

- 3.4** The Tenderer shall provide a Gantt or a similar bar chart showing how long it will take to complete the works and be energised. This chart shall be submitted with the tender submission on the closing date of the tender. Should a Tenderer be successful in winning a tender, a final bar chart shall be submitted within 14 days after the award of the contract to the employer by the successful Tenderer.
- 3.5** The Tenderer shall submit the programme/schedule in a bar chart format for the project.
- 3.6** The Tenderer shall indicate how the work will be executed and commissioned. (Approach paper)
- 3.7** Where equipment offered does not comply with standards or publications referred to in the specification, Tenderers shall state which standards apply and submit a copy in English or certified translation.
- 3.8** Tenderers shall submit descriptive literature consisting of detailed technical specifications, general constructional details and principal dimensions, together with clear illustrations of the equipment offered.
- 3.9** During the duration of the contract period, the successful Tenderer shall be required to inform the Employer / Deputy of any changes to equipment offered and submit detailed information on replacement equipment for approval prior to it being used on this contract.
- 3.10** Tenderer shall submit equipment type test certificates as specified on the contract. These shall be in English or certified translation.
- 3.11** The Tenderer shall supply a site diary and site instruction books, both books shall be of triplicates carbon copies.
- 3.12** During the duration of the contract, the successful Tenderer shall be required to inform the Supervisor of any staff changes and provide the qualifications of the replacement staff for approval.

4 **Evaluation criteria of the tender to be met are:**

- 4.1 **Phase 1:** Will be a disqualifying phase and those that comply will progress to be competitively evaluated in **phase 2.** (Refer to clause F.3.11.3)

Minimum criteria for progressing from phase 1 to phase 2 is detailed below:

- Letter of Good Standing from Department of Labour.
- CIDB grading of **1 EP** or higher to be met.
- A clause by clause statement of compliance to the following documents:
 - NEC ECSC General Conditions of Contract.
 - All secondary specifications
 - All general specifications

- 4.2 **Phase 2:** Refer to clause F.3.11.3 as mentioned above.

- 4.3 **Phase 3:** Will be evaluated in respect of Price and BBBEE at 90/10 ratio.

5. DISCLAIMERS

Transnet is not committed to any course of action as a result of its issuance of this RFQ and/or its receipt of a quotation in response to it. Please note that Transnet reserves the right to:

- modify the RFQ's goods / service(s) and request Respondents to re-bid on any changes;
- reject any Quotation which does not conform to instructions and specifications which are detailed herein;
- disqualify Quotations submitted after the stated submission deadline;
- not necessarily accept the lowest priced Quotation;
- reject all Quotations, if it so decides;
- place an order in connection with this Quotation at any time after the RFQ's closing date;
- award only a portion of the proposed goods / service/s which are reflected in the scope of this RFQ;
- split the award of the order/s between more than one Supplier/Service Provider; or
- make no award at all.

Risk/ Safety Plan:

- 5.1 A detailed plan indicating how risks and safety will be managed in a site must have the following key points depending on project requirements:
- a) Safe working procedures.
 - Construction Work supervisor
 - Subordinate construction work supervisor
 - Construction Safety officer
 - List of Tenderers already appointed – list to be updated at least monthly.
 - Health and safety representative
 - b) SHE Organisation
 - Health and safety committees
 - Composition
 - Frequency of meetings
 - Minutes of meetings
 - Legal compliance audits
 - Audit report
 - Frequency of audits
 - Finding and analysis
 - Corrective action
 - c) Risk Assessment/Management
 - Task descriptions
 - Risk identification, analysis, mitigating steps, monitoring steps and review plan.
 - Risk assessment
 - d) Education and training
 - Induction training
 - Site specific training
 - Certificate of competence
 - e) Emergency planning (Evacuation plan)
 - Client procedure
 - Site procedure
 - f) SHE communications
 - Safety/toolbox talks
 - Incident recall
 - g) Safe working Procedures and Methods
 - Method statements.
 - Safe operating procedures
 - Task/job observations
 - h) Personal Protective Equipment and Clothing
 - PPE required after all controls have been considered
 - PPE proof of issue

- i) Project security
 - Security risks identified
 - Access control
- j) Incident management
- k) Fall protection plan
- l) Substance abuse testing
- m) Logbooks and registers
- n) Health and Safety Costs

6 Environmental Management Plan

6.1 A detailed plan indicating how environmental safety will be managed in a site must have the following key points depending on projects requirements:

- a) Control of dust
- b) Noise and pollution control
- c) Waste management
- d) Environment Incident Management
- e) Contamination of surface and underground water
- f) Soil contamination
- g) Storm water drainage
- h) Environmental clean-up and rehabilitation
- i) Environment monitoring
- j) Environment training and awareness
- k) Provision for environmental clean-up and rehabilitation cost (Budget)

7 Technical Capacity/Resources

7.1 A detailed summary indicating technical capacity/resources to execute the work must have the following key points depending on projects requirements:

- a) Availability of transport to site.
- b) Number of skilled and unskilled labour who will perform work execution.
- c) Certificate for personnel with technical responsibilities
- d) Loading capacity of a truck, cranes and other machinery.
- e) Availability of tool(s) relevant to the project execution.

Note: The committee will take decision to give an average score to companies who indicated their compliance but with short comings.

Part T2: Returnable Documents

"PREVIEW COPY ONLY"

PART T2: RETURNABLE DOCUMENTS / SCHEDULES

T2.1 LIST OF RETURNABLE DOCUMENTS

The tenderer must complete the following returnable documents:

1.0 Returnable documents required for tender evaluation purposes

No	Returnable Documents
1	Letter of Good Standing with the Compensation Commissioner
2	Safety Plan and Fall Protection Plan in accordance with the Construction Regulations of 2003 and Transnet's E4E
3	Quality Assurance/control Plan
4	Environmental Management Plan
5	Certified copy of CIDB certification
6	Proposed Organization and Staffing
7	Certified Copy of Share Certificates CK1 & CK2
8	Certified Copy of Certificate of Incorporation and CM29 and CM9
9	Certified Copy of Identity Documents of Shareholders / Directors / Members (where applicable)
10	Original or certified cancelled cheque OR original or certified letter from the bank verifying banking details (with bank stamp and signature)
11	Current and original or certified Tax Clearance Certificate
12	Certified VAT registration certificate
13	A signed letter from the Accountant/Auditor confirming most recent annual turnover and percentage black ownership in the company AND/OR certified BBBEE certificate and scorecard from an accredited rating agency
14	Programme and method statement
15	Statement of compliance or non-compliance with all clauses of the Scope of Works and all the technical specifications. The clause-by-clause statement of compliance shall take the form of a separate document listing all the clause numbers of all the above specifications indicating the individual statement of compliance or non-compliance. Tenderers shall motivate a statement of non-compliance.

T2.2 RETURNABLE SCHEDULES

The tenderer must complete the following returnable schedules:

2.0 Returnable Schedules required for tender evaluation purposes

No	Returnable schedules
1	Certificate of Attendance of Information Briefing Session or site inspection
2	Certificate of Authority for Signatory (Resolution by Board)
3	Schedule of Tenderers experience
4	Schedule of Subcontractors (where applicable)
5	Certificate of authority for joint ventures (where applicable)
6	Schedule of Plant and Equipment (Tools and Machinery)
7	Foreign Exchange Rate Information (where applicable)
8	Record of Addenda to Tender Document
9	Supplier declaration form Duly completed SDF (Supplier declaration form)
10	Compulsory enterprise Questionnaire
11	Approach paper, which responds to the proposed scope of works.
12	Experience of Key Staff in the form of Curriculum Vitae
13	Transnet SOC limited contractual safety clauses which will form part of any resulting contract.
14	Proposed amendments and qualifications
15	Labour Payment Schedule

3.0 Returnable Schedules that will be incorporated into the contract

- 3.1 Certificate of attendance of information briefing session/site inspection
- 3.2 Certificate of Authority for Signatory (Resolution by Board)
- 3.3 Schedule of Tenderers experience
- 3.4 Schedule of Sub-contractors
- 3.5 Certificate of authority for joint ventures (where applicable)
- 3.6 Schedule of Plant and equipment
- 3.7 Foreign Exchange Rate Information (where applicable)
- 3.8 Record of Addenda to Tender Document
- 3.9 Supplier declaration form duly completed (SDF)
- 3.10 Compulsory Enterprise Questionnaire
- 3.11 Approach paper, which responds to the proposed scope of works.
- 3.12 Experience of key staff in the form of Curriculum Vitae
- 3.13 Transnet SOC Limited contractual safety clauses which will form part of any resulting contract
- 3.14 Proposed amendments and qualifications.
- 3.15 Labour Payment Schedule.

"PREVIEW COPY ONLY"

Part T2: Returnable Schedules

"PREVIEW COPY ONLY"

CERTIFICATE OF ATTENDANCE AT INFORMATION BRIEFING SESSION/SITE INSPECTION

This is to certify that

_____ (Tenderer)
of _____

_____ (address)

was represented by the person(s) named below at the compulsory site meeting held for all tenderers at _____ (location) on _____ (date), starting at _____ We acknowledge that the purpose of the meeting was to acquaint ourselves with the Site of the Works and/or matters incidental to doing the work specified in the tender documents in order for us to take account of everything necessary when compiling our rates and prices included in the tender.

Particulars of person(s) attending the meeting/site inspections:

Name: _____ Signature _____

Capacity: _____

Name: _____ Signature _____

Capacity _____

Attendance of the above persons at the meeting is confirmed by the Employer's representative, namely:

Name: _____ Signature _____

Capacity: _____ Date and time _____

RESOLUTION OF BOARD OF DIRECTORS

Name of firm _____

It was resolved at a meeting of the Board of Directors held on _____ that

FULL NAME(S)

SIGNATURE

in his capacity of _____ is/are hereby authorised to enter into, sign and execute and complete any documents relating to Tenders and/or Contracts for the supply of goods and services.

Confirm: Date _____

FULL NAME _____

CHAIRMAN

FULL NAME _____

SECRETARY

Certified true copy:

SIGNED AT _____ ON THIS _____ DAY OF _____ 20 _____

SCHEDULE OF THE TENDERER'S EXPERIENCE

The following is a statement of similar work successfully executed by myself/ourselves:

Employer, contact person and telephone number	Description of contract	Value of work inclusive of VAT (Rand)	Date completed
PREVIEW COPY ONLY			

Signed _____ Date _____

Name _____ Position _____

Tenderer _____

SCHEDULE OF PROPOSED SUBCONTRACTORS

We notify you that it is our intention to employ the following Subcontractors for work in this contract.

If we are awarded a contract we agree that this notification does not change the requirement for us to submit the names of proposed Subcontractors in accordance with requirements in the contract for such appointments. If there are no such requirements in the contract, then your written acceptance of this list shall be binding between us.

We confirm that all subcontractors who are contracted to construct a house are registered as home builders with the National Home Builders Registration Council.

	Name and address of proposed Subcontractor	Nature and extent of work	Previous experience with Subcontractor.
1.			
2.			
3.			
4.			
5.			

"PREVIEW COPY ONLY"

Signed _____ Date _____

Name _____ Position _____

Tenderer _____

SCHEDULE OF PLANT AND EQUIPMENT

The following are lists of major items of relevant Plant and Equipment that I/we presently own or lease and will have available for this contract or will acquire or hire for this contract if my/our tender is accepted.

(a) Details of major Plant and Equipment that is owned by and immediately available for this contract.

Quantity	Description, size, capacity, etc.

Attach additional pages if more space is required.

(b) Details of major Plant and Equipment that will be hired, or acquired for this contract if my/our tender is acceptable.

Quantity	Description, size, capacity, etc.

Attach additional pages if more space is required.

Signed _____ Date _____
Name _____ Position _____
Tenderer _____

FOREIGN EXCHANGE RATE INFORMATION REQUIRED TO BE FURNISHED BY TENDERERS.

1. Particulars of the exchange rate on which prices are based:

_____ (Foreign currency) equals R_____ (South African currency)

Note: Tenderers who offer imported material shall base their tenders on the selling rate of exchange that ruling on the last working day of the month prior to the closing date of tenders.

2. The percentage of the tender prices which is to be remitted by the Tenderers from South Africa to another country is _____% of the f.o.b./c. and f.f.o.r. in bond price (delete those not applicable).

- Note:**
- (1) The percentage quoted above will be deemed to apply even though a portion only of the item(s) tendered for is accepted.
 - (2) Adjustment in respect of variation in exchange rate will be allowed only on the percentage of the tendered price quoted above.

3. The tendered price shall be computed at the rate of exchange stated by the Tenderer in paragraphs 1 and 2 above as applied to the percentage of the tendered price quoted.

4. Transnet Freight Rail will accept for its account, in respect of such percentage of the tendered price as will be affected by the rate of exchange, any variation between the rate mentioned in paragraph 1 above, and the rate ruling at the date when payment for the goods is made by Transnet Freight Rail; provided that if the Contractor is required to remit the whole or portion of the contract price to another country in payment for goods or portion thereof prior to receiving payment from Transnet Freight Rail, the date(s) of such remittance(s) shall be deemed to be the date(s) of payment by Transnet Freight Rail for the purposes of this paragraph.

5. In the absence of a specific indication by the Contractor at the time of tendering that the proviso to paragraph 3 will apply, it will be assumed that the Contractor desires the adjustment to be effected by reference to the date on which actual payment is made by Transnet Freight Rail.

6. (a) The Contractor shall, if so required, furnish documentary proof to establish that the percentage of the contract price specified by him in paragraph 2 has actually been remitted to another country and the rate of exchange at which that was done.

- (b) Whenever the Contractor is required to remit the whole or portion of the contract price, to another country as contemplated in the proviso to paragraph 2 above, he shall notify Transnet Freight Rail forthwith and furnish documentary evidence of such remittance and of the rate of exchange at which that was done.

7. Invoices in respect of goods supplied must reflect the amount remitted or to be remitted to another country and the amount to be retained in South Africa.

8. **The Contractor shall take out forward cover for all imported materials and services within 14 days of award of the contract. Proof shall be submitted to the Project Manager of the contract. The cost of forward cover shall be invoiced separate from the contract invoices and shall not be included in the tender price.**

SIGNATURE OF TENDERER

DATE: _____

WITNESSES:

1. _____

2. _____

ADDRESS:

"PREVIEW COPY ONLY"

RECORD OF ADDENDA TO TENDER DOCUMENTS

We confirm that the following communications received from the Employer before the submission of this tender offer, amending the tender documents, have been taken into account in this tender offer:

	Date	Title or Details
1.		
2.		
3.		
4.		
5.		
6.		
7.		
8.		
9.		
10.		

Attach additional pages if more space is required.

Signed _____

Date _____

Name _____

Position _____

Tenderer _____

TRANSNET SUPPLIER DECLARATION/APPLICATION

The Financial Director or Company Secretary

Transnet Vendor Management has received a request to load your company on to the Transnet vendor database. Please furnish us with the following to enable us to process this request:

2. Complete the "Supplier Declaration Form" (SDF) on page 2 of this letter
3. **Original** cancelled cheque **OR** letter from the bank verifying banking details **(with bank stamp)**
4. **Certified** copy of Identity document of Shareholders/Directors/Members (where applicable)
5. **Certified** copy of certificate of incorporation, CM29 / CM9 (name change)
6. **Certified** copy of share Certificates of Shareholders, CK1 / CK2 (if CC)
7. A letter with the company's letterhead confirming physical and postal addresses
8. **Original** or **certified** copy of SARS Tax Clearance certificate and Vat registration certificate
9. A signed letter from the Auditor / Accountant confirming most recent annual turnover and percentage black ownership in the company **AND/OR** BBBEE certificate and detailed scorecard from an accredited rating agency (SANAS member).
NB:
 - **Failure to submit the above documentation will delay the vendor creation process.**
 - **Where applicable, the respective Transnet business unit processing your application may request further information from you. E.g. proof of an existence of a Service/Business contract between your business and the respective Transnet business unit etc.**

IMPORTANT NOTES:

- a) **If your annual turnover is less than R5 million**, then in terms of the DTI codes, you are classified as an Exempted Micro Enterprise (EME). If your company is classified as an EME, please include in your submission, a signed letter from your Auditor / Accountant confirming your company's most recent annual turnover is less than R5 million and percentage of black ownership and black female ownership in the company **AND/OR** BBBEE certificate and detailed scorecard from an accredited rating agency (e.g. permanent SANAS Member), should you feel you will be able to attain a better BBBEE score.
- b) **If your annual turnover is between R5 million and R35million**, then in terms of the DTI codes, you are classified as a Qualifying Small Enterprise (QSE) and you claim a specific BBBEE level based on any 4 of the 7 elements of the BBBEE score-card, please include your BEE certificate in your submission as confirmation of your status.
NB: BBBEE certificate and detailed scorecard should be obtained from an accredited rating agency e.g. permanent SANAS Member).
- c) **If your annual turnover is in excess of R35million**, then in terms of the DTI codes, you are classified as a Large Enterprise and you claim a specific BEE level based on all seven elements of the BBBEE generic score-card. Please include your BEE certificate in your submission as confirmation of your status.
NB: BBBEE certificate and detailed scorecard should be obtained from an accredited rating agency (permanent SANAS Member).

- d) **To avoid PAYE tax being automatically deducted from any invoices received from you,** you must also contact the Transnet person who lodged this request on your behalf, so as to be correctly classified in terms of Tax legislation.
- e) Unfortunately, **No payments can be made to a vendor** until the vendor has been registered, and no vendor can be registered until the vendor application form, together with its supporting documentation, has been received and processed.
- f) **Please return the completed Supplier Declaration Form (SDF) together with the required supporting documents mentioned above to the Transnet Official who is intending to procure your company's services/products in order that he/she should complete and Internal Transnet Departmental Questionnaire before referring the matter to the appropriate Transnet Vendor Master Office.**

Regards,

"PREVIEW COPY ONLY"

Transnet Vendor/Supplier Management *[please substitute this with your relevant Transnet department before sending this document out]*

Supplier Declaration Form

Company Trading Name							
Company Registered Name							
Company Registration Number Or ID Number If A Sole Proprietor							
Form of entity	CC	Trust	Pty Ltd	Limited	Partnership	Sole Proprietor	
VAT number (if registered)							
Company Telephone Number							
Company Fax Number							
Company E-Mail Address							
Company Website Address							
Bank Name				Bank Account Number			
Postal Address						Code	
Physical Address						Code	
Contact Person							
Designation							
Telephone							
Email							
Annual Turnover Range (Last Financial Year)	< R5 Million		R5-35 million		> R35 million		
Does Your Company Provide	Products		Services		Both		
Area Of Delivery	National		Provincial		Local		
Is Your Company A Public Or Private Entity			Public		Private		
Does Your Company Have A Tax Directive Or IRP30 Certificate			Yes		No		
Main Product Or Service Supplied (E.G.: Stationery/Consulting)							
BEE Ownership Details							
% Black Ownership		% Black women ownership		% Disabled person/s ownership			
Does your company have a BEE certificate			Yes		No		
What is your broad based BEE status (Level 1 to 9 / Unknown)							
How many personnel does the firm employ		Permanent		Part time			
Transnet Contact Person							
Contact number							

Transnet operating division			
Duly Authorised To Sign For And On Behalf Of Firm / Organisation			
Name		Designation	
Signature		Date	
Stamp And Signature Of Commissioner Of Oath			
Name		Date	
Signature		Telephone No.	

NB: Please return the completed Supplier Declaration Form (SDF) together with the required supporting documents mentioned above to the Transnet Official who is intending to procure your company's services/products.

2. VENDOR TYPE OF BUSINESS

(Please tick as applicable) (* - Minimum requirements)

2.1	Indicate the business sector in which your company is involved/operating:								
Agriculture		Mining and Quarrying							
Manufacturing		Construction							
Electricity, Gas and Water		Finance and Business Services							
Retail, Motor Trade and Repair Services		Wholesale Trade, Commercial Agents and Allied Services							
Catering, accommodation and Other Trade		Transport, Storage and Communications							
Community, Social and Personal Services		Other (Specify)							
Principal Business Activity *									
Types of Services Provided									
Since when has the firm been in business?									
2.2	What is your company's annual turnover (excluding VAT)? *								
<R20k	>R20k <R0.3m	>R0.3m <R1m	>R1m <R5m	>R6m <R10m	>R11m <R15m	>R16m <R25m	>R26m <R30m	>R31m <R34m	>R35m
2.3	Where are your operating/distribution centres situated *								

3. VENDOR OWNERSHIP DETAIL

(Please tick as applicable) (* - Minimum requirements)

3.1	Did the firm previously operate under another name? *
YES	NO

3.2	If Yes state its previous name:*
------------	---

Registered Name

Trading Name

3.3	Who were its previous owners / partners / directors?*
------------	--

SURNAME & INITIALS	ID NUMBERS

3.4	List Details of current partners, proprietors and shareholders by name, identity number, citizenship, status and ownership as relevant: *
------------	--

SURNAME & INITIALS	IDENTITY NUMBER	CITI-ZENSHIP	HDI	DIS - ABLED	GENDER	DATE OF OWNERSHIP	% OWNED	% VOTING

3.5	List details of current directors, officers, chairman, secretary etc. of the firm: *
------------	---

SURNAME & INITIALS	IDENTITY NUMBER	TITLE	DIS - ABLED	GENDER	% OF TIME DEVOTED TO THE FIRM	CONTACT NUMBER

3.6	List details of firms personnel who have an ownership interest in another firm: *
------------	--

SURNAME & INITIALS	IDENTITY NUMBER	NAME & ADDRESS OF OTHER FIRM	TITLE IN OTHER FIRM	% OWNED	TYPE OF BUSINESS OF OTHER FIRM

--	--	--	--	--	--

4. VENDOR DETAIL

(Please tick as applicable)

(* - Minimum requirements)

4.1	How many personnel does the firm employ? *					
	BLACK	WHITE	COLOURED	INDIAN	OTHER	TOTAL
Permanent						
Part Time						

4.1.1	In terms of above kindly provide numbers on women and disabled personnel? *					
	BLACK	WHITE	COLOURED	INDIAN	OTHER	TOTAL
Women						
Disabled						

4.2	Provide Details of Contact Person/s Responsible for Broad Based Black Economic Empowerment (BBBEE) in the Company *					
	SURNAME	INITIALS	DESIGNATION	TELEPHONE NO.		

4.2.1	Is your company a value adding supplier (i.e. registered as a vendor under the VAT Act of 1991, where NPAT + total labour cost > 25% of total revenue)?					
YES		NO				

4.2.2	Is your company a recipient of Enterprise Development Contributions?*					
YES		NO				

4.2.3	May the above mentioned information be shared and included in Transnet Supp Database for future reference? *					
YES		NO				

4.2.4	If you are successful in the tender/contract (where applicable) and this is awarded to your company / organisation, will this have a positive impact on your employment plans? *					
YES		NO				

4.2.5	If yes (above) kindly provide the following information:					
	BLACK	WHITE	COLOURED	INDIAN	OTHER	TOTAL
Permanent						
Part Time						

4.2.6	In terms of above kindly provide numbers on woman and disabled personnel:					
	BLACK	WHITE	COLOURED	INDIAN	OTHER	TOTAL
Women						
Disabled						

4.2.7	Are any of your members/shareholders/directors ex employees of Transnet					
YES		NO				

4.2.8 Are any of your family members employees of Transnet?					
YES		NO			
4.2.9 If Yes to points 4.2.7 & 4.2.8, list details of employees/ex-employees					
SURNAME & INITIALS	IDENTITY NUMBER	NAME & ADDRESS OF OTHER FIRM	TITLE IN OTHER FIRM	% OWNED	TYPE OF BUSINESS OF OTHER FIRM

Internal Transnet Departmental Questionnaire (for office use only)

Section 1: To be completed by the Transnet Requesting / Sourcing Department											
TFR		TRE		TPT		TPL		TNPA		TRN	
Creat		Amen		Block		Unbloc		Once-Off / Emergency			
Exten		Delete		Undel							
Supplier's trading name											
Supplier's registered name											
Please indicate if the Supplier has a contract with sourcing Transnet OD								Yes		No	
If yes please submit a copy of the letter of award											

a) What is being procured from the supplier?				
i. Products only	Yes		No	
ii. Services only	Yes		No	
iii. Labour only	Yes		No	
iv. Mix of services and products	Yes		No	
v. Mix of services and labour	Yes		No	

b) If your answer is **YES** to questions II, III, IV or V in paragraph a) above, please indicate whether the relevant **PAYE questionnaires** have been forwarded to the appropriate **Transnet Operational Divisions'** decision making bodies/ **Strategic Supply Management** team for a directive /decision on tax withholding from payments to this supplier.

Yes		No	
-----	--	----	--

c) If your reply to (b) is "NO", please furnish

d) Certification and Approval of proposed Vendor Creation/Unblocking/Other Changes by Transnet Official with Appropriate Delegated Authority :

I HEREBY CERTIFY THAT THE TRANSNET DETAILED PROCUREMENT PROCESS (DPP) / PROCUREMENT MECHANISM HAS IN ALL RESPECTS BEEN ADHERED TO AND I

THEREFORE APPROVE THE PROPOSED VENDOR CREATION/APPROVAL/OTHER CHANGES TO BE EFFECTED ON THE VENDOR MASTER

		Grade		Date				Signature			
				Y	Y	Y	Y	M	M	D	D
Tel No:				Fax							
Section 2: To be completed by the BEE Department (this section is for											
NARROW BASED (NB)				BROADBASED (BBBEE)							
BEE O	BWBE	DPBE	MR	CONTB. LEVEL	EME: <R5m	QSE: >R5m <R35m		LARGE: >R35m		VALIDITY DATE	
		Grade		Date				Signature			
				Y	Y	Y	Y	M	M	D	D
				Y	Y	Y	Y	M	M	D	D

"PREVIEW COPY ONLY"

COMPULSORY ENTERPRISE QUESTIONNAIRE

The following particulars must be furnished. In the case of a joint venture, separate enterprise questionnaires in respect of each partner must be completed and submitted.

Section 1: Name of enterprise:

Section 2: VAT registration number, if any:

Section 3: CIDB registration number, if any:

Section 4: Particulars of sole proprietors and partners in partnerships

Name*	Identity number*	Personal income tax number*

* Complete only if sole proprietor or partnership and attach separate page if more than 3 partners

Section 5: Particulars of companies and close corporations

Company registration number

Close corporation number

Tax reference number

Section 6: Record in the service of the state

Indicate by marking the relevant boxes with a cross, if any sole proprietor, partner in a partnership or director, manager, principal shareholder or stakeholder in a company or close corporation is currently or has been within the last 12 months in the service of any of the following:

- | | |
|--|---|
| <input type="checkbox"/> a member of any municipal council | <input type="checkbox"/> an employee of any provincial department, national or provincial public entity or constitutional institution within the meaning of the Public Finance Management Act, 1999 (Act 1 of 1999) |
| <input type="checkbox"/> a member of any provincial legislature | <input type="checkbox"/> a member of an accounting authority of any national or provincial public entity |
| <input type="checkbox"/> a member of the National Assembly or the National Council of Province | <input type="checkbox"/> an employee of Parliament or a provincial legislature |
| <input type="checkbox"/> a member of the board of directors of any municipal entity | |
| <input type="checkbox"/> an official of any municipality or municipal entity | |

If any of the above boxes are marked, disclose the following:

Name of sole proprietor, partner, manager, shareholder or stakeholder	Name of institution, public office, board or organ of state and position held	Status of service (tick appropriate column)	
		Current	Within last 12 months

*insert separate page if necessary

Section 7: Record of spouses, children and parents in the service of the state

Indicate by marking the relevant boxes with a cross, if any spouse, child or parent of a sole proprietor, partner in a partnership or director, manager, principal shareholder or stakeholder in a company or close corporation is currently or has been within the last 12 months been in the service of any of the following:

- a member of any municipal council
- a member of any provincial legislature
- a member of the National Assembly or the National Council of Province
- a member of the board of directors of any municipal entity
- an official of any municipality or municipal entity
- an employee of any provincial department, national or provincial public entity or constitutional institution within the meaning of the Public Finance Management Act, 1999 (Act 1 of 1999)
- a member of an accounting authority of any national or provincial public entity
- an employee of Parliament or a provincial legislature

Name of spouse, child or parent	Name of institution, public office, board or organ of state and position held	Status of service (tick appropriate column)	
		Current	Within last 12 months

*insert separate page if necessary

The undersigned, who warrants that he / she is duly authorized to do so on behalf of the enterprise:

- i) authorizes the Employer to obtain a tax clearance certificate from the South African Revenue Services that my / our tax matters are in order;
- ii) confirms that the neither the name of the enterprise or the name of any partner, manager, director or other person, who wholly or partly exercises, or may exercise, control over the enterprise appears on the Register of Tender Defaulters established in terms of the Prevention and Combating of Corrupt Activities Act of 2004;
- iii) confirms that no partner, member, director or other person, who wholly or partly exercises, or may exercise, control over the enterprise appears, has within the last five years been convicted of fraud or corruption;
- iv) confirms that I / we are not associated, linked or involved with any other tendering entities submitting tender offers and have no other relationship with any of the tenderers or those responsible for compiling the scope of work that could cause or be interpreted as a conflict of interest; and
- iv) confirms that the contents of this questionnaire are within my personal knowledge and are to the best of my belief both true and correct.

Signed _____ Date _____
Name _____ Position _____
Enterprise name _____

"PREVIEW ONLY"

EVALUATION SCHEDULE: APPROACH PAPER

The approach paper must respond to the scope of work and outline the proposed approach / methodology including that relating to health and safety. The approach paper should articulate what value add the tenderer will provide in achieving the stated objectives for the project.

The tenderer must as such explain his / her understanding of the objectives of the assignment and the Employer's stated and implied requirements, highlight the issues of importance, and explain the technical approach they would adopt to address them. The approach paper should explain the methodologies which are to be adopted, demonstrate the compatibility of those methodologies with the proposed approach. The approach should also include a quality plan which outlines processes, procedures and associated resources, applied by whom and when, to meet the requirements and indicate how risks will be managed and what contribution can be made regarding value management.

The tenderer must attach his / her approach paper to this page. The approach paper should not be longer than 8 pages.

The scoring of the approach paper will be as follows:

	Technical approach and methodology
Poor (score 40)	The technical approach and / or methodology is poor / is unlikely to satisfy project objectives or requirements. The tenderer has misunderstood certain aspects of the scope of work and does not deal with the critical aspects of the project.
Satisfactory (score 70)	The approach is generic and not tailored to address the specific project objectives and methodology. The approach does not adequately deal with the critical characteristics of the project. The quality plan, manner in which risk is to be managed etc is too generic.
Good (score 90)	The approach is specifically tailored to address the specific project objectives and methodology and is sufficiently flexible to accommodate changes that may occur during execution. The quality plan and approach to managing risk etc is specifically tailored to the critical characteristics of the project.
Very good (score 100)	Besides meeting the "good" rating, the important issues are approached in an innovative and efficient way, indicating that the tenderer has outstanding knowledge of state-of-the- art approaches. The approach paper details ways to improve the project outcomes and the quality of the outputs

The undersigned, who warrants that he / she is duly authorised to do so on behalf of the enterprise, confirms that the contents of this schedule are within my personal knowledge and are to the best of my belief both true and correct.

Signed _____ Date _____
 Name _____ Position _____
 Tenderer _____

CURRICULUM VITAE OF KEY PERSONNEL

Name:	Date of birth:
Profession:	Nationality:
Qualifications:	
Professional registration number:	
Name of employer (firm):	
Current Position:	Years with the firm:
Employment record: (list in chronological order starting with earliest work experience)	
Experience record pertinent to required service	
Certification: I, the undersigned, certify that to the best of my knowledge and belief, this data correctly describes me, my qualifications and my experience.	
_____	_____
<i>[Signature of person named in schedule]</i>	Date

TRANSNET SOC LIMITED / CONTRACTORS / SUB-CONTRACTORS

CONTRACTUAL SAFETY CLAUSES WHICH WILL FORM PART OF ANY RESULTING CONTRACT

The parties agree on the following arrangements according to section 37 (2) of the Occupational Health and Safety Act, 1993 (Act 85 of 1993) to ensure compliance by the mandatory with provisions of the Act.

- 1) That the Contractor is an "employer" in his own right as defined in section 1 of Act 85 of 1993 and that he must fulfil all his obligations as an employer in terms of the Act.
- 2) The Contractor shall comply with the requirements of Act 85 of 1993 in its entirety.
- 3) Where special permits are required, such as electrical switching, hot work permits, etc. the Contractor shall obtain them from a person designated by Transnet SOC Limited for this purpose, and all requirements of the Contractor must rigidly comply with the permit.
- 4) The Contractor shall conduct a risk assessment of the work to be performed by a competent person prior to the commencement of work, to identify risks and hazards that persons may be exposed to, analyse and evaluate identified hazards.
- 5) The Contractor shall have a documented Health and Safety Plan based on the risks and hazards identified before commencement of work.
- 6) The Health and Safety Plan shall include the following:
 - 6.1 The safety management structure to be instituted with all appointments in terms of the Act and Regulations
 - 6.2 The safe working methods and procedures to be implemented to ensure work are performed in compliance to the Act.
 - 6.3 The safety equipment, devices and clothing to be made available by the Contractor to his employees.
 - 6.4 The site access control measures pertaining to health and safety to be implemented.
 - 6.5 Control measures for ensuring that the Health and Safety Plan is maintained and monitored for the duration of the contract.
- 7) The Contractor shall ensure that all work is performed under the close supervision of a person trained to understand the hazards associated with the work performed and who has authority to ensure that the necessary precautionary measures are implemented.
- 8) The Contractor must appoint a Health and Safety Co-ordinator to liaise with Transnet SOC Limited on matters pertaining to occupational health and safety.
- 9) The appointed Safety Co-ordinator must liaise at least once a week with the* Health and Safety Section / Risk Manager /Occupational Risk Manager of Transnet SOC Limited.
- 10) The Contractor shall furnish the* Health and Safety Section/ Risk Manager/ Occupational Risk Manager of Transnet SOC Limited immediately with full particulars of any sub-Contractor which he may involve in the contract in order that the sub-Contractor himself can be made aware of all the clauses in this contract pertaining to health and safety.

- 11) The Contractor shall stop any sub-contractor from executing work which is not in accordance with the Health and Safety Plan or which poses a threat to health and safety of persons.
- 12) The Contractor shall ensure that all his employees and visitors undergoes health and safety induction pertaining to the hazards prevalent, proof of such training must be kept on file.
- 13) In the event where the risk assessment reveals the risk relating to working from an elevated position the Contractor shall cause the designation of a competent person, responsible for the preparation of a Fall Protection Plan.
- 14) The Fall Protection Plan shall include:
 - 14.1 A risk assessment of all work carried out from an elevated position
 - 14.2 Procedures and methods to address all the identified risks per location
 - 14.3 Evaluation of employee's physical and psychological fitness necessary to work at elevated position.
 - 14.4 The training of employees working from an elevated position.
 - 14.5 Procedure addressing the inspection, testing and maintenance of all fall protection equipment.
- 15) The Contractor shall advise the * Health and Safety Section / Risk Manager/ Occupational Risk Manager of Transnet SOC Limited of any hazardous situations which may arise from work being performed either by the Contractor or his sub-Contractor.
- 16) Copies of all appointments required by the act must be given to * Health and Safety Section / Risk Manager / Occupational Risk Manager of Transnet SOC Limited.
- 17) The Contractor shall ensure that a Health and Safety File is available which shall include all documentation as required by the Act, copy of his and his Sub-Contractors Risk Assessment and Health and Safety Plan.
- 18) All incidents referred to in Section 24 of the Act involving the Contractor and his Sub-Contractor on Transnet Ltd premises, shall be reported as prescribed. Transnet Ltd hereby obtains an interest in the issue of any investigation, formal inquiry conducted in terms of Section 31 and 32 of the Act into any incident involving the Contractor, his Sub-Contractor, any person or machinery under his control on Transnet Ltd premises.
- 19) No alcohol or any other intoxicating substance shall be allowed on Transnet Ltd premises. The Contractor shall not allow anyone under or suspected to be under the influence of alcohol or any other intoxicating substance on Transnet Ltd premises.
- 20) Contractor to ensure its employees undergo medical surveillance as required by legislation
- 21) Contractor will be required to provide monthly safety performance reports and statistics
- 22) A letter of good standing in terms of Section 80 (Employer to register with the Compensation Commissioner) of the Compensation for Occupational Injuries and Disease Act 1993 (Act 130 of 1993) must also be furnished.

23) All clauses in the contract pertaining health and safety form an integral part of the contract and if not complied with may be construed as breach of contract.

*As applicable

Tenderer OH & S Management System Questionnaire

This questionnaire forms part of TFR tender evaluation process and is to be completed by all Tenderer's and submitted with their tender offer. The objective of the questionnaire is to provide an overview of the status of the Tenderer's OH&S management system. Tenderers will be required to verify their responses noted in their questionnaire by providing evidence of their ability and capacity in relevant matters. **TFR will verify accuracy of this information during the physical visit as part of the tender evaluation.**

The information provided in this questionnaire is an accurate summary of the company's occupational health and safety management system.		
Company Name:		
Signed:	Name:	
Position:	Date:	
Tender Description:		
Tender Number:		
Tenderer OH&S Management System Questionnaire	Yes	No
1. OH&S Policy and Management		
- <i>Is there a written company health and safety policy?</i> - If yes provide a copy of the policy		
- <i>Does the company have an OH&S Management system e.g NOSA, OHSAS, IRCA System etc</i> - If yes provide details		
- <i>Is there a company OH&S Management System, procedures manual or plan?</i> - If yes provide a copy of the content page(s)		
- <i>Are health and safety responsibilities clearly identified for all levels of Management and employees?</i> - If yes provide details		
2. Safe Work Practices and Procedures		
- Are safe operating procedures or specific safety instructions relevant to its operations available? - If yes provide a summary listing of procedures or instructions		
- Is there a register of injury document? If yes provide a copy		

<ul style="list-style-type: none"> - Are Risk Assessments conducted and appropriate techniques used? - If yes provide details 		
3. OH&S Training		
Describe briefly how health and safety training is conducted in your company:		
<ul style="list-style-type: none"> - Is a record maintained of all training and induction programs undertaken for employees in your company? - If yes provide examples of safety training records 		
4. Health and Safety Workplace Inspection		
<ul style="list-style-type: none"> - Are regular health and safety inspections at worksites undertaken? - If yes provide details 		
<ul style="list-style-type: none"> - Is there a procedure by which employees can report hazards at workplaces? - If yes provide details 		
5. Health and Safety Consultation		
<ul style="list-style-type: none"> - Is there a workplace health and safety committee? 		
<ul style="list-style-type: none"> - Are employees involved in decision making over OH&S matters? - If yes provide details 		
<ul style="list-style-type: none"> - Are there employee elected health and safety representatives? - Comments 		
6. OH&S Performance Monitoring		
<ul style="list-style-type: none"> - Is there a system for recording and analysing health and safety performance statistics including injuries and incidents? - If yes provide details 		
<ul style="list-style-type: none"> - Are employees regularly provided with information on company health and safety performance? - If yes provide details 		
<ul style="list-style-type: none"> - Is company registered with workmen's compensation and up to date? - If yes provide proof of letter of good standing 		

- Has the company ever been convicted of an occupational health and safety offence? - If yes provide details		

Safety Performance Report
Monthly DIFR for previous months

Previous Year	No of Disabling Injuries	Total Number of employees	DIFR per month
January			
February			
March			
April			
May			
June			
July			
August			
September			
October			
November			
December			

DIFR = Number of Disabling injuries x 200000 divided by number of man hours worked for the period

 Signed
 (Tenderer)

PROPOSED AMENDMENTS AND QUALIFICATIONS

The Tenderer should record any deviations or qualifications he may wish to make to the tender documents in this Returnable Schedule. Alternatively, a tenderer may state such deviations and qualifications in a covering letter to his tender and reference such letter in this schedule.

The Tenderer's attention is drawn to clause F.3.8 of the Standard Conditions of Tender referenced in the Tender Data regarding the employer's handling of material deviations and qualifications.

Page	Clause or item	Proposal

"PREVIEW COPY ONLY"

Signed _____ Date _____
Name _____ Position _____
Tenderer _____

TRANSNET SOC LIMITED
(REGISTRATION No. 1990/000900/06)
TRADING AS
TRANSNET FREIGHT RAIL

LABOUR PAYMENT SCHEDULE

TENDERERS ARE REQUIRED TO COMPLETE THE FOLLOWING SCHEDULE:

DAY LABOUR (IF REQUIRED)

Skilled Hour _____
Unskilled Hour _____
Labourer Hour _____
Driver/Operator Hour _____
% Profit on Material _____

TRANSPORT AND MACHINERY

	RUNNING	STANDING
1. Light vehicle up to 1 ton	_____	_____
2. 5 Ton vehicle	_____	_____
3. 10 Ton vehicle with crane	_____	_____
4. Crane	_____	_____
5. Scaffolding	_____	_____
6. Generator	_____	_____
7. Other equipment:	_____	_____

8. Full details of any other charges:

TENDERER: _____

DATE: _____

Contract Data

The Employer is

Name Transnet SOC Limited, Trading as Transnet Freight Rail

Address Pavillion Building, Room 19-21

Cnr Botha Avenue & Rhodes Streets

Witbank 1035

Telephone (013) 656 4296 **Fax No.** (013) 656 4259

E-mail Nhlanhla.Vilakazi@transnet.net

The works is **Supply, Install, Test And Commission Wave Filter Equipment And Associated Cables At Ngodwana 3kv Dc Substation, Under The Control Of Depot Engineering Manager, Nelspruit.**

The site is **Ngodwana Substation**

The starting date isafter receiving official order

The completion date is

The reply period is **2 (two) weeks.**

The defects date is **52 (FiftyTwo) weeks after completion**

The defect correction period is within **one week** after defects date

The delay damages are **R5 000,00** per day (penalties)

The assessment day is the **13th (thirteenth)** of each month

The retention is **10%**

Does the United Kingdom Housing Grants, Construction and Regeneration Act (1996) apply? **No**

The Adjudicator is

Name To be advised if disputes arise.....

Address

Telephone **Fax No.**

E-mail

Contract Data

The interest rate on late payment is % per complete week of delay.

The *Contractor* is not liable to the *Employer* for loss of or damage to the *Employer's* property in excess of..... for any one event.

The *Employer* provides this: **Insurance Transnet Principal Control Insurance**

The minimum amount of cover for the third insurance stated in the Insurance Table is:
>R25, 000.00 (Limited to R10, 000,000.00. for any one event)

The minimum amount of cover for the fourth insurance stated in the Insurance Table is:
Not applicable.....

The adjudicator nominating body is: **The Chairman of the Association of Arbitrators (Southern Africa)**

The tribunal is: **Arbitration**

If the tribunal is arbitration, the arbitration procedure is: **The rules for the Conduct of Arbitrators of the Association of Arbitrators (Southern Africa)**

The *conditions of contract* are the NEC3 Engineering and Construction Short Contract (June 2005) and the following additional conditions:

As mentioned in paragraph 1.0 (Contractual obligations)

1.0 CONTRACTUAL OBLIGATIONS

A compulsory clarification meeting with representatives of the Employer will take place on **Tuesday, 05 August 2014, 09H00 at Transnet – Maroela Boardroom, Andrew Street at Nelspruit Depot and thereafter proceed to the entire substations for physical site briefing.**

(For direction please contact: Joseph Majola on 083 277 8737).

[Respondent to provide own PPE, transportation and accommodation].

Tenders must be deposited to the Tender Box, which will be located in the foyer of INYANDA HOUSE, Transnet freight rail and shall be addressed as follows : Chairperson, Transnet Freight Rail Acquisition Council, Inyanda House, 21 Wellington Road, Parktown.

1Tenders must be enclosed in a sealed envelope bearing the tender number "MMC-WGO-12053 on the outside.

Please note that this tender closes punctually at **12 August 2014 at 10H00.**

- 1.1 The Contractor shall not make use of any sub-Contractor to perform the works or parts thereof without prior permission from the Project Manager.
- 1.2 The Contractor shall ensure that a safety representative is at site at all times.
- 1.3 The Contractor shall comply with all applicable legislation and Transnet safety requirements adopted from time to time and instructed by the Project Manager/ Technical Officer. Such compliance shall be entirely at his own cost, and shall be deemed to have been allowed for in the rates and prices in the contract.
- 1.4 The Contractor shall, in particular, comply with the following Acts and Transnet Specifications:-
 - 1.4.1 The Compensation for Occupational Injuries and Diseases Act, No. 130 of 1993. The Contractor shall produce proof of his registration and good standing with the Compensation Commissioner in terms of the Act.
 - 1.4.2 The Occupational Health and Safety Act (Act 85 of 1993).
 - 1.4.3 The explosive Act No. 26 of 1956 (as amended). The Contractor shall, when applicable, furnish the Project Manager/ Technical Officer with copies of the permits authorising him or his employees, to establish an explosives magazine on or near the site and to undertake blasting operations in compliance with the Act.
 - 1.4.4 The Contractor shall comply with the current Transnet Specification E.4E, Safety Arrangements and Procedural Compliance with the Occupational Health and Safety Act, Act 85 of 1993 and Regulations and shall before commencement with the execution of the contract, which shall include site establishment and delivery of plant, equipment or materials, submit to the Project Manager / Technical Officer.
 - 1.4.5 The Contractor shall comply with the current Specification for Works On, Over, Under or Adjacent to Railway Lines and near High Voltage Equipment – E7/1, if applicable, and shall take particular care of the safety of his employees on or in close proximity to a railway line during track occupations as well as under normal operational conditions.
- 1.5 The Contractor's Health and Safety Programme shall be subject to agreement by the Project Manager / Technical Officer, who may, in consultation with the Contractor, order supplementary and/or additional safety arrangements and/or different safe working methods to ensure full compliance by the Contractor with his obligations as an employer in terms of the Act.
- 1.6 In addition to compliance with clause 1.4 hereof, the Contractor shall report all incidents in writing to the Project Manager / Technical Officer. Any incident resulting in the death of or injury to any person on the works shall be reported within 24 hours of its occurrence and any other incident shall be reported within 48 hours of its occurrence.
- 1.7 The Contractor shall make necessary arrangements for sanitation, water and electricity at these relevant sites during the installation of the equipments.
- 1.8 A penalty charge of **R5 000,00** per day will be levied for late completion.

- 1.9 **10%** retention money will be retained and will be released 12 months after the completion date of the contract.
- 1.10 The Contractor shall supply a **site diary** (with triplicate pages). This book shall be used to record any unusual events during the period of the work. Any delays to the work shall also be recorded such as delays caused by poor weather conditions, delays caused by permits being cancelled etc. The appointed Technical Officer must countersign such delays. Other delays such as non-availability of equipment from 3rd party suppliers must be communicated to the Project Manager or Technical officer in writing.
- 1.11 The Contractor shall supply a **site instruction book** (with triplicate pages). This book shall be used to record any instructions to the Contractor regarding problems encountered on site – for example the quality of work or the placement of equipment. This book shall be filled in by the Project Manager or Technical Officer and must be countersigned by the Contractor.
- 1.12 Both books mentioned in 1.10 and 1.11 shall be the property of Transnet Freight Rail and shall be handed over to the Project Manager or Technical Officer on the day of energising or handing over.
- 1.13 All processes or the manufacture and assembly of the product components must be subjected to a quality assurance system.
- 1.14 The Contractor will assume full responsibility for assuring that the products purchased meet the requirements of Transnet Freight Rail for function, performance, and reliability, including purchased products from 3rd part suppliers/Manufacturers.
- 1.15 The Contractor shall prove to Transnet Freight Rail that his equipment or those supplied from 3rd party suppliers/manufacturers confirms to Transnet freight rail specifications.
- 1.16 The Contractor will remain liable for contractual delivery dates irrespective of deficiencies discovered during workshop inspections.

**Part C1:
Agreement and Contract Data**

"PREVIEW COPY ONLY"

Contract Data

The Contractor's Offer

The Contractor is

Name

Address

.....

Telephone **Fax No.**

E-mail

The percentage for overheads and profit added to the Defined Cost for people is..... %.

The percentage for overheads and profit added to other Defined Cost is..... %.

The Contractor offers to Provide the Works in accordance with the conditions of contract for an amount to be determined in accordance with the conditions of contract.

The offered total of the
Prices is(amount in words and
amount in numbers)

Signed on behalf of the Contractor

Name

Position

Signature **Date**

The Employer's Acceptance

The Employer accepts the Contractor's Offer to Provide the Works

Signed on behalf of the Employer

Name

Position

Signature **Date**

2.0 PRICING INSTRUCTIONS

1. The agreement is based on the NEC Engineering and Construction Short Contract 3. The contract specific variables are as stated in the contract data. Only the headings and clause numbers for which allowance must be made in the Price list are recited.
2. Preliminary and General Requirements are based on part 1 of SANS 1921, 'Construction and Management Requirements for Works Contracts'. The additions, deletions and alterations to SANS 1921 as well as the contract specific variables are as stated in the contract data. Only the headings and clause numbers for which allowance must be made in the Price list are recited.
3. It will be assumed that prices included in the Price list are based on Acts, Ordinances, Regulations, By-laws, International Standards and National Standards that were published 28 days before the closing date for tenders.
4. Reference to any particular trademark, name, patent, design, type, specific origin or producer is purely to establish a standard for requirements. Products or articles of an equivalent standard may be substituted.
5. The Price list is not intended for the ordering of materials. Any ordering of materials, based only on the Price list, is at the Contractor's risk.
6. The amount of the Preliminaries to be included in each monthly payment certificate shall be assessed as an amount prorated to the value of the work duly executed in the same ratio as the preliminaries bears to the total of prices excluding any contingency sum, the amount of the Preliminaries and any amount in respect of contract price adjustment provided for in the contract.
7. The amount or items of the Preliminaries shall be adjusted to take account of the theoretical financial effect which changes in time or value (or both) have on this section. Such adjustments shall be based on adjustments in the following categories as recorded in the Price list:
 - a) an amount which is not to be varied, namely Fixed (F).
 - b) an amount which is to be varied in proportion to the contract value, namely Value Related (V).
 - c) an amount which is to be varied in proportion to the contract period as compared to the initial construction period, excluding revisions to the construction period for which no adjustment the contractor is entitled to in terms of the contract, namely Time Related (T).
8. The following abbreviations are used in the Price list:

Hr	=	Hour
Ea	=	Each
OCB	=	Oil Circuit Breaker
GCB	=	Gas Circuit Breaker
PCB	=	Polychlorinated Biphenyl
Quant.	=	Quantity
9. The prices and rates in these Price list are fully inclusive prices for the work described under the items. Such prices and rates cover all costs and expenses that may be required in and for the execution of the work described in accordance with the provisions of the scope of work and shall cover liabilities and obligations set forth or implied in the Contract data, as well as profit.
10. Where the scope of work requires detailed drawings and designs or other information to be provided, all costs associated therewith are deemed to have been provided for and included in the unit rates and sum amount tendered for such items.
11. Where no quantity has been provided against an item in the Price list, the Contractor shall use their discretion and provide the quantity.

- 12 The quantities set out in these Price list are approximate and do not necessarily represent the actual amount of work to be done. The quantities of work accepted and certified for payment will be used for determining payments due and not the quantities given in these Price list.
- 13 The short descriptions of the items of payment given in these Price list are only for purposes of identifying the items. More details regarding the extent of the work entailed under each item appear in the Scope of Work.
- 14 Tenderers shall ensure that provision (financial as well as time) for excavations in a range of soil types is made for in their tenders.
- 15 For each item in the Price list, including Preliminaries, the Contractor shall provide in the appropriate column the portion of the tendered sum (inclusive of labour and material) which has been sourced locally (Republic of South Africa).
- 16 The Contractor shall also arrange forward cover within two weeks after contract award on all imported items.
- 17 The Contractor shall provide information related to imported content, i.e. equipment to be imported, value and applicable exchange rates. This information shall be provided as an Annexure to the Price list.
- 18 The total in the Price list shall be exclusive of VAT.

"PREVIEW COPY ONLY"

"PREVIEW COPY ONLY"

**Part C2:
Pricing Data**

Contract Data Price List

Item	Description	Unit	Qu	Rate	Price
A	Ngodwana 3kV Dc substation				
1	Dismantle, remove and dispose accordingly the old wave filter equipment.	sum	1		
2	Supply and install new wave filter equipment and associated cables.	sum	1		
3	Redo complete earthing	sum	1		
4	Pre-testing and Pre-commissioning.	sum	1		
5	Catalogues, manuals and drawings.	sum	1		
6	P's and G's (Labour, site establishment, civil work, etc.).	sum	1		
A	Sub Total for Ngodwana substation =				
B	10% Retention=				
C	VAT (14% of A) =				
D	Gross Total (A + C) =				

**Part C3:
Scope of Work**

"PREVIEW COPY ONLY"

Contract Data

Scope of Work

3.0 DESCRIPTION OF WORKS

3.1 EMPLOYER'S OBJECTIVE

3.1.1 The main objective of Transnet Freight Rail is to replace the old wave filter equipment with new one.

3.2 EXTENT OF THE WORKS

The contractor shall perform the following:

3.3 NGODWANA 3KV SUBSTATION

1. The contractor shall supply and install the wave filter equipment in accordance with Transnet Freight Rail specification BBB 3139 for wave filter capacitors and BBB 3162 for inductor coils.
2. A wave filter is connected in parallel with the rectifier output. The filter unit is a capacitive inductive circuit, which is tuned to resonate at specific harmonic frequencies.
3. The filter equipment shall be so designed that no individual harmonic voltage is greater than 2% of the output voltage.
4. The inductor coils shall have sufficient adjustment to compensate for change in the capacitance values due to ageing. Refer to Transnet Freight Rail's drawing BBB3483 for assembly.
5. A 100 Ampere High Rupturing Capacity (H.R.C) fuse shall be fitted to protect the wave filter equipment.
6. The fuse holder shall be mounted on insulators.
7. The insulators shall be so designed that the flashover path is not less than 100mm and shall support the fuse at a distance of not less than 100mm from the bolts securing the base plate. The insulators shall have a minimum dry flashover value of 20kV.
8. Access to the wave filter equipment shall only be possible once the wave filter capacitors have been connected to rail, discharged and the primary circuit breaker tripped. A 75 kilo ohms resistor consisting of two 150 kilo ohms, 150 watts vitreous enamel resistors connected in parallel shall be provided for the discharging of the wave filter capacitors when the equipment is isolated and earthed.
9. The discharge resistors shall be mounted on a suitable insulation panel or bar, which shall be insulated for 3kV Dc. A minimum clearance of 75mm must be provided between the terminals, and 100mm between any 3kV live portion of the equipment and earth.
10. The wave filter capacitors shall be earthed with 95mm² PVC insulated copper cables to the DC earth leakage system.

3.4 STEELWORK

3.4.1 The design, supply and installation of all steel structures for the support of equipment shall be the responsibility of the Contractor. This shall be in accordance with Transnet freight rail specification CEE.0183.2002.

3.4.2 The manufacture of any steelwork shall not take place prior to the approval of the design drawings by the Project Manager/ Technical Officer.

3.4.3 Transnet Freight Rail shall inspect the steelwork at the manufacturers works prior to dispatch.

3.4.4 All fasteners (nuts & bolts) shall be secured using flat and spring washers where necessary.

3.4.5 All steelwork shall be galvanized in accordance with SANS 121 and, where required painted in accordance with specification CEE 045 of 2002/1.

4 INSTALLATION

4.1 The Contractor shall be responsible for the transport to site, off-loading, handling, and storage of all material required for the construction/execution of the works.

4.2 All fasteners on steelwork, components and electrical connections (nuts and bolts) shall be secured using flat as well as lock washers.

4.3 Contractor shall supply multi core cable and re-connect the tele-control that is currently available in the substation. The substation shall not be switched on unless the tele-control is fully operational.

5 INTERCONNECTION OF EQUIPMENT

5.1 High conductive silicon grease shall be liberally applied to all the connections.

5.2 All dissimilar metal connections (Cu to Al) shall be made using bi-metallic clamps that are specifically designed and manufactured to make that particular connection (ad hoc fabricated clamps are not acceptable).

6 DISPOSAL AND TREATMENT OF OIL AND OIL FILLED EQUIPMENT

6.1 The collection, handling and disposal of oil from the OCBs and VTs from the substation shall be done in a safe and environmentally sound manner.

6.2 Unless any equipment to be replaced containing oil is clearly certified PC free, the Contractor shall test or make arrangements for the testing of the equipment oil for Polychlorinated Biphenyls (PCBs) before replacing the equipment and submit the results to Transnet Freight Rail.

6.3 This will be done by first conducting preliminary screening chlorine tests and where the levels of chlorine presence are above 50ppm, further detailed PCB tests and analyses shall be conducted.

6.4 The units with levels of contamination less than 20ppm Chlorine shall be disposed of following the normal disposal procedure.

6.5 Any units with residual PCB pollution, or oils contaminated to a level greater than 50ppm shall be treated as PCB ITEMS.

6.6 Equipment and oil with a PCB content of between 20 and 49 PPM is classified as 'mildly contaminated' and shall be properly identified, i.e. marked with yellow stickers, and disposed of as contaminated.

6.7 In case of PCB items being identified, handling and disposal of the equipment shall be done in accordance to "A Manual and Guidelines for Management of Polychlorinated Biphenyls in Transnet Freight Rail".

6.8 Approved degreasing agents on concrete surfaces shall be used, if required.

6.9 The costs for the screening chlorine test and provisional analyses of oils and soil for PCB's, the tests and analysis of soil to determine the levels where spillages has occurred, must be furnished by the tenderers.

6.10 The Tenderer shall provide a provisional method statement and cost for the legal disposal of PCB items, such methodology and costing becoming applicable only in the event of PCB items requiring disposal, as specified, being required.

6.11 The old equipment that is not contaminated shall be transported by the Contractor to Transnet Freight Rail's Nelspruit Depot and scrapped by Transnet Freight Rail following normal Procedures.

6.12 The disposal of any PCB items shall be by thermal destruction method; encapsulation method is not permitted.

7 SITE TESTS

- 7.1 The equipment shall be inspected/ tested and approved by Transnet Freight Rail Quality Assurance at the Contractor's workshop prior to it being taken to site. Only once the approval has been granted can the equipment be taken to site for installation.
- 7.2 The Contractor shall be responsible for carrying out of on-site tests and commissioning of all equipment supplied and installed in terms of this specification and the contractual agreement.
- 7.3 Functional on-site tests shall be conducted on all items of equipment and circuitry to prove the proper functioning and installation thereof.
- 7.4 The Contractor shall submit a detailed list of on-site tests for the approval of the Project Manager or Technical Officer.
- 7.5 The Contractor shall arrange for the Technical Officer or his representative to be present to witness the on-site tests.
- 7.6 The on-site tests and subsequent commissioning **will not commence until ALL CONSTRUCTION** work has been completed. Construction staff, material and equipment shall be removed from site prior to the commencement of testing. Testing and commissioning of the power plants equipment will not be allowed to take place in a construction site environment.
- 7.7 The on-site tests shall include the following:
- 7.7.1.1 Test for the functionality of all electrical circuitry.
 - 7.7.1.2 Trip tests on relays.
 - 7.7.1.3 Test on equipment as per manufacturer's instructions.
 - 7.7.1.4 Insulation tests.
- 7.8 At the completion of the on-site tests, the Project Manager or Technical Officer or his representative shall either sign the tests sheets (supplied by the Contractor) as having

witnessed the satisfactory completion thereof, or hand to the Contractor a list of defects requiring rectification.

- 7.9 Upon rectification of defects, the Contractor shall arrange for the Project Manager or Technical Officer or his representative to certify satisfactory completion of on-site tests.
- 7.10 Acceptance by the Project Manager or Technical Officer of satisfactory completion of on-site tests in no way relieves the Contractor of his obligation to rectify defects which may have been overlooked or become evident at a later stage.

8 COMMISSIONING OF EQUIPMENT

- 8.1 Commissioning will only take place after all defects have been rectified to the satisfaction of the Project Manager or Technical Officer.
- 8.2 On completion of commissioning, the Contractor will hand the equipment over to the Project Manager or Technical Officer in terms of the relevant instruction.
- 8.3 The commissioning of protection equipment by Transnet Freight Rail will in no way absolve the Contractor from any of his responsibilities during the guarantee period.
- 8.4 It is the Contractor's responsibility to satisfy himself or herself that the commissioning of the protection equipment has been carried out in a satisfactory manner, and in no way compromises the proper operation of the equipment supplied in terms of the contract.
- 8.5 The Contractor shall be present during the testing and setting of the protection to rectify any faults found.

9 GUARANTEE AND DEFECTS

- 9.1 The Contractor shall guarantee the satisfactory operation of the complete electrical installation supplied and erected by him and accept liability for maker's defects that may appear in design, materials and workmanship.
- 9.2 The Contractor shall be issued with a completion certificate with the list of all defects to be repaired within 48 hours after commissioning.
- 9.3 The guarantee period for this series breaker shall expire after: A period of 12 months commencing on the date of completion of the contract or the date the series breaker was handed over to Transnet Freight Rail.
- 9.4 Any defects that may become apparent during the guarantee period shall be rectified to the satisfaction of Transnet Freight Rail, and to the account of the Contractor.
- 9.5 The Contractor shall undertake work on the rectification of any defects that may arise during the guarantee period within 7-days of him being notified by Transnet Freight Rail of such defects.
- 9.6 Should the Contractor fail to comply with the requirements stipulated above, Transnet Freight Rail shall be entitled to undertake the necessary repair work or effect replacement of defective apparatus or materials, and the Contractor shall reimburse Transnet Freight Rail the total cost of such repair or replacements, including the labour costs incurred in replacing defective material.
- 9.7 Any specific type of fault occurring three times within the guarantee period and which cannot be proven to be due to other faulty equipment not forming part of this contract e.g., faulty locomotive or overhead track equipment, etc., shall automatically be deemed an inherent defect. Such inherent defect shall be fully rectified to the satisfaction of the Project Manager or Technical Officer and at the cost of the Contractor.

- 9.8 If urgent repairs have to be carried out by Transnet Freight Rail staff to maintain supply during the guarantee period, the Contractor shall inspect such repairs to ensure that the guarantee period is not affected and should they be covered by the guarantee, reimburse Transnet Freight Rail the cost of material and labour.

10 QUALITY AND INSPECTION

- 10.1 Transnet Freight Rail shall inspect the equipment under contract on the premises of the Manufacturer or successful Contractor.
- 10.2 The Contractor shall notify Transnet Freight Rail 14 days in advance of such an inspection date.
- 10.3 The Contractor shall apply 14 days in advance for the date of energizing and ensure that all work is completed before any commissioning can take place.
- 10.4 The Contractor shall be responsible to issue a compliance certificate in terms of SANS 0142 for each site before energizing of the equipment shall take place.

"PREVIEW COPY ONLY"

**Part C3:
Works Information**

"PREVIEW COPY ONLY"

Contract Data

Works Information

12. Specifications

Unless otherwise specified all material and equipment supplied shall comply with the current edition of the relevant SANS, BS, IEC or Transnet Freight Rail publication where applicable.

The following standard specifications will be applicable to this contract.

12.1 South African National Standards:

- 12.1.1 SANS 1091 National colour standard.
- 12.1.2 SANS 763 Hot dip galvanised zinc coating.
- 12.1.3 SANS 121 Hot Dip Galvanised Coating for Fabricated Iron or Steel Article.
- 12.1.4 SANS 10142 Wiring Code.

12.2 British Standards

- 12.2.1 BS 37: Electricity meters
- 12.2.2 BS 3938: Specification for current transformers.

12.3 IEC Standards

- 12.3.1 IEC 60051: Direct acting analogue electrical measuring instruments.
- 12.3.2 IEC 60243: Electrical strength of insulating material.

12.4 South African National Standards

- 12.4.1 SANS 109: National colour standards for paint.
- 12.4.2 SANS 1019: Standard voltages, currents and insulating levels for electrical supply.
- 12.4.3 SANS 62271-100: High voltage switchgear and control gear.
- 12.4.4 SANS 60044-1: Instrument transformers-Current Transformers.
- 12.4.5 SANS 60060: High voltage test techniques.

12.5 Transnet Freight Rail

- 12.5.1 BBB 3139 Ver-1: Wave filter capacitors for 3kV Dc traction substations
- 12.5.2 BBC 0198 Ver-1: Specifications for requirements for the supply of electrical cables.
- 12.5.3 CEE.0023.90: Specifications for the installation of cables.
- 12.5.4 CEE.045: Painting of steel Components of Electrical Equipments.
- 12.5.5 CEE.0183.2002: Hot dip galvanising and painting of electrification steelwork.
- 12.5.6 CEE.0224.2002: Drawings, catalogues, instruction manuals and spares list for electrical equipment supplied under contract.
- 12.5.7 CEE-PA-13: Drawing for test block.
- 12.5.8 CEE-PA-56: Connection diagram for protection relays to CTs.
- 12.5.9 BBB 3162 ver-1: Wave filter inductors for 3kV Dc traction substations.
- 12.5.10 BBB5452 ver-6: Transnet Freight Rail's requirements for the installation of electrical equipment for 3kV dc traction substations

NOTE: Any other specifications referenced in the above mentioned specification, will be for information purposes and may be provided on request.

Occupational Health and Safety Act No. 85 of 1993 (Available at depot for referral)

13.0 Constraints on how the *Contractor* Provides the Works

The constraints shall be as specified in the specifications of the particular equipment.

14.0 It is required of the tenderer to submit the following information for evaluation purposes. Transnet Freight Rail reserves the right to disqualify tenders with incomplete information.

- CIDB registration
- VAT registration certificate
- BBB-EE certificate
- Letter of Good Standing
- Delivery period for service or product (From date of offer).
- Rate of exchange to be specified if applicable.
- Qualifications of personnel who are going to perform the work.

NB: Qualified electrician with wireman's licence and Electrical Engineering Technician registered with ECSA are compulsory. Safety representative must have at least level 2 first aid.

15.0 Requirements for the programme

Programme of work	:	To be submitted by successful Contractor
Format	:	Bar chart
Information	:	How work is going to be executed and commissioned
Submission	:	Not Applicable
Site diary	:	Successful Contractor to supply in triplicates carbon copies

16.0 Services and other things provided by the *Employer*

16.1 Transnet Freight Rail shall have an electrician available for isolation and the erection of barriers to live electrical equipment and issuing of work permits.

16.2 Upon successful completion of the works to the satisfaction of Transnet Freight Rail, Transnet Freight Rail shall perform necessary protection tests and commission the equipment.


"PREVIEW COPY ONLY"

Contract Data

Site Information

The works shall be performed at **Ngodwana 3kV Dc Traction substation**

"PREVIEW COPY ONLY"



A division of Transnet limited

**TECHNICAL
RAILWAY ENGINEERING**

SPECIFICATION CONTROL PAGE

WAVE FILTER CAPACITORS FOR 3kV DC TRACTION SUBSTATIONS


Statement of authorisation:

There is no SABS specification available for similar material / equipment and as far as can be ascertained no other specification / standard suitably covers Spoomet requirements. The specification has been compiled in a manner which shall favour / encourage local manufacture of material / equipment to a maximum degree.

Author:	Engineer Traction Power Supply Technology	S. Nhlabathi
Co-author:	Chief Engineering Technician Traction Power Supply Technology	J. Rothman
Approved:	Senior Engineer Traction Power Supply Technology	L.O.Borchard
Authorised:	Principal Engineer Railway Engineering: Electrical Technology	W.A Coetzee

Date: 05 August 2002

This page is for control purposes only and shall not be issued with the specification.



A division of Transnet limited

**TECHNICAL
RAILWAY ENGINEERING
SPECIFICATION**

WAVE FILTER CAPACITORS FOR 3kV DC TRACTION SUBSTATIONS

Circulation restricted to:

- Technical
- Railway Engineering
 - Asset Life Cycle Management
 - Infrastructure Maintenance
 - Acquisition, Evaluation and Review

© This document as a whole is protected by copyright. The information herein is the sole property of Transnet Ltd. It may not be used, disclosed or reproduced in part or in whole in any manner whatsoever, except with the written permission of and in a manner permitted by the proprietors.

INDEX

1.0 SCOPE	4
2.0 STANDARDS AND PUBLICATIONS	4
3.0 TENDERING PROCEDURE	4
4.0 DEFINITIONS	4
5.0 SERVICE CONDITIONS	5
5.1 ATMOSPHERIC CONDITIONS	5
5.2 MECHANICAL SERVICE CONDITIONS	5
5.3 ELECTRICAL SERVICE CONDITIONS	5
6.0 POWER FILTER CAPACITORS	5
6.1 GENERAL	5
6.2 CAPACITOR RATINGS	6
6.3 ADMISSIBLE OVERLOADS	7
6.4 RATING PLATE	7
6.5 INSULATION	7
6.6 LIFE EXPECTANCY OF THE CAPACITOR	7
6.7 TESTS	8
7.0 QUALITY ASSURANCE	8
8.0 GUARANTEE AND DEFECTS	8
9.0 PACKAGING AND TRANSPORT	8
APPENDIX A	9
APPENDIX B	10

"PREVIEW COPY ONLY"

1.0 SCOPE

- 1.1 This specification covers Spornet's requirements for the supply of wave filter capacitors, required for DC applications such as harmonic filters.
- 1.2 The capacitors shall be used with the resonant shunts to reduce the magnitude of the 6th, 12th, 18th and the 24th harmonics at the busbar of the 3 000 V DC rectifier traction substation.

2.0 STANDARDS AND PUBLICATIONS

- 2.1 Unless otherwise specified all materials used and equipment developed and supplied shall comply with the current edition of the relevant SABS, IEC or Spornet's publications where applicable.
- 2.2 The following publications are referred to in this specification:
 - IEC 6871 – 1 (1997) : Shunt capacitors for AC power systems having a rated voltage above 1 000V.
 - CEE TCK 004 : Wave filter cell layout.

3.0 TENDERING PROCEDURE

- 3.1 The tenderer shall indicate compliance with the specification. This shall take the form of a separate document listing all the clause numbers of the specification with an individual clause by clause statement of compliance or non-compliance.
- 3.2 The tenderer shall motivate a statement of non-compliance.
- 3.3 The tenderer shall submit descriptive literature consisting of detailed technical specifications, general construction details and principal dimensions, together with clear illustrations of the equipment offered.
- 3.4 The tenderer shall complete and submit the technical data sheet in appendix B.

4.0 DEFINITIONS

- 4.1 The definitions of all the technical terms used in this specification are listed in clause 3 of the IEC 6871 – 1 (1997) specification.

5.0 SERVICE CONDITIONS

5.1 ATMOSPHERIC CONDITIONS

- 5.1.1 Altitude : 0 to 1800m above sea level.
- 5.1.2 Ambient Temperature : -5 to +45 °C (daily average +35 °C).
- 5.1.3 Relative Humidity : As high as 90 percent (Condensing).
- 5.1.4 Lightning Conditions : 12 ground flashes per square kilometre per annum.
- 5.1.5 Pollution : Heavily salt laden or polluted with smoke from industrial sources.

5.2 MECHANICAL SERVICE CONDITIONS

- 5.2.1 The 3kV DC traction substations are situated next to railway lines and the equipment will therefore be subjected to vibration. The design must take appropriate counter measures to ensure reliability of equipment that is sensitive to vibration.
- 5.2.2 The capacitors are to be installed in the 3kV DC traction substations and shall be floor mounted.

5.3 ELECTRICAL SERVICE CONDITIONS

- 5.3.1 The nominal no-load DC voltage of a traction substation output varies between 3150 V and 3400 V.
- 5.3.2 The maximum voltage under no-load conditions can increase up to 3900 V depending on the traction transformer tap settings, Eskom's supply voltage and regenerative braking.
- 5.3.3 The substation voltage under load conditions may decrease to 2300 V.

6.0 POWER FILTER CAPACITORS

6.1 GENERAL

- 6.1.1 The capacitors are to form part of the resonant shunt connected to the positive and negative busbar to reduce the magnitude of the following harmonics:
- 6th at 300Hz,
 - 12th at 600Hz,
 - 18th at 900Hz,
 - 24th at 1200Hz.
- 6.1.2 Substations with 12-pulse rectification are normally tuned for 12th and 24th harmonics at 600Hz and 1200Hz, respectively. The 6-pulse type rectifier substations are normally equipped with 300Hz and 900Hz filters to reduce the effect of the 6th and 18th harmonics.

- 6.1.3 The design, construction and operation of the capacitors shall comply with the IEC 6871 – 1 (1997) specification.
- 6.1.4 A dielectric made from Polyester / Polypropylene film (PPR) is preferable.
- 6.1.5 The capacitor container shall be constructed of steel or stainless steel and shall have adequate mechanical strength to avoid bulging or bursting.
- 6.1.6 If lifting lugs are required each capacitor container shall be provided with two lugs.
- 6.1.7 Each capacitor container shall be provided with an earthing lug drilled for a 10-mm screw.
- 6.1.8 The capacitor container shall be hermetically sealed. Moisture and electrical environmental interference shall have no effect on the capacitor.
- 6.1.9 Each capacitor shall be provided with two bushings, one for each pole. The creepage and air clearance of the bushings shall not be less than 200 mm between the live parts of the bushings, the metal base of the container and between the bushing terminals.
- 6.1.10 The basic insulation level (BIL) for the bushings shall be at least 100kV.
- 6.1.11 The capacitors shall be immersed in a non-flammable, non-toxic and biodegradable insulating medium and sealed under vacuum.
- 6.1.12 The positioning of the capacitors in the wave filter cell is shown in drawing CEE TCK 004.
- 6.1.13 The capacitor shall have an integral discharge resistor.
- 6.1.14 The wave filter equipment in the traction substation is connected in series to a 100A fuse.

6.2 CAPACITOR RATINGS

6.2.1 The capacitors shall be made up of the following units:

- 10 MicroFarad - 80 ampere continuous,
- 20 MicroFarad - 80 ampere continuous,
- 50 MicroFarad - 80 ampere continuous.

The quantities required of the above values are dependent on the substation rectifier arrangement (12-pulse or 6-pulse rectification).

- 6.2.2 The capacitor shall be rated to handle up to four and one third (13 000 V) of the full load voltage (3kV) for one minute.
- 6.2.3 The capacitance tolerance of each capacitor shall not vary by more than 5% at 45 °C. Tenderers shall state and guarantee the tolerance of the capacitors offered.
- 6.2.4 Tenderers are requested to state the following:
- Maximum permissible voltage of the capacitor,
 - Maximum permissible current of the capacitor, as per requirement of clauses 19 and 20 of the IEC 6871 – 1 (1997) specification.

6.3 ADMISSIBLE OVERLOADS

- 6.3.1 The continuous rated excess voltage shall be at least 20% of the full load voltage (3 kV).
- 6.3.2 The excess continuous current rating shall be at least 50% of the rated current.
- 6.3.3 The rated kilo-Volt-Ampere reactive (kVAr) power shall be at least 40% of the rated power.

6.4 RATING PLATE

- 6.4.1 A non-corrosive metal nameplate shall be fixed to each capacitor container giving the following information:
 - Manufactures Name,
 - Identification Number,
 - Continuously Rated AC Current,
 - Rated DC Voltage,
 - Temperature Category,
 - Insulating Medium,
 - Insulating Level,
 - Measured Capacitance in MicroFarad.
- 6.4.2 The nameplate shall be positioned such that it is visible in the position of normal service and installation.

6.5 INSULATION

- 6.5.1 All capacitors shall be insulated to withstand a pressure of not less than 20 000 volts DC for one minute between the terminals. This must also be applicable between the short-circuited terminals and the container.
- 6.5.2 Tenderers are requested to state the expected deterioration pattern of the dielectric of the capacitors with time, while in service, and the test voltages that can be applied to the capacitors approximately six months after the manufacture's tests.

6.6 LIFE EXPECTANCY OF THE CAPACITOR

- 6.6.1 The capacitor shall have a rated life expectancy of not less than 20 years (175 000 working hours).

6.7 TESTS

- 6.7.1 The capacitors shall be subjected to the test requirements as set out in clause 5 of the IEC 6871 – 1 (1997) specification.
- 6.7.2 All the types of tests as classified in clause 6 of the IEC 6871 – 1 (1997) specification shall be conducted on each type of capacitor offered.
- 6.7.3 A TYPE TEST certificate shall be submitted for each type of capacitor offered.
- 6.7.4 The tender shall also submit routine test certificates for each capacitor offered.

7.0 QUALITY ASSURANCE

- 7.1 Spoomet reserves the right to carry out inspection and any tests on the equipment at the works of the supplier/ manufacture.
- 7.2 Arrangements will be made timeously for such inspections to be carried out before the delivery of the equipment.

8.0 GUARANTEE AND DEFECTS

- 8.1 The tenderer shall guarantee the satisfactory operation of the equipment supplied by him and accept liability for maker's defects, which may appear in design, materials and workmanship.
- 8.2 The guarantee period for the equipment shall expire after: A period of 12 months commencing on the date of installation and commissioning of the equipment or the date the equipment is handed over to Spoomet whichever is the later.

9.0 PACKAGING AND TRANSPORT

- 9.1 The tenderer shall ensure that the equipment be packed in such a manner that it will be protected during handling and transport.
- 9.2 The tenderer shall provide transport for the delivery of the equipment to the site where required.

END

APPENDIX A

SCHEDULE OF REQUIREMENTS

(To be filled in by Spoorinet's Maintenance Depot or Logistics Department)

1. CAPACITORS

1.1 10 MicroFarad

• Quantity Required: _____

1.2 20 MicroFarad

• Quantity Required: _____

1.3 50 MicroFarad

• Quantity Required: _____

2. MAINTENANCE DEPOT

2.1 Depot Name: _____

2.2 Depot Address: _____

END



"PREVIEW COPY ONLY"

APPENDIX B
TECHNICAL DATA SHEET


(To be filled in by Tenderer)

- Capacitance Value (C_N): _____
- Capacitance Tolerance: _____
- Detailed Description of Capacitor: _____
- Overall Mass of the Capacitor: _____
- Overall Dimensions of the Capacitor: _____
- Dielectric Insulating Medium: _____
- Container Material: _____
- Rated Current in RMS (I_N): _____
- Rated Voltage in RMS (U_N): _____
- Rated Output (Q_N): _____
- Temperature Category: _____
- Maximum Permissible AC Current: _____
- Maximum Permissible AC Voltage: _____
- Maximum Permissible Temperature: _____
- Capacitor Losses: _____
- Active Power: _____
- Steady State Condition: _____
- Residual Voltage: _____
- BIL (Bushing): _____
- Life Expectancy: _____

END



SECTION A - A



- NOTES
1. FOR SMALL AND LARGE COILS SEE DIMENSION "D" ON DRG NO BBB3483 ITEMS 2 & 3.
 2. CAPACITY OF ASSOCIATED CAPACITORS TO BE STENCILLED ON COIL SHEET.
 3. FOR FRAMEWORK FOR SUPPORTING WAVE FILTER HARMONIC COILS SEE DRG NO BBB3485
 4. FOR SUPPORT BRACKET FRAMEWORK FOR WAVE FILTER HARMONIC COILS SEE DRG NO BBB3499
 5. FOR DETAILS OF COIL WINDINGS SEE DRG NO BBB3486
 6. FOR SPECIFICATION SEE DOCUMENT NO BBB3162

ITEM NO	DESCRIPTION	QTY	STORAGE ITEM NO	DRAWING NO
1	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
2	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
3	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	4		
4	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
5	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
6	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
7	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
8	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
9	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
10	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
11	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
12	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
13	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
14	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
15	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
16	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
17	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
18	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
19	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
20	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
21	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
22	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
23	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
24	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
25	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
26	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
27	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
28	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
29	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
30	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
31	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
32	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
33	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
34	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
35	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
36	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
37	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
38	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
39	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
40	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
41	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
42	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
43	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
44	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
45	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
46	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
47	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
48	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
49	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
50	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
51	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
52	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
53	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
54	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
55	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
56	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
57	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
58	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
59	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
60	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
61	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
62	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
63	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
64	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
65	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
66	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
67	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
68	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
69	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
70	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
71	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
72	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
73	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
74	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
75	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
76	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
77	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
78	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
79	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
80	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
81	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
82	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
83	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
84	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
85	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
86	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
87	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
88	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
89	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
90	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
91	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
92	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
93	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
94	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
95	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
96	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
97	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
98	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
99	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		
100	WASHER BRASS 1/4" X 1/4" X 1/8" 304 SS	2		

© COPYRIGHT PROTECTED

DWG REF : 0002183
 ECP REF : 2002-072
 DRAWN BY : JR Anthony
 CHECKED : JD van Dijk

SCALE : 1:2
 ITEM NO : -

DIMENSIONS : mm
 TOLERANCE : LIN ± .000 ANG ± .000




VERSION INFO : REDRAWN, DRG NO WAS ERW4E-C0-240

DATE : -
 APPROVED : -
 AUTHORIZED : -

CENTRAL DRAWING OFFICE

SPOORNET
 BBB3483
 VERSION 1

WAVE FILTER HARMONIC COIL CARRIER ASSEMBLY
 3KV DC SUBSTATION




- NOTES:
1. SEE SCHEDULE FOR JOINTING PRACTICES TO BE FOLLOWED.
 2. ALL WELDS SHALL BE FULL PENETRATION WELDS.
 3. WELDS SHALL BE MADE IN ACCORDANCE WITH THE REQUIREMENTS OF THE CODE.
 4. DIMENSIONS SHALL BE IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.
 5. DIMENSIONS SHALL BE IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.
 6. DIMENSIONS SHALL BE IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.
 7. DIMENSIONS SHALL BE IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.
 8. DIMENSIONS SHALL BE IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.
 9. DIMENSIONS SHALL BE IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.
 10. DIMENSIONS SHALL BE IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.


NO.	DESCRIPTION	QTY	ISSUES	DATE	BY	CHKD BY
1	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
2	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
3	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
4	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
5	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
6	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
7	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
8	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
9	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
10	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			

NO.	DESCRIPTION	QTY	ISSUES	DATE	BY	CHKD BY
1	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
2	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
3	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
4	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
5	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
6	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
7	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
8	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
9	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			
10	WAVE FILTER COILS (SANDWICH TYPE) - 1000 x 1000 x 2000	2	1			


DRAWING NO: **BBB3485**
 REVISION: **1**
 PROJECT: **SPOURNET**
 TITLE: **SUPPORTING WAVE FILTER HARMONIC COILS**
 SUBTITLE: **3KV DC TRACTION SUBSTATION**
 DATE: **01/11/2011**
 DRAWN BY: **JR**
 CHECKED BY: **JR**
 APPROVED BY: **JR**
 SCALE: **1:1**
 SHEET NO: **1** OF **1**
 PROJECT NO: **BBB3485**
 DRAWING NO: **BBB3485**
 REVISION: **1**
 PROJECT: **SPOURNET**
 TITLE: **SUPPORTING WAVE FILTER HARMONIC COILS**
 SUBTITLE: **3KV DC TRACTION SUBSTATION**
 DATE: **01/11/2011**
 DRAWN BY: **JR**
 CHECKED BY: **JR**
 APPROVED BY: **JR**



NOTE 1



SECTION A - A



- NOTES
1. FOR SMALL AND LARGE COILS SEE DIMENSION "D" ON DRG NO BB33484 ITEMS 2 & 3.
 2. CAPACITY OF ASSOCIATED CAPACITOR TO BE STENCILED ON COIL CHEEK.
 3. FOR FRAMEWORK FOR SUPPORTING WAVE FILTER HARMONIC COILS SEE DRG NO BB33485.
 4. FOR SUPPORT BRACKET FRAMEWORK FOR WAVE FILTER HARMONIC COILS SEE DRG NO BB33489.
 5. FOR DETAILS OF COIL WINDINGS SEE DRG NO BB33488.
 6. FOR SPECIFICATION SEE DOCUMENT NO BB33162.

ITEM NO	DESCRIPTION	QTY	STORES ITEM NO	DRAWING NO
1	WASHER BRASS 1/4" X 1/2" X 1/8" D.I.D. A16	2		BB33484 ITEM 1
2	WASHER BRASS 1/4" X 1/2" X 1/8" D.I.D. A16	2		BB33484 ITEM 1
3	NUT BRASS 1/4" X 1/2" X 1/8" D.I.D. A16	2		BB33484 ITEM 2
4	WASHER BRASS 1/4" X 1/2" X 1/8" D.I.D. A16	2		BB33484 ITEM 1
5	NUT BRASS 1/4" X 1/2" X 1/8" D.I.D. A16	2		BB33484 ITEM 2
6	CHEESE HEAD BUSH SCREW 3/16" X 1/2" X 3/16" D.I.D. A16	2		BB33484 ITEM 3
7	WASHER BRASS 1/4" X 1/2" X 1/8" D.I.D. A16	2		BB33484 ITEM 1
8	NUT BRASS 1/4" X 1/2" X 1/8" D.I.D. A16	2		BB33484 ITEM 2
9	WOODS CREW BRASS NO. 1756	2		BB33484 ITEM 4
10	ROUNDED WOOD 3/4" X 1/2" X 1/2" D.I.D. A16	2		BB33484 ITEM 5
11	THREADED CLIPPING 1/2"	2		BB33484 ITEM 6
12	SPACER	2		BB33484 ITEM 7
13	CLAMPING ROD 1/2"	2		BB33484 ITEM 8
14	CLAMPING ROD 1/2"	2		BB33484 ITEM 8
15	COIL CHEEK	2		BB33484 ITEM 1

PREVIEW COPY ONLY

© COPYRIGHT PROTECTED

SCALE : 1:2
ITEM NO : -

DIMENSIONS : mm
TOLERANCE : ±0.15 mm

VERSION INFO : REDRAWN DRG NO WAS ENH4E1G-240

DESIGNER : J.M. VAN DIJK
CHECKER : J.M. VAN DIJK

DATE

DDP REF : CD02193
ECP REF : 2005072
DESIGNED BY : J.M. VAN DIJK
CHECKER : J.M. VAN DIJK

APPROVED


APPROVED

CENTRAL DRAWING OFFICE

WAVE FILTER HARMONIC COIL CARRIER ASSEMBLY
3KV DC SUBSTATION

SPOURNET
BBB33483
VERSION 1

SPOOL AND WINDING DETAILS



PARTICULARS OF WIRE:-
 STRANDING: 37/1,1176 DOUBLE BRAIDED.
 CROSS SECTIONAL AREA: 36.3096
 DIMENSIONS OVER BRAIDING: 10.5 x 8 (APPROXIMATELY)
 RESISTANCE: 0.000467 ohm/m AT 15.5°C

SERIES REACTOR:-
 1. (a) 1.76mH (ACTUAL VALUE) (b) 0.004574 ohm (CALCULATED) COPPER.
 2. (a) 1.76mH (ACTUAL VALUE) (b) 0.00741 ohm (CALCULATED) ALUMINIUM.

HARMONIC SHUNT	CONDENSER CAPACITY (µF)	No OF PAIRS OF COILS	MUTUAL INDUCTANCE (mH)		NUMBER OF TURNS		SPACING OF COILS "D" (mm)	APPROXIMATE LENGTH OF WINDING (m)	RESISTANCE OF SHUNT COILS (PER PAIR) DC ohms	REDUCTION FACTOR	HARMONIC (Volts.)			CURRENT (Amps.)		
			REQUIRED	CALCULATED	LARGE COIL LAYERS & TURNS	SMALL COIL LAYERS & TURNS					CONTINUOUS	30min.	1 min.	CONTINUOUS	30min.	1 min.
6th	1 x 100	1	2.814	2.826	9 + 7	88	95	111	0.0518		205	217	305	61.8	65.4	91.9
12th	3 x 20	1	1.173	1.189	6 + 2	56	115	70	0.0327		104	154	158	15.68	23.2	23.8
18th	1 x 20	1	1.564	1.557	7 + 4	67	115	78	0.0364		66.2	91.2	116	6.85	9.17	11.65
24th	1 x 10	1	1.759	1.769	7 + 7	70	115	85	0.0430		50.5	63	38	3.81	4.75	6.64

NOTES

- 12th and 24th SHUNT COIL TURNS ALTERED TO SUIT 60 AND 10µF CONDENSERS RESPECTIVELY.
- ALL COILS TO BE WOUND IN 6 POSITIONS WITH 6 TURNS OF MASON LINE AND VARNISHED.
- VALUE OF ASSOCIATED CONDENSER TO BE CLEARLY STENCILLED ON BOTH COILS.
- BOTH COILS WOUND IN THE SAME DIRECTION AND CONNECTED AS SHOWN BY ARROWS.
- WIRE TO BE WOUND ON FLAT i.e. WITH 10.5 SIDE TOWARDS COIL AXIS.
- FOR ALTERNATIVE WIRE AND "AS WOUND" DETAILS SEE DRG NO BBB3487 (HARMONIC FILTER COILS).

© COPYRIGHT PROTECTED

DIMENSIONS : mm SCALE : NTS
 TOLERANCE : LINA - ANG± ITEM NO : -
 MATERIAL : -
 VERSION INFO : REDRAWN, DRG NO WAS ENW E1C-367 SHT 1

DO REF : CDO/2193
 ECP REF : 2002-072
 DRAWN : JR Anthony
 DESIGNED : -
 CHECKED : JD van Dyk

DATE:

--- APPROVED ---
 --- AUTHORISED ---

CENTRAL DRAWING OFFICE

INDUCTANCE COILS FOR RESONANT SHUNT CIRCUITS
 3KV DC TRACTION SUBSTATION



BBB3486
 VERSION 1

A3

"PREVIEW COPY ONLY"

PARTICULARS OF WIRE	HARMONIC	MUTUAL INDUCTANCE (mH)	NUMBER OF TURNS			APPROXIMATE LENGTH OF WINDING (m)	MUTUAL INDUCTANCE OF MASTER COILS AT MAX. AND MIN. SPACING. (mH)
			LARGE COIL		SMALL COIL		
			LAYERS & TURNS	TOTAL	LAYERS & TURNS		
DIMENSIONS OVER BRAIDING: 10,5mm x 8mm APPROXIMATE. 37/1.1176 DOUBLE BRAIDED.	6th	2.814	10 + 2	92	7 + 1	29	Max. 2.630 Min. 3.010
	12th	1.173	5 + 8	53	7 + 1	29	Max. 1.090 Min. 1.270
	18th	1.564	7 + 1	64	7 + 1	29	Max. 1.440 Min. 1.680
	24th	1.759	7 + 7	70	7 + 1	29	Max. 1.650 Min. 1.890
DIMENSIONS OVER BRAIDING: 10,5mm x 8mm APPROXIMATE.	6th	2.814	10 + 1	91	7 + 1	29	Max. 2.645 Min. 3.018
	12th	1.173	5 + 7	52	7 + 1	29	Max. 1.080 Min. 1.250
	18th	1.564	7 + 1	64	7 + 1	29	Max. 1.460 Min. 1.700
	24th	1.759	7 + 5	68	7 + 1	29	Max. 1.650 Min. 1.889

NOTES
 1. MASTER COIL INDUCTANCES:
 THE MUTUAL INDUCTANCES OF THE MASTER COILS WERE MEASURED WITH THE COILS ASSEMBLED IN CHEEKS ETC. AND MOUNTED ON THE STANDARD RACK.
 2. FOR CALCULATED WINDING DETAILS SEE DRG NO BBB3486 (INDUCTANCE COILS FOR RESONANT SHUNT CIRCUITS).



© COPYRIGHT PROTECTED

DIMENSIONS : mm
 TOLERANCE : LIN ± . ANG ± -
 MATERIAL :
 VERSION INFO : REDRAWN, DRG NO WAS ENW E1C-367 SHT 2

DO REF : CDO/2193
 ECP REF : 2002-072
 DRAWN : JR Anthony
 DESIGNED :
 CHECKED : JD van Dyk

DATE:
 - - - - APPROVED - - - -
 - - - - AUTHORIZED - - - -

CENTRAL DRAWING OFFICE

HARMONIC FILTER COIL WINDING DETAILS (AS WOUND)
 3kV DC TRACTION SUBSTATION

SPOORNET
 BBB3487
 VERSION 1

A3



**TECHNOLOGY MANAGEMENT.
SPECIFICATION.**

**TRANSNET FREIGHT RAIL'S REQUIREMENTS FOR THE
INSTALLATION OF ELECTRICAL EQUIPMENT FOR 3kV DC
TRACTION SUBSTATIONS**

Author	Chief Engineering Technician Technology Management	B.L. Ngobeni
Approved:	Senior Engineer Technology Management	L.O. Borchard
Authorised:	Principal Engineer Technology Management	W. A. Coetzee

Date: 06th October 2011

Circulation Restricted To:

Transnet Freight Rail – Chief Engineer Infrastructure
- Technology Management

© This document as a whole is protected by copyright. The information herein is the sole property of Transnet Ltd. It may not be used, disclosed or reproduced in part or in whole in any manner whatsoever, except with the written permission of and in a manner permitted by the proprietors.

INDEX

SECTION	CONTENTS	PAGE
	<u>SECTION 1: SUBSTATION DESIGN INFORMATION</u>	
1.0	SCOPE	4
2.0	STANDARDS, PUBLICATIONS AND DRAWINGS	4
3.0	TENDERING PROCEDURE	5
4.0	SERVICE CONDITIONS	5
5.0	ELECTRICAL SERVICE CONDITIONS	5
6.0	GENERAL REQUIREMENTS	6
7.0	GENERAL DESIGN OF EQUIPMENT	6
8.0	INSULATION AND CLEARANCE	6
9.0	OUTDOOR CLEARANCES AND INSULATION LEVELS	7
	<u>SECTION 2: TRACTION SUBSTATION EQUIPMENT</u>	
	<u>OUTDOOR EQUIPMENT</u>	
10.0	METAL OXIDE SURGE ARRESTERS	8
11.0	HIGH VOLTAGE AC DISCONNECTOR	9
12.0	HIGH VOLTAGE PRIMARY CIRCUIT BREAKERS	9
13.0	MAIN CURRENT TRANSFORMERS	9
14.0	MAIN TRACTION TRANSFORMER	9
15.0	AUXILIARY TRANSFORMER	9
16.0	AUXILIARY TRANSFORMER PROTECTION	10
17.0	AC EARTH LEAKAGE CURRENT TRANSFORMER	10
	<u>INDOOR EQUIPMENT</u>	
18.0	3kV RECTIFIER EQUIPMENT	10
19.0	3kV DC REACTOR	11
20.0	WAVE FILTER EQUIPMENT	11
21.0	POSITIVE ISOLATOR	12
22.0	CONTROL PANELS	12
23.0	BATTERY	12
24.0	BATTERY CHARGER	12
25.0	TRACK FEEDER HIGH SPEED CIRCUIT BREAKERS	12
26.0	MODULAR TYPE, STEEL HOUSED HIGH SPEED CIRCUIT BREAKERS	13
27.0	REGENERATIVE HIGH SPEED CIRCUIT BREAKER	13
28.0	3kV DC UNDERVOLTAGE RELAY	13
	<u>SECTION 3: INSTALLATION</u>	
	SUBSTATION EARTHING	14
29.0	INDOOR EARTHING	14
30.0	OUTDOOR EARTHING	14
31.0	INTERLOCKING	15
32.0	ISOLATING PROCEDURE	15
33.0	INDOOR CABLING, BUSBARS AND ASSOCIATED EQUIPMENT	16

34.0	CABLES, BUSBARS AND CONNECTIONS (OUTDOOR)	17
35.0	LABELS AND TERMINALS	18
36.0	SUBSTATION NEGATIVE RETURN	19
37.0	3KV DC POSITIVE FEEDER CABLES	20
38.0	TRENCHING FOR OUTDOOR YARD EARTHING CONDUCTORS AND CONTROL CABLES	20
39.0	FOUNDATIONS	21
40.0	SUPPORT STRUCTURES	21
41.0	FENCING	22
42.0	GATES	22
43.0	CRUSHER STONE AND WEED KILLER	23
44.0	PAINTING	23
45.0	DISTRIBUTION AND LIGHTING OF SUBSTATION BUILDING	23
46.0	COOLING AND VENTILATION	24
47.0	BATTERY ROOM	24
48.0	CLEARING OF SITE	24
	<u>SECTION 4: SITE TESTS AND COMMISSIONING</u>	
49.0	SITE TEST AND COMMISSIONING	24
	<u>SECTION 5: GENERAL</u>	
50.0	QUALITY ASSURANCE	26
51.0	GUARANTEE AND DEFECTS	26
52.0	DRAWINGS, INSTRUCTION MANUALS AND SPARES LISTS	26
53.0	SPECIAL TOOLS AND SERVICING AIDS	26
54.0	TRAINING	26
55.0	PACKAGING AND TRANSPORT	26
	APPENDIX 1: LIST OF RELEVANT DRAWINGS	27

SECTION 1: SUBSTATION DESIGN INFORMATION

1.0 SCOPE

- 1.1 This specification covers Transnet Freight Rail's requirements for the installation of electrical equipment in 3kV DC traction substations.
- 1.2 This specification should be read with the Scope of Work specification for each site/project and the applicable equipment specifications.
- 1.3 This specification also covers the requirements for the supply of security fencing, preparation of the High Voltage (HV) outdoor yard and the erection of all structural steelwork.

2.0 STANDARDS, PUBLICATIONS AND DRAWINGS

Unless otherwise specified this specification must be read in conjunction with the current edition of the relevant SANS, BS and Transnet Freight Rail's specifications.

2.1 SOUTH AFRICAN NATIONAL STANDARDS (SANS)

SANS 121:	Hot dip galvanized coatings for fabricated iron or steel articles. Specifications and test methods.
SANS 156:	Moulded-case Circuit Breakers.
SANS 780:	Distribution Transformers.
SANS 1019:	Standard voltages, currents and insulation levels for electricity supply.
SANS 1091:	National Colour Standard.
SANS 1222:	Enclosures for Electrical Equipment.
SANS 1339:	Cross-Linked Polyethylene (XLPE) - Insulated Electric cables for rated voltages (3,8/6,6kV to 19/33kV)
SANS 1431:	Weldable structural steels.
SANS 1507:	Electric cables with extruded solid dielectric insulation for fixed installations. (300/500V to 1900/3,300V) Part 1
SANS 10142-1:	The wiring of premises. Part 1
SANS 60044-1:	Instrument Transformers Part 1. Current Transformers.

2.2 TRANSNET FREIGHT RAIL SPECIFICATIONS/ ENGINEERING INSTRUCTIONS

CEE.0023:	Laying of cables.
CEE.0045:	Painting of steel components of electrical equipment.
CEE.0099:	Specification for 3kV DC high speed circuit breakers for traction substations.
CEE.0224:	Drawings, catalogues, instruction manuals and spares lists for electrical equipment supplied under contract.
CEE.0227:	The manufacture of 3kV DC breaker cells and trucks.
BBB 0496:	3kV rectifier for traction substations.
BBB 0845:	Requirements for metal oxide surge arresters in accordance with SANS 60099-4.
BBB 1267:	Specification for Outdoor High Voltage Alternating Current Circuit Breaker in Accordance with SANS 62271-100.
BBB 1616:	450 Volt gas arrester spark gap for traction power supplies.

BBB 2502:	Requirements for battery charger for 3kV DC traction substations.
BBB 2721:	AC primary circuit breaker control panel and AC/DC distribution panel for 3kV traction substation.
BBB 3005:	3kV DC under voltage relay manufacturing specification.
BBB 3139:	Wave filter capacitors for 3kV DC traction substations.
BBB 3162:	Wave filter inductors for 3 kV DC traction substations.
BBB 3890:	Requirements for 1.8 milli Henry DC reactor for 3kV DC traction substations.
BBB 5019:	Requirements for traction transformers for 3kV DC traction substations in accordance with BS 171 and IEC 60076-1.
BBB 7842	Outdoor, High Voltage, Alternating Current Disconnectors combined with earthing switch.
BBC 0198:	Requirements for the supply of cables.
BBC 0330:	Isolation transformer.

2.3 STATUTORY REQUIREMENTS

Occupational Health and Safety Act and Regulations, Act 85,1993

3.0 TENDERING PROCEDURE

- 3.1 Tenderers shall indicate clause-by-clause compliance with the specification as well as the relevant equipment specifications. This shall take the form of a separate document listing all the specifications clause numbers indicating the individual statement of compliance or non-compliance.
- 3.2 The tenderer shall motivate a statement of non-compliance.
- 3.3 Tenderers shall submit descriptive literature consisting of detailed technical specifications, general constructional details and principal dimensions, together with clear illustrations of the equipment offered.
- 3.4 Failure to comply with clauses 3.1, 3.2, and 3.3 could preclude a tender from consideration.

4.0 SERVICE CONDITIONS

The equipment shall be designed and rated for installation and continuous operation under the following conditions:

Altitude:	0 to 1800m above sea level.
Ambient temperature:	-5°C to +45 °C.
Relative humidity:	10% to 90%
Lightning Conditions:	12 ground flashes per square kilometre per annum.
Pollution sources.	Heavily salt laden or polluted with smoke from industrial sources.

5.0 ELECTRICAL SERVICE CONDITIONS

- 5.1 The incoming AC voltage can vary $\pm 5\%$ of the nominal system r.m.s voltage. Under crippled conditions the supply voltage can drop to as low as minus 15% of the nominal r.m.s voltage.
- 5.2 Frequency of the supply voltage is 50 ± 2.5 Hz.
- 5.3 The AC high voltage system shall be treated as effectively earthed unless otherwise specified.
- 5.4 The traction DC supply voltage is 3,15 kV DC nominal but can vary between 2,4kV and 3,9kV for sustained periods.
- 5.5 The 3kV DC equipment may be subjected to fault currents up to 30kA for 200 milli seconds.

6.0 GENERAL REQUIREMENTS

- 6.1 Equipment/Installations supplied shall be in terms of this specification. Deviations from the specification will not be allowed without the written consent of the Project Manager/Engineer.
- 6.2 Transnet Freight Rail reserves the right to subject material and equipment offered to test or inspection to verify compliance with the clauses of this specification, prior to adjudication or at any stage during manufacture.
- 6.3 The tenderer shall submit the layout drawings of equipment, electrical wiring schematics, and constructional designs to Transnet Freight Rail for design review.
- 6.4 The successful tenderer will be responsible for all costs caused by modifying or replacing equipment accepted by Transnet Freight Rail on the grounds of his statement of compliance and found by Transnet Freight Rail not to comply.
- 6.5 All equipment shall be adequately earthed, insulated, enclosed and interlocked to ensure the safety of staff as well as equipment.
- 6.6 The general design and layout of all equipment shall provide for easy access to all parts.
- 6.7 The equipment shall be installed in such a manner so as to limit fire damage, which may be caused by equipment failure, overheating or flashovers.
- 6.8 The substation control and protection circuits shall be designed and wired according to the fail-safe principle. Control equipment, contactors and relays shall de-energise under fault, power failure or alarm (flag) conditions.
- 6.9 No high voltage cables shall be laid in the same trench or duct as low voltage cables.

7.0 GENERAL DESIGN OF EQUIPMENT

- 7.1 This section covers substation equipment with electrical capacities between 3,0 MW and 6,0 MW.
- 7.2 The overload ratings of the rectifier units shall be:
- 2 times full load for thirty minutes.
 - 3 times full load for one minute.
 - 3 ½ times full load for ten seconds.
- 7.3 The substation can either be a single unit or double unit substation. Each unit comprises of one set of high voltage AC switchgear, one rectifier transformer, and one rectifier assembly, connected for 6 or 12 pulse operation and protected by a AC primary circuit breaker.
- 7.4 For a double unit substation each unit shall have the overload rating as specified in clause 7.2.
- 7.5 Each substation unit shall be capable of operating independently to allow for maintenance, fault finding and servicing of the equipment.

8.0 INSULATION AND CLEARANCES FOR 3kV DC EQUIPMENT

- 8.1 All indoor equipment, which may be energised at a potential of more than 1,0kV shall be protected by, metal barriers, mesh type screens or panels.
- 8.2 The minimum clearance in air between the rectifier unit and any metal barriers, mesh type screens or panels shall not be less than 450mm.
- 8.3 All exposed electrical equipment and busbars connected between the rectifier transformer secondary and the rectifier cubicle(s), or between the rectifier cubicle(s), positive isolators, DC smoothing equipment or track breakers, which is at a potential above 1,0kV, shall be arranged so that there is a minimum clearance of 2,7 m from the lowest "live" high voltage connections and ground or the floor of the access way, unless suitably screened, or otherwise protected.
- 8.4 All nominal 1,5kV and 3kV insulation to earth shall be designed such that the complete rectifier assembly, when installed on site ready for commissioning, will successfully withstand a test voltage of 10,5kV, 50 Hz AC for one minute.

- 8.5 Where the equipment or subassemblies of the rectifier assembly is enclosed and insulated from the outer framework, the insulation between the equipment and outer framework shall withstand the test voltage of 10,5kV 50 Hz for one minute.
- 8.6 The clearance between the reactor and any metal frame shall not be less 100mm. The reactor must successfully withstand a test voltage of 10,5kV AC 50 Hz for one minute
- 8.7 The successful tenderer shall advise what precautions must be taken before undertaking the withstand insulation level voltage tests to avoid damage to the equipment.
- 8.8 Creepage distance of insulation and the required air clearances shall be as large as possible. The latter shall not be less than:
- Outdoors: 150mm between the transformer secondary busbars and any steelwork such as wall plates, screening etc.
 - Indoors: 100mm between the equipment at nominal 1,5kV or 3kV DC and negative busbars and panel steelwork, between the high voltage AC supply to the rectifier cubicles and panel steelwork, the equipment at nominal 3kV DC and negative busbars.

9.0 OUTDOOR CLEARANCES AND INSULATION LEVELS

- 9.1 The minimum safety outdoor earth clearances which shall be maintained between any live conductor or metal and earthed metal and the minimum clearances of power lines above ground are in accordance with the statutory requirements of clause 15.1 of the "Electrical Machinery Regulations" of the "Occupational Health and Safety Act and Regulations, Act 85,1993", and are tabled below: -

TABLE 1:

Highest phase-to-phase r.m.s voltage for equipment. (U_m)	24kV	36kV	48kV	72kV	100kV	145kV
Nominal system r.m.s. voltage. (U_n)	22kV	33kV	44kV	66kV	88kV	132kV
Minimum safety outdoor clearance	320mm	430mm	540mm	770mm	1000mm	1450mm
Minimum clearance of power lines above ground						
Outside security fence but within Transnet Freight Rail's reserve	5200mm	5300mm	5400mm	5700mm	5900mm	6300mm
Outside Transnet Freight Rail's reserve	5500mm	5500mm	5500mm	5700mm	5900mm	6300mm

- 9.2 In terms of Transnet Freight Rail's Electrical Safety Instructions the clearances between the nearest exposed electrical equipment and a restricted access way are tabled below: -

TABLE 2:

Highest phase-to-phase r.m.s voltage for equipment. (U_m)	24kV	36kV	48kV	72.5kV	100kV	145kV
Nominal system r.m.s. voltage. (U_n)	22kV	33kV	44kV	66kV	88kV	132kV
Restricted access way (Vertical height) *	2820mm	2930mm	3040mm	3270mm	3500mm	3950mm

*See clause 903.1.3 of "Transnet Freight Rail's Electrical Safety Instructions"

(The vertical heights in restricted access ways for the various system voltages are calculated by adding 2,5metres to the normal outdoor earth clearance for the different system voltages. Refer to Annexure 9.4 of Transnet Freight Rail's Electrical safety Instructions).

INSULATION LEVELS

- 9.2 For the medium and high voltage nominal r.m.s voltage systems on Transnet Freight Rail the recommended Insulation levels in accordance with SANS 1019 is tabled in table 3.

TABLE 3

Highest phase-to-phase r.m.s voltage for equipment. (U_m)	Nominal system r.m.s. voltage. (U_n)	Rated lightning impulse withstand voltage peak.	Rated short duration power- frequency withstand r.m.s voltage.
7,2 kV	6,6 kV	75 kV	22 kV
12 kV	11 kV	95 kV	28 kV
24 kV	22 kV	150kV	50 kV
36 kV	33 kV	200 kV	70 kV
52 kV	44 kV	250 kV	95 kV
72,5 kV	66 kV	350 kV	140 kV
100 kV	88kV	380 kV 450 kV	150 kV 185 kV
145 kV	132 kV	550 kV 650 kV	230 kV 275 kV
245 kV	220 kV	850 kV 950 kV	360 kV 395 kV
Insulation levels for highest voltage for equipment $U_m < 100$ kV are based on an earth fault factor equal to $\sqrt{3}$ and for $U_m > 100$ kV an earth fault factor equal to $0,8\sqrt{3}$. Where more than one insulation level is given per voltage system, the higher level is appropriate for equipment where the earth fault factor is greater than 1,4.			

TABLE 3: Standard Voltages and insulation levels in accordance with SANS 1019:2008 [1]

SECTION 2: TRACTION SUBSTATION EQUIPMENT

OUTDOOR YARD EQUIPMENT

10.0 METAL OXIDE SURGE ARRESTERS

- 10.1 The contractor shall supply and install metal oxide gapless surge arresters in accordance with Transnet Freight Rail's specification BBB 0845.
- 10.2 The surge arresters shall be connected between each phase of the high voltage supply and substation main earth electrode/earth mat
- 10.3 The maximum protected distance from the main transformer bushing terminal to the surge arrester terminal shall be as indicated in table 4.

TABLE 4:

NOMINAL SYSTEM R.M.S VOLTAGE (kV)	MAXIMUM DISTANCE (Metres)
44kV	5
66kV	6
88kV	6
132kV	7

- 10.4 The neutrals of high voltage supplies are to be treated as effectively earthed unless otherwise specified.
- 10.5 For the installation of high voltage surge arresters on the main transformer, refer to Transnet Freight Rail's drawing BBB 0938
- 11.0 HIGH VOLTAGE AC DISCONNECTOR**
- The contractor shall supply and install the high voltage AC disconnecting switch in accordance with Transnet Freight Rail's specification BBB 7842.
- 12.0 HIGH VOLTAGE PRIMARY CIRCUIT BREAKER**
- The contractor shall supply and install the high voltage AC primary circuit breaker in accordance with Transnet Freight Rail's specification BBB 1267.
- 13.0 MAIN CURRENT TRANSFORMERS**
- 13.1 The main current transformers shall comply with the requirements of Transnet Freight Rail specification BBB 0937.
- 13.2 The main current transformers shall either be fitted in the high voltage bushings of the main traction transformer or shall be the freestanding post type current transformers install on the line side of the main traction transformer.
- 13.3 In the event of Eskom or Local Utility requiring three current transformers for metering purposes the successful contractor shall supply and install the additional current transformer.
- 13.4 The ratios, accuracy and burdens of the current transformers shall be in accordance with Transnet Freight Rail's Specification BBB 0937.as specified:
- 14.0 MAIN TRACTION TRANSFORMER**
- 14.1 The contractor shall be responsible for the delivery, assembling, filling of transformer oil and installation on site of the main traction transformer in accordance with Transnet Freight Rail's Specification BBB 5019.
- 15.0 AUXILIARY TRANSFORMER**
- 15.1 The contractor shall make provision for the supply of an auxiliary transformer which shall comply with the requirements of SANS.780
- 15.1.1 The auxiliary transformer shall be three phase with a minimum rating of 50kVA or higher depending on the substation requirements.
- 15.1.2 The 3 phase auxiliary transformer shall be supplied from the tertiary winding of the main traction transformer
- 15.1.3 The auxiliary transformer shall be the sealed unit type suitable for outdoor installation. Full details of the transformer shall be submitted.

- 15.2 In the case of a double unit substation one auxiliary transformer may be provided unless otherwise specified.
- 15.3 The secondary winding of the auxiliary transformer shall be star-connected.
- 15.4 The auxiliary transformer shall supply the required kVA rating without exceeding the permissible temperature rise laid down in SANS 780.
- 15.5 The nominal no-load secondary voltage of the auxiliary transformer shall be 400V three phase.
- 15.6 Off-load, externally operated tap changing gear shall be provided on the transformer, with tapplings to compensate for any change in the main transformer tapping.
- 15.7 All primary and secondary terminals, including the secondary neutral, shall be brought out through the transformer tank by means of bushing type terminals and shall be arranged for busbar/cable connections.

16.0 AUXILIARY TRANSFORMER PROTECTION

PRIMARY WINDING

- 16.1 The contractor shall make provision for overload protection of the primary winding. Refer to clause 8.8 of specification No BBB 2721.
- 16.2 The protection system shall consist of an approved type of overload relay with its associated current transformers.

16.3 SECONDARY WINDING

- 16.4 The contractor shall supply and install a three phase isolating and earthing switch for the secondary supply of the auxiliary transformer to the substation.
- 16.5 The isolating and earthing switch shall be fitted with mechanical interlocking of the key exchange type, which shall form part of the interlocking procedure for the substation. Refer to clauses 31.0 and 32.0 of this specification.

17.0 AC EARTH LEAKAGE CURRENT TRANSFORMER.

- 17.1 The contractor shall supply and install a bar primary current transformer for the AC earth leakage protection. The current transformer shall be installed on the support steel structure of the primary circuit breaker.
- 17.2 One terminal of the primary winding shall be connected to the primary circuit breaker frame and the other terminal shall be connected to the substation main earth electrode/mat. (Refer to drawing CEE-TBD-7 and BBB 3620).
- 17.3 The current transformer shall be class 10P10, ratio 50/5 or 100/5.
- 17.4 The current transformer shall be designed to withstand a test voltage of 2kV for 1 minute.

INDOOR EQUIPMENT

18.0 3kV DC RECTIFIER

- 18.1 The contractor shall supply and install 3kV DC rectifiers in accordance with Transnet Freight Rail's Specification BBB 0496.
- 18.2 Each rectifier unit and its associated control equipment shall be designed to form an independent unit.
- 18.3 The rectifier equipment shall be installed in screened bays fitted with gates.
- 18.4 The gates shall be fitted with mechanical interlocks of the key exchange type in accordance with clauses 31 and 32 of the specification.
- 18.5 The bay screens shall be constructed of approximately 25mm woven wire mesh or expanded metal fixed to tubular or angle iron frames complete with doors, pillars, gates etc.

- 18.6 The height of the screens and gates shall be similar to the height of the control panels but shall be not be less than 1,8 m.
- 18.7 In a double unit substation the rectifier units are referred to as the "A" and "B" units and shall be labelled as such.
- 18.8 It is required that each rectifier unit in a double unit substation can be isolated independently and earthed without shutting down the whole substation.
- 18.9 Individual rectifier units shall be screened from each other and from any other live common equipment. A mechanical key exchange interlocking system type in accordance with clauses 31 and 32 shall be fitted to ensure the safety of personnel working on the isolated rectifier equipment.
- 18.10 The rectifier units and bay screens shall be insulated from the floor.

19.0 3kV DC REACTOR

- 19.1 The contractor shall supply and install a 1.8 milli Henry 3kV DC air core reactor for each rectifier unit. The installation shall include the supply of all the required insulators, foundations, foundation bolts and fasteners.
- 19.2 The 3kV DC reactor shall be in accordance with Transnet Freight Rail's Specification BBB 3890.
- 19.3 The reactor shall be insulated from the substation floor by means of insulators.
- 19.4 Sufficient space shall be allowed for access to the reactor for maintenance and inspection purposes.

20.0 WAVE FILTER

- 20.1 The contractor shall supply and install the wave filter equipment in accordance with Transnet Freight Rail's specification BBB 3139 for wave filter capacitors and BBB 3162 for inductor coils.
- 20.2 A wave filter is connected in parallel with the rectifier output. The filter unit is a capacitive inductive circuit, which is tuned to resonate at specific harmonic frequencies.
- 20.3 The filter equipment shall be so designed that no individual harmonic voltage is greater than 2% of the output voltage.
- 20.4 The inductor coils shall have sufficient adjustment to compensate for change in the capacitance values due to ageing. Refer to Transnet Freight Rail's drawing BBB 3483 for assembly.
- 20.5 A 100 Ampere High Rupturing Capacity (H.R.C) fuse shall be fitted to protect the wave filter equipment.
- 20.6 The fuse holder shall be mounted on insulators.
- 20.7 The insulators shall be so designed that the flashover path is not less than 100mm and shall support the fuse at a distance of not less than 100mm from the bolts securing the base plate. The insulators shall have a minimum dry flashover value of 20kV.
- 20.8 Access to the wave filter equipment shall only be possible once the wave filter capacitors have been connected to rail, discharged and the primary circuit breaker tripped.
A 75 kilo Ohm resistor consisting of two 150 Kilo Ohm, 150 watt vitreous enamel resistors connected in parallel shall be provided for the discharging of the wave filter capacitors when the equipment is isolated and earthed.
- 20.9 The discharge resistors shall be mounted on a suitable insulation panel or bar, which shall be insulated for 3kV DC. A minimum clearance of 75mm must be provided between the terminals, and 100mm between any 3kV live portion of the equipment and earth.
- 20.10 The wave filter capacitors shall be earthed with 95mm² PVC insulated copper cables to the DC earth leakage system.
- 20.11 The wave filter equipment shall be housed in a separate explosion proof room or cubicle.

21.0 3kV DC POSITIVE ISOLATOR

21.1 The contractor shall supply and install the 3kV DC positive isolator in accordance with Transnet Freight Rail's specification BBB 4724.

21.2 The DC positive isolator metal cubicle/housing shall be insulated from the substation floor.

22.0 CONTROL PANELS

22.1 The contractor shall supply and install the AC primary circuit breaker control panel and the AC/DC distribution panel in accordance with Transnet Freight Rail's specification BBB 2721.

22.2 The control panels shall be insulated from the substation floor.

ELECTRONIC EQUIPMENT

22.3 The tenderer must be aware that high voltage surges and transient voltages can be induced in low voltage and control wiring due to switching and lightning. Special care shall be taken in the design and layout of the equipment to limit these voltages.

22.4 Electronic equipment shall suitably be protected against over voltages, surges and transients. Dehn type surge protection units or equivalent shall be used. Liberal use of metal oxide varistors is also encouraged.

23.0 BATTERIES

23.1 The contractor shall supply, install and commission a 53 cell 110 Volt Planté lead acid battery bank. The capacity of the battery can either be 100 Ampere hour rating, 200 Ampere hour rating or capacity dependant on the substation requirements. The standard for the batteries shall be the 10-hour rate at 20°C. The battery shall be capable of delivering a minimum of 10 Amperes for 10 hours.

23.2 Batteries are installed in traction substations for control and protection purposes. The battery is used for the following functions:

- Tripping and closing of primary circuit breakers.
- Supply to protection relays.
- Closing and holding coil supply to DC high speed circuit breakers.
- 110 Volt supply to control panel.

24.0 BATTERY CHARGER.

24.1 The contractor shall supply and install the battery charger in accordance with Transnet Freight Rail's specification BBB 2502.

24.2 The battery charger shall be insulated from the substation floor by means of "Marley" or "Lino" floor covering not less than 2mm thickness.

25.0 TRACK FEEDER HIGH SPEED CIRCUIT BREAKERS

25.1 The successful tenderer shall supply and install the required 3kV DC high speed circuit breakers in accordance with Transnet Freight Rail's specification CEE.0099 as well as with the following additional requirements:

25.2 The high-speed circuit breakers shall be of the conventional truck mounted type as commonly used by Transnet Freight Rail in the 3kV DC traction substations.

25.3 High-speed circuit breakers shall be fitted with an automatic reclosing feature, which provides for 1 (one) reclosure at 20 to 35 seconds interval. Refer to drawings CEE-TBP-35. "Connection diagram for the high speed circuit breaker and electronic control relay". CEE-TBP-39."Circuit diagram for auto reclosure for the high speed circuit breaker.

25.4 Transnet Freight Rail shall provide the auto reclosure relays. The relays shall be wired by the contractor in accordance with the requirements of clause 25.3.

- 25.5 The high speed circuit breakers shall be complete in all respects. This shall include housings, rack out trucks, base rails, main and auxiliary contacts and flapper gear and any other fittings or equipment required for the correct operation of the high-speed circuit breakers.
- 25.6 The high-speed circuit breakers shall be racked into breaker cells, each having two fixed contacts mounted at the rear of the breaker cell. One contact is connected to the substation positive busbar and the other to a wall bushing mounted in the building outer wall.
- 25.7 All other items of material such as cell slabs, main busbars, earthing connections, wall bushing plates or blanking-off plates, control cables etc, shall be included in the tenderer's offer.
- 25.8 Transnet Freight Rail shall provide details of the wall plate frame and standard cell slabs where applicable.
- 25.9 Where access is possible to the rear of the high-speed circuit breakers (busbar chamber) access barriers shall be installed.
- 25.9.1 The barriers shall be fixed to angle iron frames with fasteners which only be removed with tools. Warning signs shall be fitted to the barriers.
- 26.0 MODULAR TYPE STEEL HOUSED HIGH SPEED CIRCUIT BREAKERS**
- 26.1 Where tenderers offer modular type high-speed circuit breakers they shall submit full information, construction and dimensional drawings with their offer.
- 26.2 Transnet Freight Rail specification CEE.0227 shall be used as a guideline.
- 26.3 The tenderers must be fully aware that the requirements of Transnet Freight Rail's specification CEE.0099 are relevant.
- 26.4 Transnet Freight Rail reserves the right to accept or reject offers for equipment after consultation with tenderers. Transnet Freight Rail's Senior Engineer, Technology Management, shall approve all designs.
- 26.5 The modular type steel housings shall be insulated from the substation floor.
- 27.0 REGENERATIVE HIGH SPEED CIRCUIT BREAKER**
- 27.1 At certain substations Transnet Freight Rail will require 3kV DC regenerative braking energy absorption equipment. If required the successful contractor shall supply the high speed circuit breaker for the protection of the regenerative braking equipment in accordance with Transnet Freight Rail's specification CEE.0099.
- 28.0 3kV DC UNDERVOLTAGE RELAY**
- 28.1 The contractor shall supply and install a 3kV DC undervoltage relay with a high voltage potential divider in accordance with Transnet Freight Rail Specification BBB 3005 and shall provide the following:
- 28.2 Fibre optic technology must be used to provide galvanic isolation between the potential divider and the undervoltage relay.
- 28.3 The potential divider shall be mounted in the 3kV busbar chamber or in the high voltage compartment of the positive isolator cubicle in accordance with Transnet Freight Rail's Specification BBB 4724.
- 28.4 The potential divider shall be protected by an H.R.C fuse connected between the positive side of the 3kV DC supply and the input of the potential divider.
- 28.5 Insulation clearance shall be not less than 100mm. All normally live equipment on the potential divider shall withstand a test voltage of 10,5kV AC RMS 50 Hz for one minute to earth without breakdown.

- 28.6 If the undervoltage relay is wall mounted, an engraved warning label shall be fixed to the front of the undervoltage relay panel with the following warning:

WARNING

THE POSITIVE BUSBAR MUST BE ISOLATED AND EARTHED BEFORE WORK IS UNDERTAKEN ON THE UNDERVOLTAGE RELAY

- 28.7 The following connections shall consist of 95mm² cross-sectional area copper or copper equivalent conductors.
- Potential divider to negative busbar.
 - Resistor base plate to DC earth leakage busbar.
 - Relay metal case to DC earth leakage busbar.

SECTION 3: INSTALLATION

SUBSTATION EARTHING

29.0 INDOOR EARTHING (REFER TO DRAWING CEE-TBD-0007)

The successful contractor shall supply, install and comply with the following:

- 29.1. The supply and installation in the substation building of all earthing conductors for the earthing of all metal work which includes supporting frames, control panels, battery charger, positive isolator panel, track breaker cells, rectifier bay screens, chequer plates and metal bases of insulators mounted directly on the walls or floor etc.
- 29.2. The frames and bases of all items associated with the 3kV DC including the track feeder wall plates, shall be connected through the DC earth leakage relay to the negative busbar in accordance with Transnet Freight Rail's drawing CEE-TBD-0007.
- 29.3. The DC earth leakage relay and the installation thereof shall comply with the requirements specified in clause 8.6 of Transnet Freight Rail's specification BBB2721.
- 29.4. Earthing conductors which could be subjected to 3 kV DC faults caused by insulation breakdown, etc., shall be not less than 70mm² copper strap cross-sectional area or 95mm cross-sectional area PVC insulated stranded copper cable. Other earth conductors must have a minimum of 16mm² copper cross-sectional area.
- 29.5. The earthing system for the 3kV DC positive busbar chamber shall be supplied by the successful tenderer. The design of the system shall be in conjunction with Transnet Freight Rail staff.
- 29.6. The successful tenderer shall supply the portable earthing device and cables according to Transnet Freight Rail's requirements.
- 29.7. All connections to the DC earth leakage relay shall form part of a ring circuit for safety when part of the circuit is disconnected. Refer to drawing CEE-TBD-0007.
- 29.8. The earth conductors shall not be installed in such a manner as to bridge out the earth leakage relay.
- 29.9. The resistance between the DC earth leakage busbar and the substation main earth electrode/mat shall be not less than 25 ohms.
- 29.10. Holding-down bolts grouted in the floor shall not be in direct contact with reinforcing or in with the earth under the concrete floor in the substation.
- 29.11. Where mounting bolts are used for securing electrical equipment to the floor, these bolts must be insulated to prevent electrical contact with any reinforcing or floor.
- 29.11.1 The indoor substation equipment shall be earthed in groups as shown in Transnet Freight Rail's drawing CEE-TBD-0007.

30.0 OUTDOOR EARTHING (DRAWING NO CEE-TBD-7 AND BBB 3620)

The successful tenderer shall supply, install and comply with the following:

- 30.1 Outdoor yard earthing which includes earth spikes, trench earths, earth connections to the support steel structures and fence posts. The material used shall comply with Transnet Freight Rail's specification BBB 3059 and drawing BBB3620.
- 30.2 A rail-earth switch mounted on the gate that provides access to the outdoor yard and where applicable to the 3kV DC overhead feeder security area and provide all connections thereto.
- 30.3 In Transnet Freight Rail switchyards where the supply from the Electrical Utility is terminated on portal structures or where a flying busbar is provided the contractor shall earth these structures.
- 30.3.1 Install two 50mm² galvanised steel earth conductors, one each between the outside portal structure or flying busbar support and the gable of the substation building.
- 30.3.2 The earth conductor shall be suitably terminated and connected to the portal or flying busbar structures. A suitable bracket shall be supplied and mounted on the gable of the substation building. The earth conductors shall directly be terminated on the bracket and connected to the main earth electrode/mat.
- Insulating of structures and electrical equipment.**
- 30.3.3 The tenderer shall make provision for the insulating of the support steel structures for i.e. the primary circuit breaker, main current transformers and any other structure that is connected to the AC earth leakage system from the concrete foundation.
- 30.3.3.1 The insulating material shall be either the same material used for the insulating of the mast bases for the overhead track equipment or other insulating material that has been approved by Technology Management.
- 30.4. The tenderer shall make provision for the insulating of the base of the main traction transformer from the concrete plinth. Malthoid or any other approved insulation shall be used.

31.0 INTERLOCKING (mechanical)**GENERAL**

- 31.1 The equipment for each substation shall include a mechanical interlocking system; preferably the "Castell" or other approved key type. Full details of the type offered instead of the "Castell" type shall be submitted with the tender.
- 31.2 The mechanical interlocking system must be designed to prevent access to the high voltage equipment whilst "live" and ensure that switching and isolating operations are carried out in the correct sequence.
- 31.3 All equipment shall be delivered with the necessary interlocks fitted.
- 31.4 It shall not be possible to operate the locks and release the keys in any but the correct sequence or in any position of the switches or gates, other than the fully "closed" or fully "open" position, as the case may be.
- 31.5 When a unit is switched to local condition and isolated, no remote switching from the control office shall be possible. Tenderers shall furnish full explanatory details of the arrangement whereby the foregoing provisions are met.
- 31.6 The track feeder breakers shall remain closed throughout the isolation procedure.

32.0 ISOLATING PROCEDURE

Sequence to isolate a single unit substation rectifier unit.

- 32.1 Trip high voltage AC circuit breaker.
- 32.2 Open high voltage AC disconnecting switch-key "1" released.
- 32.3 Remove key "1"- AC disconnecting switch locked in open and earthed position.

- 32.4 Use key "1" to operate auxiliary supply's three phase isolating and earthing switch - key "1" trapped - key "2" released.
- 32.5 Use key "2" to unlock DC positive isolating and earthing switch.
- 32.6 Open DC positive isolating and earthing - key "2" trapped - key "3" released. Remove key "3". DC positive isolating and earthing switch locked in open position.
- 32.7 Use key "3" to open rectifier unit bay gate (and DC smoothing reactor screen if required).
- 32.8 If a number of keys are required to open the rectifier cubicles, a key exchange system may be used.
- 32.9 Procedure is reversed to switch the rectifier unit back on load.
- 32.10 The number indicated for the keys are for single unit substations only. Where there are two units in one substation the numbers of keys for the two units shall be A1 and B1, A2, and B2, etc. It shall not be possible to exchange keys between any equipment on different units.
- 32.11 The foregoing sequence is given as a guide and may be altered to suit tenderer's equipment. The design shall be approved by Transnet Freight Rail.
- 32.12 Where the wave filter equipment is not located in the rectifier bay, the access to the equipment shall be mechanically interlocked and form part of the interlocking procedure.
- 32.13 Access to the wave filter shall only be possible once the positive isolator is earthed and the primary circuit breaker is tripped. Refer to clause 20.8
- 32.14 Any deviation from the above guideline must be approved by Transnet Freight Rail.

33.0 INDOOR CABLING, BUSBARS AND ASSOCIATED EQUIPMENT

The contractor shall supply and install the following:

- 33.1 All low voltage PVC insulated supply and control cables.
- 33.2 3kV DC copper cables and copper busbars from the Anode wall plate to the rectifier and from the rectifier equipment to the DC positive isolating switches, DC smoothing reactors, and main DC negative busbar. In the event of aluminium (grade 6063) being used the minimum size shall be 50mm X 25mm busbar.
- 33.3 Where required, the supply and fitting of hot dip galvanised anode wall plates in the wall of the substation building, at the rectifier bays. The wall plate galvanising shall comply with SANS 121.
- 33.3.1 Wall plates shall be fitted with wall bushings, one for each phase and the neutral.
- 33.3.2 Designs and drawings of the wall plate arrangement must be submitted for approval after adjudication of the tender.
- 33.4 The interconnecting busbars from the anode wall plate to the rectifier.
- 33.5 The main 3kV DC positive and negative copper busbars. Minimum dimension of busbars shall be 100mm X 10mm copper or 127mm X 12,5mm aluminium (grade 6063) busbar.
- 33.6 The 3kV DC output positive busbar system, which includes high-speed circuit breaker busbars, and where required the outgoing feeder cables between the high speed circuit breaker busbars and wall bushings.
- 33.7 Barriers in accordance with clause 8.0 where exposed busbars exist between the positive isolator and the DC track breaker positive, busbar.
- 33.8 Cables from the DC smoothing reactor or main positive busbar to the wave-filter equipment.
- 33.9 Control cables from the rectifier cubicles to their respective control panels.
- 33.10 Cables from the auxiliary equipment to the substation control panels.
- 33.11 Connections and cabling between control panels.

- 33.12 Cables between the 110V substation battery and the auxiliary DC panel (2 core, minimum 16mm²).
- 33.13 Cables (95mm² stranded copper) to the wave-filter room(s) for rail (negative) and DC earth leakage connections to wave-filter equipment.
- 33.14 Earthing cables (95mm² stranded copper) between the DC earth leakage busbar and substation negative busbar.
- 33.15 Two core 16mm² and multicore 2,5mm² cables between panel and high-speed 3kV DC circuit breakers.
- 33.16 Two core 6mm² cables between the 25A circuit breakers on the DC panel and the Electrical Supply Utility meter room. Make-off and connect at the DC panel only.
- 33.17 All other busbars and cables required for the interconnection of the substation indoor equipment.
- 33.18 Cable glands for the termination of the cables at the control panels and other equipment. Neoprene shrouds shall be fitted over the cable glands.
- 33.19 The maximum current density per square mm for open conductors shall not exceed 1.55 Ampere for copper and 1.0 Ampere for aluminium.
- 33.20 Low voltage cables for indoor use may be unarmoured.
- 33.21 All high voltage cables shall be armoured XLPE insulated and shall comply with SANS 1339 and Transnet Freight Rail specification BBC 0198. All wiring used on the 3kV DC equipment shall have nominal 3kV insulation unless the clearances comply with those laid down in clause 8.9.
- 33.22 All negative connections and terminals associated with high voltage circuits and which are accessible without first having to isolate and earth such high voltage circuits e.g. the main negative busbar, DC earth leakage relay, etc., shall be of 95mm², copper or copper equivalent cross-section. The terminals shall be painted red.
- 33.23 Notwithstanding the above clauses the contractor shall supply and install any other cables, conductors or busbars required for the successful operation of the substation.
- 33.24.0 BLOCK JOINTS**
- 33.24.1 The contractor shall make block joints in the armouring of all the low voltage supply and control cables, which are connected between the indoor control equipment and the outdoor yard equipment.
- 33.24.2 The block joints shall be clearly visible and shall be not less than 200mm from the cable glands terminating at the outdoor equipment.
- 33.24.3 The block joints shall be sealed with a heat shrink covering to prevent the ingress of moisture.
- 33.25.0 CHEQUER PLATES**
- 33.25.1 The contractor shall be responsible for the supply of all metal chequer plates required for covering of cable trenches inside the substation.
- 33.25.2 Earthing studs suitable for the fitting of 95mm² copper cable shall be welded to each chequer plate.
- 34.0 CABLES, BUSBARS AND CONNECTIONS. (OUTDOOR)**
- The Contractor shall supply and install the following:
- 34.1 The Inter-connections cables or conductors in the High Voltage yard.
- 34.2 The high voltage AC connections which shall be solderless, concentric grip, or other approved solderless type. The connections must have adequate cross-sectional area to suit both electrical and mechanical requirements.
- 34.3 Copper busbars between separately mounted outdoor equipment. The busbars shall incorporate a degree of flexibility to avoid any overstressing of connections due to foundation movement and expansion or contraction.

- 34.4 All negative connections and terminals associated with high voltage circuits and which are accessible without first having to isolate and earth such high voltage circuits e.g. the main negative busbar shall be of 95mm², copper or copper equivalent cross-section. The terminals shall be painted red.
- 34.5 Copper busbars with removable flexible connections or "all aluminium" stranded conductor may be used interconnection conductors between the main traction transformer secondary bushings and the anode wall bushings which are fixed to the anode wall plate of the substation building.
- 34.5.1 Where "all aluminium conductors are to be installed the following sizes and number of conductors shall be installed:
- 2 X 800 mm² "all aluminium" stranded conductor per each phase for 4,5 MW substations, or 50mm X 25mm aluminium (grade 6063) busbar in accordance to Transnet freight rail drawing BBF1615.
 - 2 X 500 mm² "all aluminium" stranded conductor per each phase for 3 MW substations, or 50mm X 25mm aluminium (grade 6063) busbar in accordance to Transnet freight rail drawing BBF1615.
- 34.5.2 Where two different conductor material joints are used, the Bi-Metallic plates shall be applied.
- 34.6 Conductors from the high voltage AC line aerial conductors and between the surge arresters, AC disconnecting switch, high voltage AC circuit breaker, current transformers, rectifier transformer and rectifier.
- 34.7 Cables or busbars from the rectifier transformer to the auxiliary transformer.
- 34.7.1 The auxiliary transformer shall be connected directly to the tertiary winding of the traction transformer for new installations or existing installations where tertiary windings are employed on the main traction transformer.
- 34.8 Cable from the auxiliary transformer secondary to the short-circuiting switch.
- 34.9 Control cables from the high voltage AC disconnecter, AC circuit breaker and main and auxiliary transformers to the substation control panels.
- 34.10 A multi-core 4mm² cable between the current transformers and the Electrical Supply Utility meter room. Make-off and connect at the current transformer only.
- 34.11 In the case of the Electrical Supply Utility Tee-supplies a multi-core 4mm² cable between the voltage transformers and the Electrical Supply Utility. The Electrical Supply Utility will do the cable connection.
- 34.12 In the case of the Electrical Supply Utility Duplicate Supplies one multi-core 4mm² cable between Transnet Freight Rail's high voltage AC circuit breaker and the Electrical Supply Utility meter room. (For interlocking Electrical Supply Utility M.O.D's). The cable shall have 10% spare cores.
- 34.13 A multi-core 2,5mm² cable between the tele-control remote terminals on the control panel and the electrical supply utility meter room. (For tele-control of the Electrical Supply Utility equipment). The cable shall have 10% spare cores.
- 34.14 All other cables as specified. e.g. security lighting and alarms.
- 34.15 All control cables, security and alarm cables shall be armoured cables.
- 34.16 Notwithstanding the clauses above the contractor shall be responsible for all cables, busbars and connections required for the successful operation of the 3kV DC traction substation.
- 35.0 LABELS AND TERMINALS**
- 35.1 All labels shall be in English. All lettering shall be white on a black background. Lettering shall be a minimum of 6mm in height.
- 35.2 All labels shall be neatly secured by rivets or screws.
- 35.3 All conductors and cables shall be provided with identification tags at terminals.

35.4 All terminals and equipment such as switches and relays shall be suitably numbered according to the substation schematic and wiring diagrams. All terminal blocks and groups of terminal blocks shall be suitably numbered.

36.0 SUBSTATION NEGATIVE RETURN

The substation negative return system which can be in the form of the following:

- Buried XLPE insulated copper cable.
- Rail on sleepers.
- Aerial conductors.

36.1 BURIED XLPE INSULATED COPPER CABLE

36.1.1 The contractor shall install 2 x 500mm² single core XLPE copper cables from the substation negative busbar to the negative manhole situated near the railway line.

36.1.2 Transnet Freight Rail's staff will undertake the provision of the bare conductors from the negative manhole to track, as well as the rail connections.

36.1.3 The negative manhole to drawing CEE-TU-41 is to be supplied and installed by the contractor.

36.1.4 The negative return cables shall be laid, in 150mm of soft soil in a trench, at a depth of not less than 1000mm below ground level and spaced not less than 300mm between centres.

36.1.5 Where cables are likely to be damaged they shall be protected by concrete slabs. Refer to Transnet Freight Rail specification CEE.0023.

36.1.6 The cable route shall be provided with cable warning tape. Refer to Transnet Freight Rail specification CEE.0023.

36.1.7 The cable runs shall be marked by cable markers painted signal red. (Stores Item No 9/1503)

36.2 RAIL NEGATIVE RETURN.

36.2.1 Where rail is used for the negative return system Transnet Freight Rail shall supply and install the rail from the inside of the substation building to the railway track.

36.2.2 The rail shall be insulated from ground by means of concrete sleepers supplied by Transnet Freight Rail.

36.2.3 Where the rail enters the substation building it must be insulated from all concrete and brickwork to prevent stray current damage to building reinforcing or other metal. After installation the hole in the wall shall be sealed and made good by Transnet Freight Rail.

36.2.4 The rail shall be connected to negative output of the rectifier by means of a suitably rated busbar/cable supplied by the contractor. Transnet Freight Rail will make provision for terminations on the rail.

36.2.5 Transnet Freight Rail shall connect the negative return rail to the track by means of PVC insulated steel conductors.

36.3 NEGATIVE FEEDER MONITORING SYSTEM.

36.3.1 The contractor shall design supply and install a negative feeder monitoring system in accordance with Transnet Freight Rail specification BBB1843.

36.3.2 The negative feeder monitoring system shall be designed to trip the 3 kV DC track breakers in the event of the traction substation negative return circuit becoming open circuited due to cable theft of the negative return cables or other cause of failure of the negative return circuit.

36.4 AERIAL CONDUCTORS

36.3.1 Where aerial conductors are used for the negative return, the contractor shall provide the wall plates and wall bushings where required.

36.3.2 In the case of aerial conductors used for the negative return, Transnet Freight Rail shall provide the conductors and the installation.

37.0 3kV DC POSITIVE FEEDER CABLES

The positive feeder cables shall be either:

- Buried armoured medium voltage XLPE insulated cable.
- Aerial aluminium conductor

37.1 BURIED XLPE INSULATED CABLE

37.1.1 The contractor shall install two single core 6,6kV, 500mm² armoured medium voltage XLPE insulated cables with stranded copper conductors. The cables shall be manufactured with copper tape screen, armour and sheath in accordance with SANS 1339 and Transnet Freight Rail specification BBC 0198. The cables shall run from the high-speed circuit breaker busbar chamber to the associated track switch structure.

37.1.2 Tenderers are to allow for making off the cables with suitable terminations. Sufficient length of cable must be left buried at the base of the track switch structure for erection and connection to the track switch. Transnet Freight Rail will do connection to the track switch.

37.1.3 The medium voltage cables shall be laid in 150mm of soft soil, in a trench at a depth of not less than 1000mm below ground level and spaced not less than 300mm between centres.

37.1.4 Where cables are likely to be damaged they shall be protected by concrete slabs. Refer to Transnet Freight Rail specification CEE.0023.

37.1.5 The cable route shall be provided with cable warning tape. Refer to Transnet Freight Rail specification CEE.0023.

37.1.6 The cable runs shall be marked by cable markers painted white (Stores Item No 9/1539).

37.1.7 Should it be necessary for the cables to pass under the tracks suitable pipes will be installed by Transnet Freight Rail.

37.1.8 Where required, the contractor shall supply the necessary wall bushings for positive feeder cables.

37.2 AERIAL CONDUCTOR

37.2.1 In the case of aerial conductors used for the positive feeders, Transnet Freight Rail shall make provision for conductors and installation.

37.2.2 Where aerial conductors are used for the 3kV DC positive, the contractor shall provide the wall plates and wall bushings.

38.0 TRENCHING FOR OUTDOOR YARD EARTHING CONDUCTORS AND CONTROL CABLES.

38.1 Before any trenching commences the contractor shall consult with Transnet Freight Rail staff for approval of the routing of the trenches in the outdoor yard.

38.2 In existing substation outdoor yards the contractor shall remove the necessary crusher stone in the outdoor yard before any excavation commences. The contractor shall restore the crusher stone after the completion of the work.

38.3 Trenching includes all trenches required for the installation of the earthing system and control cables.

38.4 The depth of trenches shall not be less than 700 millimetres.

38.5 With the installation of new earthing conductors and control cables at existing substations, care must be taken not to damage existing cables in the high voltage outdoor yard during trenching operations.

38.6 The Contractor and Transnet Freight Rail staff shall inspect the trenches before and during the installation of the earthing system and control cables.

38.7 Before the trenches are closed a representative from Transnet Freight Rail shall inspect the earthing system and other cabling for damage.

39.0 FOUNDATIONS.

39.1 The successful tenderer shall be responsible for the design and casting of foundations for the portal and support structures in the traction substation high voltage outdoor yard.

39.2 Notwithstanding the supply arrangements (single or double) at any particular substation, tenderers shall clearly understand that all foundations and steelwork to accommodate the supply and to cater for the traction yard are to be provided and erected by the successful tenderer.

39.3 Wherever there is a combined traction and 11kV/6,6kV distribution yard, a flying busbar is to be provided in Transnet Freight Rail's yard. All foundations and steelworks required to suit this arrangement, including the erection and earthing thereof shall be included in tenderer's offers.

39.4 The foundations in the high voltage outdoor yard shall include the following:

- Voltage Transformers if applicable.
- Surge arresters.
- AC disconnectors.
- Current transformers. (If applicable)
- Primary circuit breakers.
- Main traction transformer.
- Auxiliary transformers.
- Portal lattice structures as required.
- Any other foundations as specified.

39.5 The successful tenderer shall carry out his own survey in regard to soil types and their load bearing capabilities.

39.6 Equipment support foundations shall be finished off 200mm above the finished earth level of the yard. The design must be such as to prevent standing water.

39.7 All foundation edges shall be bevelled, and the surfaces must be float finished.

39.8 All support foundations shall be at the same level.

39.9 The design of the concrete plinth for the main traction transformer shall include a concrete gutter around the perimeter of the plinth to contain any spillage of transformer oil.

39.10 Provision shall be made on the plinth for skid rails. The spacing of the rails between centres shall be a minimum of 1meter. Details of the design and load bearing parameters of the skid rail system, plinth and rail shall be submitted to Transnet Freight Rail for approval.

39.11 The auxiliary transformer if separate shall be provided with its own concrete plinth with a concrete gutter, or may be installed on the same plinth as the main traction transformer.

39.12 The 28-day strength of all concrete used shall be a minimum of 20Mpa.

39.13 Hand mixed concrete is not acceptable, it must be mechanically mixed.

40.0 SUPPORT STRUCTURES

40.1 The design, supply and installation of all steel structures for the support of equipment and tensioning of conductors shall be the responsibility of the successful tenderer.

40.2 Special attention shall be taken for the prevention of corrosion of all metallic parts.

- 40.3 The bases of insulators, studs, bolts, support structures and other parts made of ferrous material associated with the electrical connections outdoors, shall be hot-dip galvanised, in accordance with SANS 121.
- 40.4 Steelwork for outdoor installation in coastal areas, i.e., within 50km of the coast, shall first be hot-dip galvanised in accordance with SANS 121, followed immediately at the galvanising plant by the application of the Sterling paint system in accordance with specification CEE.0045.
- 40.5 Steelwork for outdoor installation in inland areas, i.e., at a distance greater than 50km from the coast, shall be hot-dip galvanised to SANS 121.
- 40.6 All high voltage equipment shall be provided with hot-dipped galvanised support structures or pedestals to provide a minimum clearance of 3,6 m (up to 88kV) or 4,1 m (above 88kV) from the lowest "live" high voltage connection to finished ground level.
- 40.7 Structural steel shall comply with SANS 1431.
- 40.8 All welded joints shall be seal welded with no gaps or blowholes.
- 40.9 All fasteners, nuts and bolts used for the installation of substation steelwork and equipment shall be hot dipped galvanised to prevent corrosion.
- 41.0 FENCING**
- 41.1 The successful tenderer shall supply and install new perimeter fencing as specified.
- 41.2 The successful tenderer shall make provision for the levelling of outdoor yard if required.
- 41.3 The fencing shall be either of the following:
- Concrete palisade fencing in accordance to drawing CEE-TDF- 0016.
 - Hot dipped galvanised steel palisade fencing with the minimum requirements of:
Height 2,4 metres
Size and thickness of pales 40mm x 40mm x 3mm thick.
Corner and intermediate posts 100mm x100mm x 3mm.
Horizontal cross bars 40mmx5mm.
- 41.3.1 The successful tenderer shall make provision for the installation of safety barriers in the high voltage yard in accordance with Transnet Freight Rail's requirements. (Refer to Transnet Freight Rail's Engineering instruction S.016)
- 41.3.2 The successful tenderer shall make provision for a metal barrier screen of 25mm-wire mesh or expanded metal to be constructed around the auxiliary transformer to prevent accidental contact.
- 41.3.3 The successful tenderer shall cast a concrete apron of 150mm wide x 300mm under the perimeter fences of the substation. The top of the apron shall be a minimum of 100 mm above the ground level.
- 42.0 GATES**
- 42.1 The contractor shall supply and install two 4.6 metre wide X 2,4 metres minimum height lockable gates in the perimeter fence to allow for:
- Entrance to substation building and yard.
 - Entrance to the high voltage outdoor yard adjacent to the main transformer (s).
- 42.2 Where access to the HV outdoor yard is gained between the substation building and perimeter fence, a fence the same height as the perimeter fence shall be installed. A 1000mm wide lockable gate shall form part of the fence.
- 42.3 Provision must be made for the fitting of a spark gaps and rail earth switch on the HV yard small gate. Refer to drawings CEE-TBD-7 and BBB3620. The spark gaps shall be provided by Transnet Freight Rail on request.

42.4 Where steel palisade fencing is used the gates shall be connected to the fence support post by means of a flexible connection to prevent electrolytic corrosion of gate hinges.

42.5 Warning notices and danger signs in accordance with Transnet Freight Rail's Electrical Safety Instructions shall be fitted to the perimeter fencing and gates. This shall be provided by Transnet Freight Rail.

43.0 CRUSHER STONE AND WEED KILLER

43.1 After completion of construction, installation of equipment, the laying of all cables and earthing conductors, a suitable weed killer approved by the Technical Officer shall be applied in HV outdoor yard.

43.2 Great care shall be exercised to avoid contaminating private property and water supplies.

43.3 After treatment with the weed killer, a 100mm layer of 25mm crusher stone shall be laid over the whole area of the Transnet Freight Rail high voltage outdoor yard (within the apron).

44.0 PAINTING

44.1 All indoor and outdoor steelwork, metal screens and barriers shall be painted in accordance with Transnet Freight Rail's Specification CEE.0045.

44.2 The finishing coats for indoor equipment shall be in accordance with SANS 1091.

Metal Bay Screens - Eau-de-Nil (H43).

Support frameworks (indoor) - Eau-de-Nil (H43).

45.0 DISTRIBUTION, LIGHTING OF SUBSTATION BUILDING AND STANDBY 400V AUXILIARY SUPPLIES

45.1 The successful tenderer shall supply and install all light fittings, plugs, conduits, distribution boards, switches, cables and other material in accordance with SANS 10142-1. Galvanised, alternatively PVC conduit and galvanised fittings shall be provided at all substations within 50km of the coast.

45.2 The contractor shall furnish a certificate of compliance for the 400V/220V AC distribution and lighting of the traction substation signed by the accredited person in terms of SANS 10142-1 and who is registered with "Electrical Contracting Board".

45.3 Complete Layout drawing showing the position/type of light fittings, position of plugs, distribution board and switches to be submitted to Transnet Freight Rail for approval.

45.4 220V AC fluorescent light fittings shall provided. The minimum lighting requirement shall be 100 lux in terms of the "Occupational Health and Safety Act".

11KV/6,6KV TO 400V AUXILIARY SUPPLY AND CHANGE OVER SYSTEM.

45.5 Where specified a 11kV/6,6kV to 400V distribution transformer will be installed to supply the traction substation in the event of substation failure or when the substation is taken off load.

45.5.1 The 3 phase 400V supply from the above transformer shall be connected to the control circuitry via a automatic change over switching system.

45.5.2 The change over switching system shall be mechanically and electrically interlocked.

45.5.3 Transnet Freight Rail shall supply and install a suitably rated 4core armoured cable from the 11kV/6,6kV to 400V distribution transformer to the change over switching unit.

45.5.4 A 1:1 ratio isolation transformer shall be installed between the 11kV/6.6kV to 400V distribution transformer and change over switching system.

45.5.5 The isolation transformer shall comply with specification BBC 0330.

45.5.6 The successful tenderer shall supply the isolation transformer unless otherwise specified.

EMERGENCY LIGHTING.

45.6 Fluorescent light fittings with its own battery back up supply shall be supplied for emergency lighting.

- 45.6.1 A minimum of three fittings shall be installed in a single unit substation and four in a double unit substation.
- 45.6.2 The light fittings shall be installed at the following locations:
- In single unit substations two in the main walkway between the control panels and rectifier unit. One flameproof fitting in the battery room
 - In a double unit substation three in the main walkway and one flameproof fitting in the battery room.
 - In additional locations where requested by the Project Manager/Engineer.
- 45.6.3 The light switch shall be clearly labelled " EMERGENCY LIGHTNING".

MOULDED CASE CIRCUIT BREAKERS

- 45.7 All low voltage circuits and equipment shall be protected by moulded case circuit breakers, which comply with specification SANS 156.

SECURITY LIGHTS

- 45.8 Where outdoor security lights are specified 400W high-pressure sodium fittings shall be installed at locations specified by the "Scope of Work".

46.0 COOLING AND VENTILATION

- 46.1 Where specified, 3 phase cooling fans shall be supplied and installed in the substation building.
- 46.2 The required filters, louvres and guards shall be provided and installed.

47.0 BATTERY ROOM

- 47.1 A three/single phase non-sparking extraction fan shall be installed for the battery room.
- 47.2 Only Ex non-sparking light fittings shall be installed in the battery room.
- 47.3 Light switches and plug sockets shall not be installed in the battery room.
- 47.4 No-smoking, naked flames and hand protection warning signs shall be fitted to the battery room doors.
- 47.5 A wooden stand treated with acid proof paint shall be provided for the batteries.
- 47.6 A hydrometer and logbook shall be supplied by the contractor for each installation.
- 47.7 The floor of the battery room shall be painted with acid proof paint.

48.0 CLEARING OF SITE

- 48.1 All rubble which is left over as a direct result of work performed by the Contractor shall be removed from the substation building and yard and disposed of by the Contractor. The substation floors and walls shall be left in a clean condition. All cable, wire and conductor cut-offs and surplus material shall be removed from site.

SECTION 4: SITE TESTING AND COMMISSIONING

49.0 SITE TESTS AND COMMISSIONING

The successful tenderer shall be responsible for carrying out on-site tests and commissioning of all equipment supplied and installed in terms of this specification and the contractual agreement.

49.1 ON-SITE TESTS

- 49.1.1 Functional on-site tests shall be conducted on all items of equipment, circuitry and interlocking to prove the proper functioning and installation thereof.

- 49.1.2 The successful tenderer shall submit a detailed list of on-site tests for the approval of the Project Manager/Engineer at least six weeks before tests are due to commence at the first substation.
- 49.1.3 The successful tenderer shall arrange for the Project Manager/Engineer or his representative to be present to witness the on-site tests at each substation.
- 49.1.4 On-site tests and subsequent commissioning shall not commence until all construction work has been completed. Construction staff, material and equipment shall be removed from site prior to the commencement of testing. Testing and commissioning of the substation equipment will not be allowed to take place in a construction site environment.
- 49.1.5 On-site tests shall include the following;
- Polarity tests on all CT's.
 - Ratio tests on all CT's.
 - Magnetising current of all CT's.
 - Secondary injection of all relays.
 - Trip testing, all relays must be checked for correct operation.
 - The functionality of all electrical circuitry must be tested.
 - The operation of both mechanical and electrical interlocking.
 - Tests on primary circuit breakers and other primary equipment in accordance with manufacturer's instructions.
- 49.1.6 At the completion of the on-site tests the Project Manager/Engineer or his representative, shall either sign the test sheets (supplied by the successful tenderer) as having witnessed the satisfactory completion thereof, or hand to the successful tenderer a list of defects requiring rectification.
- 49.1.7 Upon rectification of defects the successful tenderer shall arrange for the Project manager/Engineer or his representative to certify satisfactory completion of on-site tests for that particular substation.
- 49.1.8 Acceptance by the Project Manager/Engineer of satisfactory completion of on-site tests in no way relieves the contractor of his obligation to rectify defects which may have been overlooked or become evident at a later stage.
- 49.2 COMMISSIONING OF EQUIPMENT**
- 49.2.1 Commissioning will include the energising of equipment from the AC disconnects to the OHTE track feeder switches. The successful tenderer must prove the satisfactory operation of all equipment under live conditions.
- 49.2.2 On completion of commissioning the successful tenderer will hand the substation over to the Project Manager/Engineer in terms of the relevant instructions.
- 49.2.3 Tenderers shall allow a period of at least three days per substation between satisfactory completion of on-site tests and commissioning of equipment.
- 49.2.4 During this period the Transnet Freight Rail's Test staff will test the operation of all protective relays and circuits and set the protection relays at each substation.
- 49.2.5 The contractor shall rectify any faults found during the testing and setting of the protection relays.
- 49.2.6 The final testing of the substation must commence at least three days ahead of the contract completion date.
- 49.2.7 The commissioning of the protection equipment by Transnet Freight Rail will in no way absolve the successful tenderer from any of his responsibilities during the guarantee period. It is the successful tenderers responsibility to satisfy himself that the commissioning of the protection equipment has been carried out in a satisfactory manner and in no way compromises the proper operation of the equipment supplied in terms of the contract.

- 49.2.8 The commissioning dates for the substations will be dependent on the availability of power supplies from the supply utility as well as Transnet Freight Rail's electrification program and will be defined by the Project Manager/Engineer.

SECTION 5: GENERAL

50.0 QUALITY ASSURANCE

- 50.1 Transnet Freight Rail reserves the right to carry out inspection and tests on the equipment at the works of the supplier/manufacturer.
- 50.2 Arrangements must be made timeously for such inspections and type/routine tests in accordance with the equipment specifications are carried out before delivery of the equipment to the site.
- 50.3 Type/routine test sheets of the equipment shall be forwarded to the Project Manager.

51.0 GUARANTEE AND DEFECTS

- 51.1 The contractor shall guarantee the satisfactory operation of the complete electrical installation supplied and installed by him and accept liability for maker's defects, which may appear in design, materials and workmanship.
- 51.2 The guarantee period shall commence from the date of successful commissioning of the substation.
- 51.3 The guarantee period for all substations shall expire after a period of 12 months commencing from the date of successful completion of the contract or the date the equipment is handed over to Transnet Freight Rail whichever is the later.
- 51.4 If urgent repairs have to be carried out by Transnet Freight Rail staff to maintain supply during the guarantee period the contractor shall inspect such repairs to ensure that the guarantee period is not affected and should they be covered by the guarantee, reimburse Transnet Freight Rail the cost of material and labour.
- 51.5 The cost of training shall be included in the tenderers quotation.

52.0 DRAWINGS, INSTRUCTION MANUALS AND SPARES LISTS

- 52.1 Drawings, instruction manuals and catalogues shall be supplied in accordance with Transnet Freight Rail specification CEE.0224.
- 52.2 The tenderer shall supply three copies of an instruction/maintenance manuals, schematic and wiring diagrams.
- 52.3 The contractor shall submit details of spares required in accordance with Transnet Freight Rail's specification no. CEE.0224.
- 52.4 All spares recommended for normal maintenance purposes that are not available locally (requires importation) must be highlighted.

53.0 SPECIAL TOOLS AND/OR SERVICING AIDS

Special tools or servicing aids necessary for the efficient maintenance, repair or calibration of the equipment shall be quoted for separately.

54.0 TRAINING

- 54.1 The contractor shall submit details with the tender of the training courses which will be conducted by the contractor for the training of Transnet Freight Rail maintenance staff in the operation and maintenance of the equipment supplied. The courses shall include theoretical as well as practical tuition. The date and venue of this training course shall be arranged with the Maintenance manager.

55.0 PACKAGING AND TRANSPORT.

- 55.1 The contractor shall ensure that the equipment be packed in such a manner that it will be protected during handling and transport.
- 55.2 The contractor shall provide transport for the delivery of the equipment to the site where required.


56.0 BIBLIOGRAPHY

- [1] SANS 1019: 2008 Edition 2.5 Standard voltages, currents and insulation levels for electricity supply

APPENDIX 1

DRAWINGS ISSUED WITH THIS SPECIFICATION

DRAWING NUMBER	AMENDMENT	DESCRIPTION.
CEE-TDF-0016		Concrete fencing
CEE-TBD-7		Earthing Arrangements Traction Substations.
CEE-TU-41		Negative Return Cable Terminating Box.
CEE-TCK-1		Reactor 1,84mH, 1 500 A. (For reference purposes only)
CEE-TBP-1		Wiring diagram for auto reclosure for HSCB.
CEE-TBP-39		Circuit diagram for auto reclosure for HSCB
CEE-TBP-35		Connection diagram for HSCB and electronic control relay
CEE-TBP-38		Schematic Diagram of 3kV HV Protection.
CEE-TCL-63		3kV Busbar Chamber Arrangement: Cable Feeders.
CEE-TCQ-208		DC High Speed Circuit Breaker Cell Panel (Cell slabs) (sheets 1 to 10)
CEE-TBP-33		DC Track Breaker and Truck Wiring Diagram.
BBB 0938		Surge arresters mounted on traction transformer.
BBB 3620		3kV Earthing arrangement for traction substation
BBF 1615		Busbar connection assembly



SPOORNET

A division of Transnet limited

**TECHNICAL
RAILWAY ENGINEERING**

SPECIFICATION CONTROL PAGE

**HOT DIP GALVANISING AND PAINTING OF
ELECTRIFICATION STEELWORK**

Statement of authorisation:


There is no SABS specification available for similar material / equipment and as far as can be ascertained no other specification / standard suitably covers Spoornet requirements. The specification has been compiled in a manner, which shall favour / encourage local manufacture of material/equipment to a maximum degree.

Author:	Chief Engineering Technician Configuration management	Jan C van Tonder
Approved:	Senior Technologist Railway Engineering	HA Slier
Authorised:	Senior Engineer Railway Engineering	L O Borchard

Two handwritten signatures are present. The top signature is for Jan C van Tonder and the bottom signature is for L O Borchard. Both signatures are written in black ink and are positioned above horizontal lines that serve as baselines for the signatures.

Date: January 2002

This page is for control purposes only and shall not be issued with the specification.



SPOORNET

A division of Transnet limited

**TECHNICAL
RAILWAY ENGINEERING**

SPECIFICATION

**HOT DIP GALVANISING AND PAINTING OF
ELECTRIFICATION STEELWORK**

Circulation restricted to:

Technical

© This document as a whole is protected by copyright. The information herein is the sole property of Transnet Ltd. It may not be used, disclosed or reproduced in part or in whole in any manner whatsoever, except with the written permission of and in a manner permitted by the proprietors.

INDEX

SECTION	CONTENTS	PAGE NO
1.0	SCOPE	3
2.0	REFERENCES	3
3.0	METHOD OF TENDERING	3
4.0	APPENDICES	3
5.0	GALVANISING OF STEELWORK	3
6.0	PRIMER COATING	3
7.0	TOP COATING	4
8.0	QUALITY	4
9.0	SUBSTITUTION	5

"PREVIEW COPY ONLY"

1.0 SCOPE

- 1.1 This specification covers the hot dipped galvanising and painting of electrification steelwork.
- 1.2 The extent of work includes galvanising and painting of steelwork consisting of universal column masts with welded on bases up to 14 m in length and small part steelwork consisting of channel, angle and flat iron fittings, welded assemblies and tubular cantilevers.

2.0 REFERENCES

- 2.1 The following publications (latest edition) are referred to herein:

SABS 763: Hot Dipped Galvanising.

SABS 1091: National Colour Standards for Paint.

3.0 METHOD OF TENDERING

- 3.1 Tenderers shall indicate clause by clause compliance or non-compliance with the specification. This shall take the form of a separate document listing all the specification clause numbers indicating the individual statement of compliance or non-compliance.
- 3.2 The Schedule of Requirements, Quantities and Prices, Appendix 1 to this specification shall be fully completed by Tenderers. Failure to submit a fully completed sheet may preclude a tender from further consideration.

4.0 APPENDICES

The following appendices form an integral part of this specification:

Appendix 1: Schedule of Requirements, Quantities and Prices.

5.0 GALVANISING OF STEELWORK

- 5.1 The steelwork must be cleaned and hot dip galvanised to SABS 763 except for the following:
- 5.1.1 No ammonium chloride salts shall be used on withdrawal from the molten zinc.
- 5.2 After galvanising no passivation must take place. Quenching may be done with clean water. No sodium dicromate must be used.
- 5.3 All surface contamination of zinc oxide (zinc ash) must be removed by means of brushing.

6.0 PRIMER COATING

- 6.1 The hot dip galvanising shall be followed as soon, as is practical by the painting procedures as specified hereunder:
- 6.1.1 Prior to painting, all steelwork shall be cleaned with a solvent cleaner and washed down with clean water to remove all traces of solvent. The solvent cleaner used must be compatible with zinc (similar to Galv Clean).
- 6.1.2 The primer coating, a two-component polyamide cured epoxy primer e.g.: PLASCOGUARD GEHOPPENS PRIMER or equivalent shall be applied to a dry film thickness of 75 microns. Application shall be in accordance with the manufacturers

instructions.

- 6.1.3 The primer coating shall be allowed to cure for a minimum period of 48 hours before handling to facilitate coating of the rest of the surfaces as well as the application of the intermediate coat.
- 6.1.4 A coat of a two-component high-build micaceous iron oxide pigmented polyamide cured re-coatable epoxy e.g.: SIGMACOVER CM MIOCOAT or equivalent shall be applied to a wet film thickness of 75-85 microns. Application shall be in accordance with manufacturers instructions.
- 6.1.5 A further 48 hours period must be allowed for curing of the primer coatings before handling the steelwork for transportation purposes.
- 6.2 All care must be exercised during handling to prevent damage of the painted surfaces.
- 6.3 Loading of steelwork must be done in such a way to limit damage of surfaces to a minimum during transit.
- 6.4 Only non-metallic slings should be used, preferably nylon or cotton material.
- 6.5 Spoornet reserves the right to inspect the premises where this work is carried out at any time during the duration of galvanising and primer painting.
- 6.6 Spoornet shall inspect all steelwork at the Tenderers premises before dispatch of any such steelwork.

7.0 TOP COATING

- 7.1 The topcoat shall be applied directly after erection of the steelwork in accordance with procedures hereunder:
- 7.1.1 Damage of the primed surfaces shall be repaired, after erection, by the application of one or more coats of a two component high build micaceous iron oxide pigmented polyamide cured re-coatable epoxy coating e.g.: SIGMACOVER CM MIOCOAT or equivalent until the original film thickness is obtained.
- 7.1.2 A topcoat of a two-component aliphatic isocyanate cured acrylic finish e.g.: SIGMADUR GLOSS or equivalent shall be applied according to the paint manufacturers instructions to a minimum dry film thickness of 50 microns. The topcoat shall be determined by whether steelwork is for Spoornet or the South African Rail Commuter Corporation.
- 7.1.2.1 For Spoornet the colour shall be French Grey (SABS 1091: Code H30).
- 7.1.2.2 For the South African Rail Commuter Corporation the colour shall be Medium Sea Grey (SABS 1091: Code G24).

8.0 QUALITY

- 8.1 The tenderer shall submit a copy of a Quality Plan to be implemented during the process. The Quality Plan shall include stages for preparation of metalwork prior to galvanising, for the galvanising and for the painting process.
- 8.2 The Quality Plan shall furthermore make provision for the customer's requirements for inspection and acceptance points and witnessing of tests to establish whether requirements of SABS 763 in so far as preparation of steelwork prior to galvanising, galvanising and painting requirements as per this specification are complied with.

9.0 SUBSTITUTION

7.1 This instruction replaces Specification CEE.0183.95.

7.2 All clauses have been revised to suit latest requirements e.g.: removal of the Complies/Does not complies reference.

END

TENDERER'S SIGNATURE: _____

DATE: _____

FOR SPOORNET: _____

GRADE: _____

"PREVIEW COPY ONLY"

SCHEDULE OF REQUIREMENTS, QUANTITIES AND PRICES

1.0

"PREVIEW COPY ONLY"

END

FOR SPOORNET: _____

GRADE: _____